

R-410A

Service Manual



RXYQ5-54PY1 R-410A Heat Pump 50Hz







VRVIII R-410A Heat Pump 50Hz

	1. Introduction	
	1.1 Safety Cautions	
	1.2 PREFACE	x
Part 1	General Information	1
	Model Names of Indoor/Outdoor Units	
	2. External Appearance	
	2.1 Indoor Units	
	3. Combination of Outdoor Units	
	Model Selection	
	4. Model Selection	/
Part 2	Specifications	11
	1. Specifications	12
	1.1 Outdoor Units	
	1.2 Indoor Units	33
Da4 2	Defeirement Circuit	5 0
Part 3	Refrigerant Circuit	59
	Refrigerant Circuit	
	1.1 RXYQ5P	
	1.2 RXYQ8P	
	1.3 RXYQ10P, 12P 1.4 RXYQ14P, 16P, 18P	
	1.5 Outdoor air processing unit FXMQ125MFV1~250MFV1	
	Functional Parts Layout	
	2.1 RXYQ5P	
	2.2 RXYQ8P	
	2.3 RXYQ10P, 12P (12P: EUROPE)	
	2.4 RXYQ12P	
	2.5 RXYQ14P, 16P, 18P	
	Refrigerant Flow for Each Operation Mode	74
Part 4	Function	91
	1. Function general	92
	1.1 Symbol	
	1.2 Operation Mode	
	2. Basic Control	94
	2.1 Normal Operation	94
	2.2 Compressor PI Control	
	2.3 Electronic Expansion Valve PI Control	
	2.4 Step Control of Outdoor Unit Fans	
	2.5 Outdoor Unit Fan Control in Cooling Operation	108

Table of Contents

i

		3.	Spe	cial Control	109
			3.1	Startup Control	
			3.2	Large capacity start up control (Heating)	
			3.3	Oil Return Operation	
			3.4	Defrosting Operation	
			3.5	Pump-down Residual Operation	
			3.6	Standby	
			3.7	Stopping Operation	116
		4.	Prot	ection Control	118
			4.1	High Pressure Protection Control	
			4.2	Low Pressure Protection Control	
			4.3	Discharge Pipe Protection Control	120
			4.4	Inverter Protection Control	
			4.5	STD Compressor Overload Protection	
			4.6	Injection Control (only for RXYQ5P)	
		5		er Control	
		٥.	5.1	Outdoor Unit Rotation	
			5.2	Emergency Operation	
			5.3	Demand Operation	
			5.4	Heating Operation Prohibition	
		^			
		о.		ine of Control (Indoor Unit)	
			6.1	Drain Pump Control	
			6.2	Louver Control for Preventing Ceiling Dirt	
			6.3	Thermostat Sensor in Remote Controller	
			6.4	Thermostat Control While in Normal Operation	
			6.5	Thermostat Control in Dry Operation	
			6.6	Electronic Expansion Valve Control	
			6.7	Hot Start Control (In Heating Operation Only)	
			6.8	Freeze Prevention	
			6.9	Heater Control	
				List of Swing Flap Operations	137
			6.11	Control of Outdoor Air Processing Unit	
				(Unique Control for Outdoor Air Processing Unit)	138
Part 5	Test	Op	era	ıtion	143
		4	Toot	Operation	111
		١.	1.1	Operation	
				Procedure and Outline	
		_		Operation When Power is Turned On	
		2.	Outo	door Unit PC Board Layout	160
		3.	Field	d Setting	161
			3.1	Field Setting from Remote Controller	161
			3.2	Field Setting from Outdoor Unit	174
Part 6	Trou	ble	sho	ooting	199
		1.	Sym	ptom-based Troubleshooting	201
		2.	Trou	ubleshooting by Remote Controller	
			2.1	The INSPECTION / TEST Button	
			2.2	Self-diagnosis by Wired Remote Controller	205
			2.3	Self-diagnosis by Wireless Remote Controller	
				-	

ii Table of Contents

	2.4	Operation of The Remote Controller's Inspection /	
		Test Operation Button	
	2.5	Remote Controller Service Mode	
	2.6	Remote Controller Self-Diagnosis Function	212
3.	Trou	bleshooting by Indication on the Remote Controller	220
	3.1	"RO" Indoor Unit: Error of External Protection Device	
	3.2	"Ri" Indoor Unit: PC Board Defect	221
	3.3	"83" Indoor Unit: Malfunction of Drain Level Control System (S1L)	222
	3.4	"R6" Indoor Unit: Fan Motor (M1F) Lock, Overload	
	3.5	"87" Indoor Unit: Malfunction of Swing Flap Motor (M1S)	
	3.6	"R9" Indoor Unit: Malfunction of Moving Part of	
		Electronic Expansion Valve (Y1E)	227
	3.7	"RF" Indoor Unit: Drain Level above Limit	
	3.8	"RJ" Indoor Unit: Malfunction of Capacity Determination Device	
	3.9	"E4" Indoor Unit: Malfunction of Thermistor (R2T)	
	0.0	for Heat Exchanger	231
	3.10	"£5" Indoor Unit: Malfunction of Thermistor (R3T) for Gas Pipes	
		"£9" Indoor Unit: Malfunction of Thermistor (R1T) for Suction Air	
		"LJ" Indoor Unit: Malfunction of Thermostat Sensor	200
	0.12	in Remote Controller	234
	3 13	"E?" Outdoor Unit: PC Board Defect	
		"E3" Outdoor Unit: Actuation of High Pressure Switch	
		"EY" Outdoor Unit: Actuation of Low Pressure Sensor	
		"E5" Outdoor Unit: Inverter Compressor Motor Lock	
		"E6" Outdoor Unit: STD Compressor Motor Overcurrent/Lock	
		"E7" Outdoor Unit: Malfunction of Outdoor Unit Fan Motor	
		"E3" Outdoor Unit: Malfunction of Moving Part of	240
	3.19	Electronic Expansion Valve (Y1E, Y2E)	246
	2 20		
		"F3" Outdoor Unit: Abnormal Discharge Pipe Temperature	
		"F5" Outdoor Unit: Refrigerant Overcharged	
		"HT" Outdoor Unit: Abnormal Outdoor Fan Motor Signal	
		"H3" Outdoor Unit: Malfunction of Thermistor (R1T) for Outdoor Air	
		"J2" Outdoor Unit: Current Sensor Malfunction	252
	3.25	"J3" Outdoor Unit: Malfunction of Discharge Pipe Thermistor	050
	0.00	(R3, R31~33T)	253
	3.26	"J5" Outdoor Unit: Malfunction of Thermistor (R2T), (R7T)	05.4
		for Suction Pipe	254
	3.27	"J6" Outdoor Unit: Malfunction of Thermistor (R4T) for	
		Outdoor Unit Heat Exchanger	
		"J7" Outdoor Unit: Malfunction of Liquid Pipe Thermistor (R6T)	256
	3.29	"J9" Outdoor Unit: Malfunction of Subcooling Heat Exchanger	
		Gas Pipe Thermistor (R5T)	
		"JR" Outdoor Unit: Malfunction of High Pressure Sensor	
		"JC" Outdoor Unit: Malfunction of Low Pressure Sensor	259
	3.32	"L4" Outdoor Unit: Malfunction of Inverter Radiating Fin	
		Temperature Rise	
		"L5" Outdoor Unit: Inverter Compressor Abnormal	
		"L8" Outdoor Unit: Inverter Current Abnormal	
		"L9" Outdoor Unit: Inverter Start up Error	266
	3.36	"LC" Outdoor Unit: Malfunction of Transmission Between Inverter	
		and Control PC Board	
	3.37	"Pi" Outdoor Unit: Inverter Over-Ripple Protection	271

Table of Contents iii

		3.38 "P4" Outdoor Unit: Malfunction of	
		Inverter Radiating Fin Temperature Rise Sensor	272
		3.39 "PJ" Outdoor Unit: Faulty Field Setting after Replacing Main PC Boa	
		or Faulty Combination of PC Board	
		3.40 "UO" Outdoor Unit: Low Pressure Drop Due to Refrigerant Shortage	
		or Electronic Expansion Valve Failure	275
		3.41 "Ut" Reverse Phase, Open Phase	
		3.42 "U2" Outdoor Unit: Power Supply Insufficient or	270
		Instantaneous Failure	277
		3.43 "U3" Outdoor Unit: Check Operation not Executed	
		3.44 "U4" Malfunction of Transmission Between Indoor Units	281
		3.45 "U5" Indoor Unit: Malfunction of Transmission Between	
		Remote Controller and Indoor Unit	283
		3.46 "U7" Indoor Unit: Malfunction of Transmission	
		Between Outdoor Units	284
		3.47 "UB" Indoor Unit: Malfunction of Transmission Between Main and	
		Sub Remote Controllers	286
		3.48 "US" Indoor Unit: Malfunction of Transmission Between Indoor	
		and Outdoor Units in the Same System	287
		3.49 "UR" Improper Combination of Indoor and Outdoor Units,	
		Indoor Units and Remote Controller	288
		3.50 "UC" Address Duplication of Centralized Controller	
		3.51 "UE" Malfunction of Transmission Between Centralized Controller	
		and Indoor Unit	291
		3.52 "UF" System is not Set yet	
		3.53 "UH" Malfunction of System, Refrigerant System Address Undefined	
	4		
	4.	Troubleshooting (OP: Central Remote Controller)	
		4.1 "fil" PC Board Defect	297
		4.2 "#8" Malfunction of Transmission Between Optional Controllers	000
		for Centralized Control	298
		4.3 "A" Improper Combination of Optional Controllers	
		for Centralized Control	
		4.4 "MC" Address Duplication, Improper Setting	
	5.	Troubleshooting (OP: Unified ON/OFF Controller)	305
		5.1 Operation Lamp Blinks	
		5.2 Display "Under Centralized Control" Blinks (Repeats Single Blink)	307
		5.3 Display "Under Centralized Control" Blinks (Repeats Double Blink).	
Part 7	Append	lix	315
	pp		• • •
	1.	Piping Diagrams	316
		1.1 Outdoor Unit	316
		1.2 Indoor Unit	320
	2.	Wiring Diagrams for Reference	.324
		2.1 Outdoor Unit	
		2.2 Field Wiring	
		2.3 Indoor Unit	
	_		
	3.	List of Electrical and Functional Parts	
		3.1 Outdoor Unit	
		3.2 Indoor Side	
	4.	Option List	357
		4.1 Option List of Controllers	357

iv Table of Contents

	4.2 Option Lists (Outdoor Unit)	359
Ę	5. Piping Installation Point	361
	5.1 Piping Installation Point	
	5.2 The Example of A Wrong Pattern	362
6	S. Example of connection (R-410A Type)	
7	7. Thermistor Resistance / Temperature Characteristics	365
	3. Pressure Sensor	
	Method of Checking The Inverter's Power Transistors	
	and Diode Modules	368
8 Preca	and Diode Modulesutions for New Refrigerant (R-410A)	
	utions for New Refrigerant (R-410A)	371
		3 71
	utions for New Refrigerant (R-410A)	371 372
	utions for New Refrigerant (R-410A)	371372372374

Table of Contents v

Introduction Si34-601A

1. Introduction

1.1 Safety Cautions

Cautions and Warnings

- Be sure to read the following safety cautions before conducting repair work.
- The caution items are classified into "♠ Warning" and "♠ Caution". The "♠ Warning" items are especially important since they can lead to death or serious injury if they are not followed closely. The "♠ Caution" items can also lead to serious accidents under some conditions if they are not followed. Therefore, be sure to observe all the safety caution items described below.
- About the pictograms
- △ This symbol indicates an item for which caution must be exercised.
- The pictogram shows the item to which attention must be paid.

 This symbol indicates a prohibited action.
- The prohibited item or action is shown inside or near the symbol.

 This symbol indicates an action that must be taken, or an instruction
- This symbol indicates an action that must be taken, or an instruction. The instruction is shown inside or near the symbol.
- After the repair work is complete, be sure to conduct a test operation to ensure that the equipment operates normally, and explain the cautions for operating the product to the customer

1.1.1 Caution in Repair

• Warning	
Be sure to disconnect the power cable plug from the plug socket before disassembling the equipment for a repair. Working on the equipment that is connected to a power supply can cause an electrical shook. If it is necessary to supply power to the equipment to conduct the repair or inspecting the circuits, do not touch any electrically charged sections of the equipment.	B =\$
If the refrigerant gas discharges during the repair work, do not touch the discharging refrigerant gas. The refrigerant gas can cause frostbite.	\bigcirc
When disconnecting the suction or discharge pipe of the compressor at the welded section, release the refrigerant gas completely at a well-ventilated place first. If there is a gas remaining inside the compressor, the refrigerant gas or refrigerating machine oil discharges when the pipe is disconnected, and it can cause injury.	
If the refrigerant gas leaks during the repair work, ventilate the area. The refrigerant gas can generate toxic gases when it contacts flames.	0
The step-up capacitor supplies high-voltage electricity to the electrical components of the outdoor unit. Be sure to discharge the capacitor completely before conducting repair work. A charged capacitor can cause an electrical shock.	A
Do not start or stop the air conditioner operation by plugging or unplugging the power cable plug. Plugging or unplugging the power cable plug to operate the equipment can cause an electrical shock or fire.	\bigcirc

Si34-601A Introduction

<u> Caution</u>	
Do not repair the electrical components with wet hands. Working on the equipment with wet hands can cause an electrical shock.	\bigcirc
Do not clean the air conditioner by splashing water. Washing the unit with water can cause an electrical shock.	\bigcirc
Be sure to provide the grounding when repairing the equipment in a humid or wet place, to avoid electrical shocks.	•
Be sure to turn off the power switch and unplug the power cable when cleaning the equipment. The internal fan rotates at a high speed, and cause injury.	9 🗲
Do not tilt the unit when removing it. The water inside the unit can spill and wet the furniture and floor.	\bigcirc
Be sure to check that the refrigerating cycle section has cooled down sufficiently before conducting repair work. Working on the unit when the refrigerating cycle section is hot can cause burns.	
Use the welder in a well-ventilated place. Using the welder in an enclosed room can cause oxygen deficiency.	0

1.1.2 Cautions Regarding Products after Repair

^	
Warning	
Be sure to use parts listed in the service parts list of the applicable model and appropriate tools to conduct repair work. Never attempt to modify the equipment. The use of inappropriate parts or tools can cause an electrical shock, excessive heat generation or fire.	
When relocating the equipment, make sure that the new installation site has sufficient strength to withstand the weight of the equipment. If the installation site does not have sufficient strength and if the installation work is not conducted securely, the equipment can fall and cause injury.	
Be sure to install the product correctly by using the provided standard installation frame. Incorrect use of the installation frame and improper installation can cause the equipment to fall, resulting in injury.	For integral units only
Be sure to install the product securely in the installation frame mounted on a window frame. If the unit is not securely mounted, it can fall and cause injury.	For integral units only
Be sure to use an exclusive power circuit for the equipment, and follow the technical standards related to the electrical equipment, the internal wiring regulations and the instruction manual for installation when conducting electrical work. Insufficient power circuit capacity and improper electrical work can cause an electrical shock or fire.	

Introduction Si34-601A

• Warning	
Be sure to use the specified cable to connect between the indoor and outdoor units. Make the connections securely and route the cable properly so that there is no force pulling the cable at the connection terminals. Improper connections can cause excessive heat generation or fire.	
When connecting the cable between the indoor and outdoor units, make sure that the terminal cover does not lift off or dismount because of the cable. If the cover is not mounted properly, the terminal connection section can cause an electrical shock, excessive heat generation or fire.	
Do not damage or modify the power cable. Damaged or modified power cable can cause an electrical shock or fire. Placing heavy items on the power cable, and heating or pulling the power cable can damage the cable.	
Do not mix air or gas other than the specified refrigerant (R-410A) in the refrigerant system. If air enters the refrigerating system, an excessively high pressure results, causing equipment damage and injury.	
If the refrigerant gas leaks, be sure to locate the leak and repair it before charging the refrigerant. After charging refrigerant, make sure that there is no refrigerant leak. If the leak cannot be located and the repair work must be stopped, be sure to perform pump-down and close the service valve, to prevent the refrigerant gas from leaking into the room. The refrigerant gas itself is harmless, but it can generate toxic gases when it contacts flames, such as fan and other heaters, stoves and ranges.	0
When replacing the coin battery in the remote controller, be sure to disposed of the old battery to prevent children from swallowing it. If a child swallows the coin battery, see a doctor immediately.	

<u> </u>	
Installation of a leakage breaker is necessary in some cases depending on the conditions of the installation site, to prevent electrical shocks.	
Do not install the equipment in a place where there is a possibility of combustible gas leaks. If a combustible gas leaks and remains around the unit, it can cause a fire.	
Be sure to install the packing and seal on the installation frame properly. If the packing and seal are not installed properly, water can enter the room and wet the furniture and floor.	For integral units only

1.1.3 Inspection after Repair

• Warning	
<u>/</u> waiting	
Check to make sure that the power cable plug is not dirty or loose, then insert the plug into a power outlet all the way. If the plug has dust or loose connection, it can cause an electrical shock or fire.	0
If the power cable and lead wires have scratches or deteriorated, be sure to replace them. Damaged cable and wires can cause an electrical shock, excessive heat generation or fire.	0
Do not use a joined power cable or extension cable, or share the same power outlet with other electrical appliances, since it can cause an electrical shock, excessive heat generation or fire.	\bigcirc

Si34-601A Introduction

<u> </u>	
Check to see if the parts and wires are mounted and connected properly, and if the connections at the soldered or crimped terminals are secure. Improper installation and connections can cause excessive heat generation, fire or an electrical shock.	
If the installation platform or frame has corroded, replace it. Corroded installation platform or frame can cause the unit to fall, resulting in injury.	
Check the grounding, and repair it if the equipment is not properly grounded. Improper grounding can cause an electrical shock.	
Be sure to measure the insulation resistance after the repair, and make sure that the resistance is 1 Mohm or higher. Faulty insulation can cause an electrical shock.	
Be sure to check the drainage of the indoor unit after the repair. Faulty drainage can cause the water to enter the room and wet the furniture and floor.	

1.1.4 Using Icons

Icons are used to attract the attention of the reader to specific information. The meaning of each icon is described in the table below:

1.1.5 Using Icons List

Icon	Type of Information	Description
Note:	Note	A "note" provides information that is not indispensable, but may nevertheless be valuable to the reader, such as tips and tricks.
Caution	Caution	A "caution" is used when there is danger that the reader, through incorrect manipulation, may damage equipment, loose data, get an unexpected result or has to restart (part of) a procedure.
(Warning	Warning	A "warning" is used when there is danger of personal injury.
5	Reference	A "reference" guides the reader to other places in this binder or in this manual, where he/she will find additional information on a specific topic.

Introduction Si34-601A

1.2 PREFACE

Thank you for your continued patronage of Daikin products.

This is the new service manual for Daikin's Year 2006 VRVIII series Heat Pump System. Daikin offers a wide range of models to respond to building and office air conditioning needs. We are confident that customers will be able to find the models that best suit their needs.

This service manual contains information regarding the servicing of VRVIII series R-410A Heat Pump System.

July, 2007

After Sales Service Division

Part 1 General Information

1.	Model Names of Indoor/Outdoor Units	2
2.	External Appearance	3
	2.1 Indoor Units	
	2.2 Outdoor Units	4
3.	Combination of Outdoor Units	5
4.	Model Selection	7

1. Model Names of Indoor/Outdoor Units

Indoor Units

Туре						M	odel Nar	ne					Power Supply
Ceiling Mounted Cassette Type (Double Flow)	FXCQ	20M	25M	32M	40M	50M	63M	80M	_	125M	_		VE
Ceiling Mounted Cassette Type (Multi Flow)	FXFQ	_	25M	32M	40M	50M	63M	80M	100M	125M	_		VL
600×600 Ceiling Mounted Cassette Type	FXZQ	20M	25M	32M	40M	50M	_	_	_	_	_	_	V1
Ceiling Mounted Cassette Corner Type	FXKQ	_	25MA	32MA	40MA	_	63MA	_	_	_	_	_	
	FXDQ- PVE	20P	25P	32P	_	_	_	_	_	_	_	_	
Slim Ceiling Mounted	FXDQ- PVET	20P	25P	32P	_	-	_	_	_	_	_		
Duct Type	FXDQ- NAVE	20NA	25NA	32NA	40NA	50NA	63NA	_	_	_	_	_	
	FXDQ- NVET	20N	25N	32N	40N	50N	63N	_	_	_	_	_	
Ceiling Mounted Built-In Type	FXSQ	20M	25M	32M	40M	50M	63M	80M	100M	125M	_	_	VE
Ceiling Mounted Duct Type	FXMQ	_	_	_	40MA	50MA	63MA	80MA	100MA	125MA	200MA	250MA	
Ceiling Suspended Type	FXHQ	_	_	32MA	_	_	63MA	_	100MA	_	_	_	
Wall Mounted Type	FXAQ	20MA	25MA	32MA	40MA	50MA	63MA	_	_	_	_	_	
Floor Standing Type	FXLQ	20MA	25MA	32MA	40MA	50MA	63MA	_	_	_	_	_	
Concealed Floor Standing Type	FXNQ	20MA	25MA	32MA	40MA	50MA	63MA	_	_	_	_	_	
Outdoor Air Processing Unit	FXMQ- MF	_	_	_	_	_	_	_	_	125MF	200MF	250MF	V1
Ceiling Suspended Cassette Type	FXUQ	_	_	_	_	_	_	71MA	100MA	125MA	_	_	
Connection Unit	BEVQ-MA	_	_	_	_		_	71MA	100MA	125MA	_		VE

Note: FXDQ has following 2 Series, as show below.

FXDQ-P, N(A)VET: without Drain Pump (For General, Asia: except for EU, China and Australia)

FXDQ-P, N(A)VE: with Drain Pump

BEV unit is required for each indoor unit.

MA, NA: RoHS Directive models; Specifications, Dimensions and other functions are not changed compared with M, N type.

Outdoor Units

Normal Series

Series		Model Name									Power Supply
		5P	8P	10P	12P	14P	16P	18P	20P	22P	
Heat Pump	RXYQ	24P	26P	28P	30P	32P	34P	36P	38P	40P	Y1(E)
		42P	44P	46P	48P	50P	52P	54P			

High COP Series (Energy Saving Series)

Series		Model Name									Power Supply
Heat Pump	IRXYQ —	16PH	18PH	24PH	26PH	28PH	30PH	32PH	34PH	36PH	Y1(E)
		38PH	40PH	42PH	44PH	46PH	48PH	50PH			

*Power Supply VE: 1 phase 220~240V, 50Hz

V1: 1 phase 220~240V, 50Hz Y1: 3 phase 380~415V, 50Hz E: The unit with anti corrosion treatment

Si34-601A External Appearance

2. External Appearance

2.1 Indoor Units



External Appearance Si34-601A

2.2 Outdoor Units



3. Combination of Outdoor Units

Normal Series

System	Number	nber Module							Outdoor Unit Multi Connection
Capacity	of units	5	8	10	12	14	16	18	Piping Kit (Option)
5HP	1	•							
8HP	1		•						1
10HP	1			•					1
12HP	1				•				1 – 1
14HP	1					•			1
16HP	1						•		1
18HP	1							•]
20HP	2		•		•				
22HP	2			•	•]
24HP	2		•				•		
26HP	2		•					•	
28HP	2			•				•	Heat Pump: BHFP22P100
30HP	2				•			•	
32HP	2						••		
34HP	2						•	•	
36HP	2							•	
38HP	3		•		•			•	
40HP	3		•				••		
42HP	3		•				•	•	
44HP	3		•					••	
46HP	3			•				••	Heat Pump: BHFP22P151
48HP	3				•			••	
50HP	3					•		••	
52HP	3						•	••	
54HP	3							•••	

A Note:

For multiple connection of 18HP system or more, an optional Daikin Outdoor Unit Multi Connection Piping Kit is required.

High COP Series (Energy Saving Series)

System	Number			Mod		Outdoor Unit Multi Connection		
Capacity	of units	8	10	12	14	16	18	Piping Kit (Option)
16HP	2	••						
18HP	2	•	•					
24HP	3	•••						
26HP	3	••	•					
28HP	3	••		•				Heat Pump: BHFP22P100
30HP	3	•	•	•				1
32HP	3	•		••				
34HP	3		•	••				
36HP	3			•••				
38HP	3			••	•			
40HP	3			••		•		
42HP	3			••			•	1
44HP	3			•		••		Heat Pump: BHFP22P151
46HP	3			•		•	•]
48HP	3					•••]
50HP	3					••	•]

Note:

For multiple connection of 16HP system or more, an optional Daikin Outdoor Unit Multi Connection Piping Kit is required.

Si34-601A Model Selection

4. Model Selection

VRV III Heat Pump Series

Connectable indoor units number and capacity Normal Series

HP	5HP	8HP	10HP	12HP	14HP	16HP	18HP
System name	RXYQ5P	RXYQ8P	RXYQ10P	RXYQ12P	RXYQ14P	RXYQ16P	RXYQ18P
Outdoor unit 1	RXYQ5P	RXYQ8P	RXYQ10P	RXYQ12P	RXYQ14P	RXYQ16P	RXYQ18P
Outdoor unit 2	_	-	-	-	-	-	-
Outdoor unit 3	-	-	-	-	-	-	-
Total number of connectable indoor units	8	13	16	19	23	26	29
Total capacity of connectable indoor units (kW)	7.00~18.20	11.20~29.12	14.00~36.40	16.75~43.55	20.00~52.00	22.40~58.24	25.20~65.52
HP	20HP	22HP	24HP	26HP	28HP	30HP	32HP
System name	RXYQ20P	RXYQ22P	RXYQ24P	RXYQ26P	RXYQ28P	RXYQ30P	RXYQ32P
Outdoor unit 1	RXYQ8P	RXYQ10P	RXYQ8P	RXYQ8P	RXYQ10P	RXYQ12P	RXYQ16P
Outdoor unit 2	RXYQ12P	RXYQ12P	RXYQ16P	RXYQ18P	RXYQ18P	RXYQ18P	RXYQ16P
Outdoor unit 3	_	_	_	_	_	_	_
Total number of connectable indoor units	32	35	39	42	45	48	52
Total capacity of connectable indoor units (kW)	27.95~72.67	30.75~79.95	33.60~87.36	36.40~94.64	39.15~101.79	41.95~109.07	44.70~116.22
HP	34HP	36HP	38HP	40HP	42HP	44HP	46HP
System name	RXYQ34P	RXYQ36P	RXYQ38P	RXYQ40P	RXYQ42P	RXYQ44P	RXYQ46P
Outdoor unit 1	RXYQ16P	RXYQ18P	RXYQ8P	RXYQ8P	RXYQ8P	RXYQ8P	RXYQ10P
Outdoor unit 2	RXYQ18P	RXYQ18P	RXYQ12P	RXYQ16P	RXYQ16P	RXYQ18P	RXYQ18P
Outdoor unit 3	-	-	RXYQ18P	RXYQ16P	RXYQ18P	RXYQ18P	RXYQ18P
Total number of connectable indoor units	55	58	61		6	4	
Total capacity of connectable indoor units (kW)	47.50~123.50	50.25~130.65	53.50~139.10	56.00~145.60	58.00~150.80	61.75~160.55	63.75~165.75
HP	48HP	50HP	52HP	54HP			
System name	RXYQ48P	RXYQ50P	RXYQ52P	RXYQ54P			
Outdoor unit 1	RXYQ12P	RXYQ14P	RXYQ16P	RXYQ18P			
Outdoor unit 2	RXYQ18P	RXYQ18P	RXYQ18P	RXYQ18P			
Outdoor unit 3	RXYQ18P	RXYQ18P	RXYQ18P	RXYQ18P			
Total number of connectable indoor units		6	4	1			
Total capacity of connectable indoor units (kW)	67.50~175.50	69.50~180.70	71.50~185.90	73.50~191.10			
					-		

Model Selection Si34-601A

High COP Series (Energy Saving Series)

HP	16HP	18HP
System name	RXYQ16PH	RXYQ18PH
Outdoor unit 1	RXYQ8P	RXYQ8P
Outdoor unit 2	RXYQ8P	RXYQ10P
Outdoor unit 3	ı	1
Total number of connectable indoor units	26	29
Total capacity of connectable indoor units (kW)	22.40~58.24	25.20~65.52

HP	24HP	26HP	28HP	30HP	32HP
System name	RXYQ24PH	RXYQ26PH	RXYQ28PH	RXYQ30PH	RXYQ32PH
Outdoor unit 1	RXYQ8P	RXYQ8P	RXYQ8P	RXYQ8P	RXYQ8P
Outdoor unit 2	RXYQ8P	RXYQ8P	RXYQ8P	RXYQ10P	RXYQ12P
Outdoor unit 3	RXYQ8P	RXYQ10P	RXYQ12P	RXYQ12P	RXYQ12P
Total number of connectable indoor units	39	42	45	48	52
Total capacity of connectable indoor units (kW)	33.60~87.36	36.40~94.64	39.15~101.79	41.95~109.07	44.70~116.22

HP	34HP	36HP	38HP	40HP	42HP	44HP	46HP
System name	RXYQ34PH	RXYQ36PH	RXYQ38PH	RXYQ40PH	RXYQ42PH	RXYQ44PH	RXYQ46PH
Outdoor unit 1	RXYQ10P	RXYQ12P	RXYQ12P	RXYQ12P	RXYQ12P	RXYQ12P	RXYQ12P
Outdoor unit 2	RXYQ12P	RXYQ12P	RXYQ12P	RXYQ12P	RXYQ12P	RXYQ16P	RXYQ16P
Outdoor unit 3	RXYQ12P	RXYQ12P	RXYQ14P	RXYQ16P	RXYQ18P	RXYQ16P	RXYQ18P
Total number of connectable indoor units	55	58	61	64			
Total capacity of connectable indoor units (kW)	47.50~123.50	50.25~130.65	53.50~139.10	56.00~145.60	58.00~150.80	61.75~160.55	63.75~165.75

HP	48HP	50HP		
System name	RXYQ48PH	RXYQ50PH		
Outdoor unit 1	RXYQ16P	RXYQ16P		
Outdoor unit 2	RXYQ16P	RXYQ16P		
Outdoor unit 3	RXYQ16P	RXYQ18P		
Total number of connectable indoor units	64			
Total capacity of connectable indoor units (kW)	67.50~175.50	69.50~180.70		

Si34-601A Model Selection

Connectable Indoor Unit

Туре	Model Name								Power Supply					
Ceiling Mounted Cassette Type (Double Flow)	FXCQ	20M	25M	32M	40M	50M	63M	80M	_	125M	_	_		
Ceiling Mounted Cassette Type (Multi Flow)	FXFQ	_	25M	32M	40M	50M	63M	80M	100M	125M	_	_		
600×600 Ceiling Mounted Cassette Type (Multi Flow)	FXZQ	20M	25M	32M	40M	50M	_	_	_	_	_	_		
Ceiling Mounted Cassette Corner Type	FXKQ	_	25MA	32MA	40MA		63MA	_	_	_	_	_		
	FXDQ- PVE	20P	25P	32P	_	_	_	_	_	_	_	_		
Slim Ceiling Mounted	FXDQ- PVET	20P	25P	32P	_	_	_	_	_	_	_	_		
Duct Type	FXDQ- NAVE	20NA	25NA	32NA	40NA	50NA	63NA	_	_	_	_	_	VE	
	FXDQ- NVET	20N	25N	32N	40N	50N	63N	_	_	_	_	_	VE	
Ceiling Mounted Built-In Type	FXSQ	20M	25M	32M	40M	50M	63M	80M	100M	125M	_	_		
Ceiling Mounted Duct Type	FXMQ	_	_	_	40MA	50MA	63MA	80MA	100MA	125MA	200MA	250MA		
Ceiling Suspended Type	FXHQ	_	_	32MA	_	_	63MA	_	100MA	_	_	_		
Wall Mounted Type	FXAQ	20MA	25MA	32MA	40MA	50MA	63MA	_	_	_	_	_		
Floor Standing Type	FXLQ	20MA	25MA	32MA	40MA	50MA	63MA	_	_	_	_	_		
Concealed Floor Standing Type	FXNQ	20MA	25MA	32MA	40MA	50MA	63MA	_	_	_	_	_		
Outdoor Air Processing Unit	FXMQ- MF	_	_	_	_	_	_	_	_	125MF	200MF	250MF	\/4	
Ceiling Suspended Cassette Type	FXUQ	_	_	_	_	_	_	71MA	100MA	125MA	_	_	- V1	
Connection Unit	BEVQ-MA	_	_	_	_	_	_	71MA	100MA	125MA	_	_	VE	

Note: FXDQ has following 2 Series, as show below.

FXDQ-P, N(A)VET: without Drain Pump (For General, Asia: except for EU, China and Australia)

FXDQ-P, N(A)VE: with Drain Pump BEV unit is required for each indoor unit. FXZQ: only for EU, Australia

Indoor unit capacity

New refrigerant model code	P20	P25	P32	P40	P50	P63	P80	P100	P125	P200	P250
	type	type	type	type	type	type	type	type	type	type	type
Selecting model capacity	2.2	2.8	3.5	4.5	5.6	7.0	9.0	11.2	14.0	22.4	28.0
	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW
Equivalent output	0.8HP	1HP	1.25HP	1.6HP	2.0HP	2.5HP	3.2HP	4HP	5HP	8HP	10HP

Use the above tables to determine the capacities of indoor units to be connected. Make sure the total capacity of indoor units connected to each outdoor unit is within the specified value (kW).

- The total capacity of connected indoor units must be within a range of 50 to 130% of the rated capacity of the outdoor unit.
- In some models, it is not possible to connect the maximum number of connectable indoor units. Select models so the total capacity of connected indoor units conforms to the specification.

Model Selection Si34-601A

Differences from Conventional Models

Item		Differences	
nem	Object	Object New model (P Model)	
Compressor	Connection of equalizer oil pipe	NONE (No particular changes in terms of service)	• YES
	Equalizer oil pipe for multi- outdoor-unit system	• NONE	• YES
Workability	Procedure for calculating refrigerant refilling quantity	Refilling quantity due to piping length + Adjustment quantity according to models of outdoor units	Refilling quantity due to piping length - Adjustment quantity according to models of outdoor units
Optional accessories	Branch pipe for outdoor unit connection	Y branch Type: BHFP22P100/151	● T branch Type: BHFP22MA90/135

Part 2 Specifications

1.	Spec	cifications	1	2
	1.1	Outdoor Units	1	2
	1.2	Indoor Units	3	33

Specifications Si34-601A

1. Specifications

1.1 Outdoor Units

Heat Pump 50Hz Standard Series <RXYQ-P>

Model Name			RXYQ5PY1(E)	RXYQ8PY1(E)
★1 Cooling Capacity (19.5°CWB) kcal / h Btu / h kW		kcal / h	12,100	19,400
		Btu / h	48,100	77,000
		kW	14.1	22.5
★2 Cooling C	Capacity (19.0°CWB)	kW	14.0	22.4
		kcal / h	13,800	21,500
★3 Heating C	Capacity	Btu / h	54,600	85,300
		kW	16.0	25.0
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: ((H×W×D)	mm	1680×635×765	1680×930×765
Heat Exchanç	ger		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	13.72	13.72
Comp.	Number of Revolutions	r.p.m	6300	7980
	Motor Output×Number of Units	kW	2.8×1	3.8×1
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	0.35×1	0.75×1
Ган	Air Flow Rate	m³/min	95	180
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ9.5 (Brazing Connection)	φ9.5 (Brazing Connection)
Pipes	Gas Pipe	mm	φ15.9 (Brazing Connection)	φ19.1 (Brazing Connection)
Product Mass	(Machine weight)	kg	160	205
Safety Device	es .		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	od		Deicer	Deicer
Capacity Con	Capacity Control %		28~100	20~100
Refrigerant Name			R-410A	R-410A
Refrigerant	Charge	kg	6.2	7.7
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acc	essories		Installation Manual, Operation Manual, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.			C: 4D051441A	C: 4D051442A

Notes:

★1 Indoor temp. : 27°CDB, 19.5°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

★2 Indoor temp. : 27°CDB, 19.0°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

The Reference Number
C~: Partly corrected drawings.
J~: Original drawing is Japanese

V~: Printing Convenience

Si34-601A Specifications

Model Name			RXYQ10PY1(E)	RXYQ12PY1(E)
		kcal / h	24,300	29,000
, , , , , , , , , , , , , , , , , , ,		Btu / h	96,200	115,000
		kW	28.2	33.7
★2 Cooling Ca	apacity (19.0°CWB)	kW	28.0	33.5
		kcal / h	27,100	32,300
★3 Heating Ca	apacity	Btu / h	107,000	128,000
		kW	31.5	37.5
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (I	H×W×D)	mm	1680×930×765	1680×1240×765
Heat Exchang	er		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
Comp.	Piston Displacement	m³/h	13.72+10.53	13.72+10.53
	Number of Revolutions	r.p.m	6300, 2900	6300, 2900
	Motor Output×Number of Units	kW	(1.2+4.5)×1	(2.5+4.5)×1
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	0.75×1	0.35×2
Fall	Air Flow Rate	m³/min	185	233
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ9.5 (Brazing Connection)	φ12.7 (Brazing Connection)
Pipes	Gas Pipe	mm	φ22.2 (Brazing Connection)	φ28.6 (Brazing Connection)
Product Mass	(Machine Weight)	kg	249	285
Safety Devices	s		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	d		Deicer	Deicer
Capacity Cont	Capacity Control %		14~100	14~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge	kg	8.4	10.0
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator O	il		Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.			C: 4D051443A	C: 4D051444A

Notes:

★1 Indoor temp. : 27°CDB, 19.5°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Specifications Si34-601A

Model Name			RXYQ14PY1(E)	RXYQ16PY1(E)
		kcal / h	34,600	39,000
★1 Cooling Capacity (19.5°CWB)		Btu / h	137,000	155,000
		kW	40.2	45.3
★2 Cooling C	apacity (19.0°CWB)	kW	40.0	45.0
		kcal / h	38,700	43,000
★3 Heating C	apacity	Btu / h	154,000	171,000
		kW	45.0	50.0
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H×W×D)	mm	1680×1240×765	1680×1240×765
Heat Exchang	jer		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
Comp.	Piston Displacement	m³/h	13.72+10.53+10.53	13.72+10.53+10.53
	Number of Revolutions	r.p.m	6300, 2900×2	6300, 2900×2
	Motor Output×Number of Units	kW	(0.3+4.5+4.5)×1	(1.4+4.5+4.5)×1
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	0.35×2	0.35×2
ran	Air Flow Rate	m³/min	233	233
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ12.7 (Brazing Connection)	φ12.7 (Brazing Connection)
Pipes	Gas Pipe	mm	φ28.6 (Brazing Connection)	φ28.6 (Brazing Connection)
Product Mass	(Machine Weight)	kg	329	329
Safety Device	es		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	od		Deicer	Deicer
Capacity Control %		%	10~100	10~100
Refrigerant Name			R-410A	R-410A
Refrigerant	Charge	kg	12.3	12.5
Control		•	Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.			C: 4D051445A	C: 4D051446A
			I.	I.

Notes:

★1 Indoor temp. : 27°CDB, 19.5°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Specifications Si34-601A

Model Name	Combination Unit)		RXYQ18PY1(E)	RXYQ20PY1(E)
Model Name	Independent Unit)		_	RXYQ8PY1(E)+RXYQ12PY1(E)
		kcal / h	42,000	48,300
★1 Cooling Capacity (19.5°CWB) Btu		Btu / h	168,000	192,000
	kW		49.3	56.2
★2 Cooling Ca	apacity (19.0°CWB)	kW	49	55.9
		kcal / h	48,600	53,800
★3 Heating Ca	apacity	Btu / h	193,000	213,000
		kW	56.5	62.5
Casing Color		_	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (I	H×W×D)	mm	1680×1240×765	(1680×930×765)+(1680×1240×765)
Heat Exchange	er		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	13.72+10.53+10.53	(13.72)+(13.72+10.53)
Comp.	Number of Revolutions	r.p.m	7980, 2900, 2900	(7980)+(6300, 2900)
	Motor Output×Number of Units	kW	(3.0+4.5+4.5)×1	(3.8×1)+((2.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	0.75×2	(0.75×1)+(0.35×2)
Ган	Air Flow Rate	m³/min	239	180+233
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ15.9 (Brazing Connection)	φ15.9 (Brazing Connection)
Pipes	Gas Pipe	mm	φ28.6 (Brazing Connection)	φ28.6 (Brazing Connection)
Product Mass	(Machine Weight)	kg	341	205+285
Safety Devices	3		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	d		Deicer	Deicer
Capacity Control %		%	9~100	8~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge	kg	12.7	7.7+12.3
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator O	i		Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.			C: 4D051447A	

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Model Name (Combination Unit)			RXYQ22PY1(E)	RXYQ24PY1(E)	
Model Name	(Independent Unit)		RXYQ10PY1(E)+RXYQ12PY1(E)	RXYQ8PY1(E)+RXYQ16PY1(E)	
		kcal / h	53,200	58,300	
★1 Cooling Capacity (19.5°CWB)		Btu / h	211,000	231,000	
		kW	61.9	67.8	
★2 Cooling Ca	apacity (19.0°CWB)	kW	61.5	67.4	
		kcal / h	59,300	64,500	
★3 Heating Ca	apacity	Btu / h	235,000	256,000	
		kW	69	75.0	
Casing Color		•	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	
Dimensions: (I	H×W×D)	mm	(1680×930×765)+(1680×1240×765)	(1680×930×765)+(1680×1240×765)	
Heat Exchang	er	•	Cross Fin Coil	Cross Fin Coil	
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type	
	Piston Displacement	m³/h	(13.72+10.53)+(13.72+10.53)	13.72+(13.72+10.53+10.53)	
Comp.	Number of Revolutions	r.p.m	(6300, 2900)+(6300, 2900)	7980+(6300, 2900×2)	
	Motor Output×Number of Units	kW	((1.2+4.5)×1)+((2.5+4.5)×1)	(3.8×1)+((1.4+4.5+4.5)×1)	
	Starting Method		Soft Start	Soft Start	
	Туре		Propeller Fan	Propeller Fan	
Fan	Motor Output	kW	(0.75×1)+(0.35×2)	(0.75×1)+(0.35×2)	
ган	Air Flow Rate	m³/min	185+233	180+233	
	Drive		Direct Drive	Direct Drive	
Connecting	Liquid Pipe	mm	φ15.9 (Brazing Connection)	φ15.9 (Brazing Connection)	
Pipes	Gas Pipe	mm	φ28.6 (Brazing Connection)	φ34.9 (Brazing Connection)	
Product Mass	(Machine Weight)	kg	249+285	205+329	
Safety Device	s		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	
Defrost Metho	d		Deicer	Deicer	
Capacity Cont	rol	%	7~100	6~100	
	Refrigerant Name		R-410A	R-410A	
Refrigerant	Charge	kg	8.4+10.0	7.7+12.5	
Control			Electronic Expansion Valve	Electronic Expansion Valve	
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor	
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps	
Drawing No.					

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Si34-601A **Specifications**

Model Name (Combination Unit)			RXYQ26PY1(E)	RXYQ28PY1(E)
Model Name	(Independent Unit)		RXYQ8PY1(E)+RXYQ18PY1(E)	RXYQ10PY1(E)+RXYQ18PY1(E)
		kcal / h	61,700	66,700
★1 Cooling Capacity (19.5°CWB)		Btu / h	250,000	26,400
		kW	71.8	77.5
★2 Cooling Ca	apacity (19.0°CWB)	kW	71.4	77.0
		kcal / h	70,100	75,700
★3 Heating Ca	apacity	Btu / h	278,000	300,000
		kW	81.5	88.0
Casing Color		•	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (I	H×W×D)	mm	(1680×930×765)+(1680×1240×765)	(1680×930×765)+(1680×1240×765)
Heat Exchang	er	•	Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72+10.53+10.53)	(13.72+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(7980, 2900, 2900)	(6300, 2900)+(7980, 2900×2)
	Motor Output×Number of Units	kW	(3.8×1)+((3.0+4.5+4.5)×1)	((1.2+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Type		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.75×1)+(0.75×2)	(0.75×1)+(0.75×2)
ran	Air Flow Rate	m³/min	180+239	185+239
	Drive	•	Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)
Pipes	Gas Pipe	mm	φ34.9 (Brazing Connection)	φ34.9 (Brazing Connection)
Product Mass	(Machine Weight)	kg	205+341	249+341
Safety Device	s		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	d		Deicer	Deicer
Capacity Control %		%	6~100	5~100
	Refrigerant Name	•	R-410A	R-410A
Refrigerant	Charge	kg	7.7+12.7	8.4+12.7
Control		•	Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

*1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 *2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Refrigerativ 19.0°CWB KW 83.3 90.5 90	Model Name (Combination Unit)			RXYQ30PY1(E)	RXYQ32PY1(E)	
Reference Red	Model Name (Independent Unit)		RXYQ12PY1(E)+RXYQ18PY1(E)	RXYQ16PY1(E)+RXYQ16PY1(E)	
No.			kcal / h	71,400	77,800	
A2 Cooling Capacity (19.0°CWB) Kw Koal / h 80,800 86,000 86,000 83 Heating Capacity Btu / h 321,000 341,000 341,000	★1 Cooling Capacity (19.5°CWB)		Btu / h	283,000	309,000	
Real Realing Capacity Real Re			kW	83	90.5	
Bit / h 321,000 341,000 341,000	★2 Cooling Ca	pacity (19.0°CWB)	kW	82.5	90	
Note			kcal / h	80,800	86,000	
Casing Color	★3 Heating Ca	pacity	Btu / h	321,000	341,000	
Dimensions: (HxWxD)			kW	94	100	
Type	Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	
Type	Dimensions: (H	l×W×D)	mm	(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)	
Piston Displacement m³/h (13.72+10.53)+(13.72+10.53) (13.72+10.53)+(13.72+10.53)+(13.72+10.53) Number of Revolutions r.p.m (6300, 2900)+(7980, 2900) (6300, 2900)+(6300, 2900)+(6300, 2900) Motor OutputxNumber of Units kW ((2.5+4.5)x1)+((3.0+4.5+4.5)x1) ((1.4+4.5+4.5)x1)+((1.4+4.5+4.5)x1) Starting Method Soft Start Soft Start Type Propeller Fan Propeller Fan Motor Output kW ((0.35x2)+(0.75x2) (0.35x2)+(0.35x2)+(0.35x2) Air Flow Rate m³/min 233+239 233+233 Drive Direct Drive Direct Drive Connecting Propeller Fan Propeller Fan Liquid Pipe mm \$19.1 (Brazing Connection) \$19.1 (Brazing Connection) Product Mass (Machine Weight) kg 285+341 329+329 Safety Devices High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector Capacity Control Propeller Fan Propeller Fan Affigerant Name Refrigerant Name Refrigerator Oller Refer to the nameplate of compressor Refer to the nameplate of compressor	Heat Exchange	er		Cross Fin Coil	Cross Fin Coil	
Number of Revolutions		Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type	
Motor OutputxNumber of Units		Piston Displacement	m³/h	(13.72+10.53)+(13.72+10.53+10.53)	(13.72+10.53+10.53)+(13.72+10.53+10.53)	
Motor OutputxNumber of Units KW ((2.5+4.5)x1)+((3.0+4.5+4.5)x1) ((1.4+4.5+4.5)x1)+((1.4+4.5+4.5)x1) Starting Method	Comp	Number of Revolutions	r.p.m	(6300, 2900)+(7980, 2900, 2900)	(6300, 2900, 2900)+(6300, 2900, 2900)	
Type Propeller Fan Propeller F	- Cop.	Motor Output×Number of Units	kW	((2.5+4.5)×1)+((3.0+4.5+4.5)×1)	((1.4+4.5+4.5)×1)+((1.4+4.5+4.5)×1)	
Motor Output		Starting Method		Soft Start	Soft Start	
Air Flow Rate m³/min 233+239 233+233 Drive Direct Drive Direct Drive Connecting Liquid Pipe mm 619.1 (Brazing Connection) 619.1 (Brazing Connection) Product Mass (Machine Weight) kg 285+341 329+329 Cafety Devices High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector Capacity Control 9% 5~100 5~100 Refrigerant Name Refrigerant Name Refrigerant Oil Refer to the nameplate of compressor Air Flow Rate m³/min 233+239 233+233 233+233 233+233 233+233 234-239 Air Flow Rate Direct Drive Direct Drive Direct Drive Defraction) At Flow Rate m³/min 233+239 At Flow Refraction of Protector of Plant and Protection of Plant and		Type		Propeller Fan	Propeller Fan	
Air Flow Rate m³/min 233+239 233+233 Drive Direct Drive Direct Drive Connecting Cas Pipe mm \$419.1 (Brazing Connection) \$49.1 (Brazing Connection) \$34.9 (Brazing Connection) \$34.9 (Brazing Connection) \$329+329 \$329 \$329 \$329 \$329 \$329 \$329 \$329 \$	Fon	Motor Output	kW	(0.35×2)+(0.75×2)	(0.35×2)+(0.35×2)	
Liquid Pipe mm \$19.1 (Brazing Connection) \$19.1 (Brazing Connection)	Ган	Air Flow Rate	m³/min	233+239	233+233	
Capacity Control Capacity Co		Drive		Direct Drive	Direct Drive	
Product Mass (Machine Weight) kg 285+341 329+329 Safety Devices High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector Over Current Relay, Inverter Overload Protector Defrost Method Deicer Deicer Capacity Control % 5~100 5~100 Refrigerant Name R-410A R-410A Charge kg 10.0+12.7 12.5+12.5 Control Electronic Expansion Valve Refer to the nameplate of compressor Refer to the nameplate of compressor	Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)	
High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector, Over Current Relay, Inverter Overload Protector Defrost Method Deicer	Pipes	Gas Pipe	mm	φ34.9 (Brazing Connection)	φ34.9 (Brazing Connection)	
Current Relay, Inverter Overload Protector Current Relay, Inverter Overload Protector Current Relay, Inverter Overload Protector Capacity Control Refrigerant Name Refrigerant Name Charge Control Refer to the nameplate of compressor Refer to the nameplate of compressor	Product Mass	(Machine Weight)	kg	285+341	329+329	
Capacity Control % 5~100 5~100	Safety Devices	;		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector		
Refrigerant Name R-410A R-410A Charge kg 10.0+12.7 12.5+12.5 Control Electronic Expansion Valve Electronic Expansion Valve Refrigerator Oil Refer to the nameplate of compressor Refer to the nameplate of compressor	Defrost Method	t		Deicer	Deicer	
Refrigerant Charge kg 10.0+12.7 12.5+12.5 Control Electronic Expansion Valve Electronic Expansion Valve Refrigerator Oil Refer to the nameplate of compressor Refer to the nameplate of compressor	Capacity Conti	Capacity Control %		5~100	5~100	
Control Electronic Expansion Valve Electronic Expansion Valve Refrigerator Oil Refer to the nameplate of compressor Refer to the nameplate of compressor		Refrigerant Name		R-410A	R-410A	
Refrigerator Oil Refer to the nameplate of compressor Refer to the nameplate of compressor	Refrigerant	Charge	kg	10.0+12.7	12.5+12.5	
Ÿ i i	Control			Electronic Expansion Valve	Electronic Expansion Valve	
	Refrigerator O	l		Refer to the nameplate of compressor	·	
Standard Accessories Installation Manual, Operation Manual, Connection Pipes, Clamps Installation Manual, Operation Manual, Connection Pipes, Clamps	Standard Acce	ssories			Installation Manual, Operation Manual, Connection Pipes, Clamps	
Drawing No.	Drawing No.					

Notes:

 $\star 1$ Indoor temp. : 27°CDB, 19.5°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

 $\star 2$ Indoor temp. : 27°CDB, 19.0°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Specifications Si34-601A

Model Name (Combination Unit)			RXYQ34PY1(E)	RXYQ36PY1(E)
Model Name (Independent Unit)			RXYQ16PY1(E)+RXYQ18PY1(E)	RXYQ18PY1(E)+RXYQ18PY1(E)
		kcal / h	81,400	85,100
★1 Cooling C	★1 Cooling Capacity (19.5°CWB) Btu / h		323,000	338,000
		kW	94.6	99
★2 Cooling C	apacity (19.0°CWB)	kW	94.0	98
		kcal / h	92,000	97,200
★3 Heating C	apacity	Btu / h	365,000	386,000
		kW	107	113
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H×W×D)	mm	(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)
Heat Exchang	ger		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72+10.53+10.53)+(13.72+10.53+10.53)	(13.72+10.53+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(6300, 2900, 2900)+(7980, 2900, 2900)	(7980, 2900, 2900)+(7980, 2900, 2900)
comp.	Motor Output×Number of Units	kW	((1.4+4.5+4.5)×1)+((3.0+4.5+4.5)×1)	((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.35×2)+(0.75×2)	(0.75×2)+(0.75×2)
ıan	Air Flow Rate	m³/min	233+239	239+239
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)
Pipes	Gas Pipe	mm	φ34.9 (Brazing Connection)	φ41.3 (Brazing Connection)
Product Mass	(Machine Weight)	kg	329+341	341+341
Safety Device	es		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	od		Deicer	Deicer
Capacity Control %		%	5~100	4~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge	kg	12.5+12.7	12.7+12.7
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator C	Dil		Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acc	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Model Name (Combination Unit)			RXYQ38PY1(E)	RXYQ40PY1(E)
Model Name (Independent Unit)			RXYQ8PY1(E)+RXYQ12PY1(E)+RXYQ18PY1(E)	RXYQ8PY1(E)+RXYQ16PY1(E)+RXYQ16PY1(E)
★1 Cooling Capacity (19.5°CWB)		kcal / h	91,200	97,200
		Btu / h	362,000	386,000
		kW	106	113
★2 Cooling Ca	★2 Cooling Capacity (19.0°CWB) kW		105	112
		kcal / h	102,000	108,000
★3 Heating Capacity Btu / h		Btu / h	406,000	427,000
		kW	119	125
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (I	H×W×D)	mm	(1680×930×765)+(1680×1240×765)+(1680×1240×765)	(1680×930×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchang	er	•	Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72+10.53)+(13.72+10.53+10.53)	(13.72)+(13.72+10.53+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(6300, 2900)+(7980, 2900, 2900)	(7980)+(6300, 2900, 2900)+(6300, 2900, 2900)
Comp.	Motor Output×Number of Units	kW	(3.8×1)+((2.5+4.5)×1)+((3.0+4.5+4.5)×1)	(3.8×1)+((1.4+4.5+4.5)×1)+((1.4+4.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.75×1)+(0.35×2)+(0.75×2)	(0.75×1)+(0.35×2)+(0.35×2)
ган	Air Flow Rate	m³/min	180+233+239	180+233+233
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)
Pipes	Gas Pipe	mm	φ41.3 (Brazing Connection)	φ41.3 (Brazing Connection)
Product Mass	(Machine Weight)	kg	205+285+341	205+329+329
Safety Devices			High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	d		Deicer	Deicer
Capacity Control %		%	4~100	4~100
Refrigerant	Refrigerant Name		R-410A	R-410A
	Charge	kg	7.7+10.0+12.7	7.7+12.5+12.5
	Control		Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

 $\bigstar 3 \quad \text{Indoor temp.}: 20^{\circ}\text{CDB / outdoor temp.}: 7^{\circ}\text{CDB, } 6^{\circ}\text{CWB / Equivalent piping length}: 7.5\text{m, level difference}$: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Si34-601A **Specifications**

Model Name (Combination Unit)			RXYQ42PY1(E)	RXYQ44PY1(E)
Model Name (Independent Unit)			RXYQ8PY1(E)+RXYQ16PY1(E)+RXYQ18PY1(E)	RXYQ8PY1(E)+RXYQ18PY1(E)+RXYQ18PY1(E)
★1 Cooling Capacity (19.5°CWB)		kcal / h	101,000	104,000
		Btu / h	399,000	413,000
		kW	117	121
★2 Cooling Ca	apacity (19.0°CWB)	kW	116	120
		kcal / h	114,000	119,000
★3 Heating Capacity Btu / h		Btu / h	450,000	471,000
		kW	132	138
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (I	H×W×D)	mm	(1680×930×765)+(1680×1240×765)+(1680×1240×765)	(1680×930×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchang	er		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72+10.53+10.53)+(13.72+10.53+10.53)	(13.72)+(13.72+10.53+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(6300, 2900, 2900)+(7980, 2900, 2900)	(7980)+(7980, 2900×2)+(7980, 2900, 2900)
Comp.	Motor Output×Number of Units	kW	(3.8×1)+((1.4+4.5+4.5)×1)+((3.0+4.5+4.5)×1)	(3.8×1)+((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Type		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.75×1)+(0.35×2)+(0.75×2)	(0.75×1)+(0.75×2)+(0.75×2)
ган	Air Flow Rate	m³/min	180+233+239	180+239+239
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)
Pipes	Gas Pipe	mm	φ41.3 (Brazing Connection)	φ41.3 (Brazing Connection)
Product Mass	(Machine Weight)	kg	205+329+341	205+341+341
Safety Devices			High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Method			Deicer	Deicer
Capacity Control %		%	4~100	4~100
Refrigerant	Refrigerant Name		R-410A	R-410A
	Charge	kg	7.7+12.5+12.7	7.7+12.7+12.7
	Control		Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Model Name (Combination Unit)			RXYQ46PY1(E)	RXYQ48PY1(E)
Model Name (Independent Unit)			RXYQ10PY1(E)+RXYQ18PY1(E)+RXYQ18PY1(E)	RXYQ12PY1(E)+RXYQ18PY1(E)+RXYQ18PY1(E)
★1 Cooling Capacity (19.5°CWB)		kcal / h	109,000	114,000
		Btu / h	433,000	454,000
		kW	127	133
★2 Cooling Capacity (19.0°CWB) kW		kW	126	132
		kcal / h	124,000	130,000
★3 Heating C	★3 Heating Capacity Btu / h		495,000	515,000
		kW	145	151
Casing Color		•	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H×W×D)	mm	(1680×930×765)+(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchang	jer	•	Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.7+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)	(13.72+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(6300, 2900)+(7980, 2900, 2900)+(7980, 2900, 2900)	(6300, 2900)+(7980, 2900, 2900)+(7980, 2900, 2900)
оср.	Motor Output×Number of Units	kW	((1.2+4.5)×1)+((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)	((2.5+4.5)×1)+((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.75×1)+(0.75×2)+(0.75×2)	(0.35×2)+(0.75×2)+(0.75×2)
Ган	Air Flow Rate	m³/min	185+239+239	233+239+239
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)
Pipes	Gas Pipe	mm	φ41.3 (Brazing Connection)	φ41.3 (Brazing Connection)
Product Mass (Machine Weight) kg		kg	249+341+341	285+341+341
Safety Devices			High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	od		Deicer	Deicer
Capacity Control %		%	3~100	3~100
Refrigerant	Refrigerant Name		R-410A	R-410A
	Charge	kg	8.4+12.7+12.7	10.0+12.7+12.7
	Control		Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

 $\bigstar 3 \quad \text{Indoor temp.}: 20^{\circ}\text{CDB / outdoor temp.}: 7^{\circ}\text{CDB, } 6^{\circ}\text{CWB / Equivalent piping length}: 7.5\text{m, level difference}$: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Model Name (Combination Unit)			RXYQ50PY1(E)	RXYQ52PY1(E)
Model Name (Independent Unit)			RXYQ14PY1(E)+RXYQ18PY1(E)+RXYQ18PY1(E)	RXYQ16PY1(E)+RXYQ18PY1(E)+RXYQ18PY1(E)
★1 Cooling Capacity (19.5°CWB) kcal / h Btu / h kW		kcal / h	120,000	124,000
		Btu / h	474,000	491,000
		kW	139	144
★2 Cooling Ca	pacity (19.0°CWB)	kW	138	143
	kcal / h		136,000	140,000
★3 Heating Capacity Btu / I		Btu / h	539,000	556,000
		kW	158	163
Casing Color		_	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H	l×W×D)	mm	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchange	er		Cross Fin Coil	Cross Fin Coil
	Type		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72+10.53+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)	(13.72+10.53+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(6300, 2900×2)+(7980, 2900, 2900)+(7980, 2900, 2900)	(6300, 2900×2)+(7980, 2900, 2900)+(7980, 2900, 2900)
	Motor Output×Number of Units	kW	((0.3+4.5+4.5)×1)+((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)	((1.4+4.5+4.5)×1)+((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft Start	Soft Start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.35×2)+(0.75×2)+(0.75×2)	(0.35×2)+(0.75×2)+(0.75×2)
i aii	Air Flow Rate	m³/min	233+239+239	233+239+239
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	φ19.1 (Brazing Connection)
Pipes	Gas Pipe	mm	φ41.3 (Brazing Connection)	φ41.3 (Brazing Connection)
Product Mass (Machine Weight)	kg	329+341+341	329+341+341
Safety Devices	Safety Devices		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Method	Defrost Method		Deicer	Deicer
Capacity Control %		%	3~100	3~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge	kg	12.3+12.7+12.7	12.5+12.7+12.7
	Control		Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Model Name (Combination Unit)			RXYQ54PY1(E)	
Model Name (Independent Unit)			RXYQ18PY1(E)+RXYQ18PY1(E)+RXYQ18PY1(E)	
★1 Cooling Capacity (19.5°CWB) Btu		kcal / h	127,000	
		Btu / h	505,000	
		kW	148	
★2 Cooling Ca	pacity (19.0°CWB)	kW	147	
kca		kcal / h	146,000	
★3 Heating Ca	★3 Heating Capacity		580,000	
		kW	170	
Casing Color			Ivory White (5Y7.5/1)	
Dimensions: (H	l×W×D)	mm	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	
Heat Exchange	er		Cross Fin Coil	
	Туре		Hermetically Sealed Scroll Type	
	Piston Displacement	m³/h	(13.72+10.53+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)	
Comp.	Number of Revolutions	r.p.m	(7980, 2900, 2900)+(7980, 2900, 2900)+(7980, 2900, 2900)	
	Motor Output×Number of Units	kW	((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)+((3.0+4.5+4.5)×1)	
	Starting Method		Soft Start	
	Туре		Propeller Fan	
Fan	Motor Output	kW	(0.75×2)+(0.75×2)+(0.75×2)	
i aii	Air Flow Rate	m³/min	239+239+239	
	Drive		Direct Drive	
Connecting	Liquid Pipe	mm	φ19.1 (Brazing Connection)	
Pipes	Gas Pipe	mm	φ41.3 (Brazing Connection)	
Product Mass	(Machine Weight)	kg	341+341+341	
Safety Devices	;		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	
Defrost Method			Deicer	
Capacity Control		%	3~100	
Refrigerant	Refrigerant Name		R-410A	
	Charge	kg	12.7+12.7	
	Control		Electronic Expansion Valve	
Refrigerator Oil			Refer to the nameplate of compressor	
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Specifications Si34-601A

Heat Pump 50Hz High COP Series <RXYQ-PH>

Model Name			RXYQ16PHY1(E)	RXYQ18PHY1(E)
Model Name (Independent Unit)			RXYQ8PY1(E)+RXYQ8PY1(E)	RXYQ8PY1(E)+RXYQ10PY1(E)
★1 Cooling Capacity (19.5°CWB)		kcal / h	38,800	43,600
		Btu / h	154,000	173,000
		kW	45.1	50.7
★2 Cooling Capacity (19.0°CWB) kW		kW	44.8	50.4
kcal / h ★3 Heating Capacity Btu / h		kcal / h	43,000	48,600
		Btu / h	171,000	193,000
		kW	50	56.5
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (I	H×W×D)	mm	(1680×930×765)+(1680×930×765)	(1680×930×765)+(1680×930×765)
Heat Exchang	er		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72)	(13.72)+(13.72+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(7980)	(7980)+(6300,2900)
озр.	Motor Output×Number of Units	kW	(3.8×1)+(3.8×1)	(3.8×1)+((1.2+4.5)×1)
	Starting Method		Soft start	Soft start
	Type		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.75×1)+(0.75×1)	(0.75×1)+(0.75×1)
ran	Air Flow Rate	m³/min	180+180	180+185
	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe	mm	φ12.7(Brazing Connection)	φ15.9(Brazing Connection)
Pipes	Gas Pipe	mm	φ28.6(Brazing Connection)	φ28.6(Brazing Connection)
Product Mass	(Machine weight)	kg	205+205	205+249
Safety Devices			High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Method			Deicer	Deicer
Capacity Control %		%	10~100	8~100
Refrigerant	Refrigerant Name		R-410A	R-410A
	Charge	kg	7.7+7.7	7.7+8.4
	Control		Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Accessories			Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

 $\bigstar 1 \quad \text{Indoor temp.} : 27^{\circ}\text{CDB, } 19.5^{\circ}\text{CWB / outdoor temp.} : 35^{\circ}\text{CDB / Equivalent piping length} : 7.5\text{m, level}$

difference : 0m.

★2 Indoor temp. : 27°CDB, 19.0°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

 $\bigstar 3 \quad \text{Indoor temp.}: 20^{\circ}\text{CDB / outdoor temp.}: 7^{\circ}\text{CDB, } 6^{\circ}\text{CWB / Equivalent piping length}: 7.5\text{m, level difference}$

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Model Name			RXYQ24PHY1(E)	RXYQ26PHY1(E)
Model Name	(Independent Unit)		RXYQ8PY1(E)+RXYQ8PY1(E)+RXYQ8PY1(E)	RXYQ8PY1(E)+RXYQ8PY1(E)+RXYQ10PY1(E)
kcal /		kcal / h	58,100	63,000
		Btu / h	231,000	250,000
		kW	67.6	73.2
★2 Cooling C	y Capacity (19.0°CWB) kW 67.2 72.8 kcal / h 64,500 70,100		72.8	
		kcal / h	64,500	70,100
★3 Heating C	★3 Heating Capacity Bi		260,000	278,000
		kW	75	81.5
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H×W×D)	mm	(1680×930×765)+(1680×930×765)+(1680×930×765)	(1680×930×765)+(1680×930×765)+(1680×930×765)
Heat Exchang	jer		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72)+(13.72)	(13.72)+(13.72)+(13.72+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(7980)+(7980)	(7980)+(7980)+(6300,2900)
Comp.	Motor Output×Number of Units	kW	(3.8×1)+(3.8×1)+(3.8×1)	(3.8×1)+(3.8×1)+((1.2+4.5)×1)
	Starting Method		Soft start	Soft start
	Туре		Propeller Fan	Propeller Fan
Fon.	Motor Output	kW	(0.75×1)+(0.75×1)+(0.75×1)	(0.75×1)+(0.75×1)+(0.75×1)
ran	Air Flow Rate	m³/min	180+180+180	180+180+185
Fan	Drive		Direct Drive	Direct Drive
Connecting	Liquid Pipe		φ15.9(Brazing Connection)	φ19.1(Brazing Connection)
Pipes			φ34.9(Brazing Connection)	φ34.9(Brazing Connection)
Product Mass	(Machine weight)	kg	205+205+205	205+205+249
Safety Device	s		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	od		Deicer	Deicer
Capacity Control %		%	7~100	6~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge kg		7.7+7.7	7.7+7.7+8.4
Control		•	Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator C	rigerator Oil Refer to the nameplate of compressor Refer to the nameplate of		Refer to the nameplate of compressor	
Standard Acc	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp. : 27°CDB, 19.5°CWB / outdoor temp. : 35°CDB / Equivalent piping length : 7.5m, level difference : 0m.

*2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Model Name			RXYQ28PHY1(E)	RXYQ30PHY1(E)
Model Name (Independent Unit)			RXYQ8PY1(E)+RXYQ10PY1(E)+RXYQ12PY1(E)
★1 Cooling Capacity (19.5°CWB) kcal / h Btu / h		kcal / h	67,800	72,600
		Btu / h	269,000	288,000
		kW	78.8	84.4
r2 Cooling Capacity (19.0°CWB) kW		kW	78.3	83.9
		kcal / h	75,300	80,800
		Btu / h	299,000	321,000
		kW	87.5	94
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H	H×W×D)	mm	(1680×930×765)+(1680×930×765)+(1680×1240×765)	(1680×930×765)+(1680×930×765)+(1680×1240×765)
Heat Exchange	er		Cross Fin Coil	Cross Fin Coil
Type			Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72)+(13.72+10.53)	(13.72)+(13.72+10.53)+(13.72+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(7980)+(6300,2900)	(7980)+(6300,2900)+(6300,2900)
оср.	Motor Output×Number of Units	kW	(3.8×1)+(3.8×1)+((2.5+4.5)×1)	(3.8×1)+((1.2+4.5)×1)+((2.5+4.5)×1)
	Starting Method		Soft start	Soft start
	Туре		Propeller Fan	Propeller Fan
Eon	Motor Output	kW	(0.75×1)+(0.75×1)+(0.35×2)	(0.75×1)+(0.75×1)+(0.35×2)
Ган	Air Flow Rate	m³/min	180+180+233	180+185+233
Fan	Drive		Direct Drive	Direct Drive
Connecting	ting Liquid Pipe		φ19.1(Brazing Connection)	φ19.1(Brazing Connection)
Pipes	Gas Pipe	mm	φ34.9(Brazing Connection)	φ34.9(Brazing Connection)
Product Mass ((Machine weight)	kg	205+205+285	205+249+285
Safety Devices			High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Method	d		Deicer	Deicer
Capacity Control %		%	6~100	5~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge kg		7.7+7.7+10.0	7.7+8.5+10.0
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oil			Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acce	ssories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

			RXYQ32PHY1(E)	RXYQ34PHY1(E)
Model Name Model Name (Independent Unit)			RXYQ8PY1(E)+RXYQ12PY1(E)+RXYQ12PY1(E)	RXYQ10PY1(E)+RXYQ12PY1(E)+RXYQ12PY1(E)
★1 Cooling Capacity (19.5°CWB) ★2 Cooling Capacity (19.0°CWB) kW		kcal / h	77,300	82,200
		Btu / h	307,000	326,000
		kW	89.9	95.6
★2 Cooling Ca	pacity (19.0°CWB)	kW	89.4	95
		kcal / h	86,000	92,000
		Btu / h	341,000	365,000
		kW	100	107
Casing Color		•	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H	H×W×D)	mm	(1680×930×765)+(1680×1240×765)+(1680×1240×765)	(1680×930×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchange	er	•	Cross Fin Coil	Cross Fin Coil
Type			Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72)+(13.72+10.53)+(13.72+10.53)	(13.72+10.53)+(13.72+10.53)+(13.72+10.53)
Comp.	Number of Revolutions	r.p.m	(7980)+(6300,2900)+(6300,2900)	(6300,2900)+(6300,2900)+(6300,2900)
Somp.	Motor Output×Number of Units	kW	(3.8×1)+((2.5+4.5)×1)+((2.5+4.5)×1)	((1.2+4.5)×1)+((2.5+4.5)×1)+((2.5+4.5)×1)
	Starting Method		Soft start	Soft start
	Туре		Propeller Fan	Propeller Fan
Fon	Motor Output	kW	(0.75×1)+(0.35×2)+(0.35×2)	(0.75×1)+(0.35×2)+(0.35×2)
-aii	Air Flow Rate	m³/min	180+233+233	185+233+233
Fan	Drive		Direct Drive	Direct Drive
Connectina	cting Liquid Pipe		φ19.1(Brazing Connection)	φ19.1(Brazing Connection)
Connecting Liquid Pipe mm \text{919.1(Brazing Connection)} \\ Pipes \text{Gas Pipe} \text{mm} \text{94.9(Brazing Connection)} \\ \text{934.9(Brazing Connection)} \text{94.9(Brazing Connection)} \\ \text{1.1.1}		φ34.9(Brazing Connection)		
Product Mass	(Machine weight)	kg	205+285+285	249+285+285
Safety Devices	3		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Method	t		Deicer	Deicer
Capacity Control %		%	5~100	5~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge	kg	7.7+10.0+10.0	8.4+10.0+10.0
	Control		Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator Oi	I		Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

 $\bigstar 3 \quad \text{Indoor temp.}: 20^{\circ}\text{CDB / outdoor temp.}: 7^{\circ}\text{CDB, } 6^{\circ}\text{CWB / Equivalent piping length}: 7.5\text{m, level difference}$: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Model Name			RXYQ36PHY1(E)	RXYQ38PHY1(E)	
Model Name	(Independent Unit)		RXYQ12PY1(E)+RXYQ12PY1(E)+RXYQ12PY1(E)	RXYQ12PY1(E)+RXYQ12PY1(E)+RXYQ14PY1(E)	
★1 Cooling Capacity (19.5°CWB) kcal		kcal / h	87,700	92,900	
		Btu / h	348,000	368,000	
	kW g Capacity (19.0°CWB) kW kcal / h g Capacity Btu / h kW lor s: (HxWxD) mm (1680x1240x765) anger Type Herm		102	108	
★2 Cooling Ca	apacity (19.0°CWB)	kW	101	107	
		kcal / h	97,200	103,000	
★3 Heating Capacity		Btu / h	386,000	409,000	
		kW	113	120	
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	
Dimensions: (I	H×W×D)	mm	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	
Heat Exchang	er		Cross Fin Coil	Cross Fin Coil	
<u> </u>			Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type	
	Piston Displacement	m³/h	(13.72+10.53)+(13.72+10.53)+(13.72+10.53)	(13.72+10.53)+(13.72+10.53)+(13.72+10.53+10.53)	
Comp.	Number of Revolutions	r.p.m	(6300,2900)+(6300,2900)+(6300,2900)	(6300,2900)+(6300,2900)+(6300,2900,2900)	
сопр.	Motor Output×Number of Units	kW	((2.5+4.5)×1)+((2.5+4.5)×1)+((2.5+4.5)×1)	((2.5+4.5)×1)+((2.5+4.5)×1)+((0.3+4.5+4.5)×1)	
	Starting Method		Soft start	Soft start	
	Type		Propeller Fan	Propeller Fan	
Гол	Motor Output	kW	(0.35×2)+(0.35×2)+(0.35×2)	(0.35×2)+(0.35×2)+(0.35×2)	
ran	Air Flow Rate	m³/min	233+233+233	233+233+233	
Fan	Drive		Direct Drive	Direct Drive	
Connecting	Liquid Pipe	mm	φ19.1(Brazing Connection)	φ19.1(Brazing Connection)	
Pipes	necting S Liquid Pipe mm \$\phi 19.1(Brazing Connection) \$\phi 19.1(Brazing Connection) \$\phi 19.1(Brazing Connection) \$\phi 41.3(Brazing Connection) \$\		φ41.3(Brazing Connection)		
Product Mass	(Machine weight)	kg	285+285+285	285+285+329	
Safety Device	s	•	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	
Defrost Metho	d		Deicer	Deicer	
Capacity Cont	rol	%	5~100	4~100	
	Refrigerant Name		R-410A	R-410A	
Refrigerant	Charge kg		10.0+10.0+10.0	10.0+10.0+12.3	
Control		•	Electronic Expansion Valve	Electronic Expansion Valve	
Refrigerator O	il		Refer to the nameplate of compressor	Refer to the nameplate of compressor	
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps	
Drawing No.					

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Model Name			RXYQ40PHY1(E)	RXYQ42PHY1(E)
Model Name	(Independent Unit)	RXYQ12PY1(E)+RXYQ12PY1(E)+RXYQ16PY1(E) RXYQ12PY1(E)+RXYQ12PY1(E)+RXYQ		RXYQ12PY1(E)+RXYQ12PY1(E)+RXYQ18PY1(E)
★1 Cooling Capacity (19.5°CWB) kcal Btu /		kcal / h	97,200	101,000
		Btu / h	386,000	399,000
		kW	113	117
★2 Cooling C	apacity (19.0°CWB)	kW	112	116
		kcal / h	108,000	114,000
★3 Heating Capacity		Btu / h	427,000	450,000
		kW	125	132
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H×W×D)	mm	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchang	jer		Cross Fin Coil	Cross Fin Coil
Type			Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72+10.53)+(13.72+10.53)+(13.72+10.53+10.53)	(13.72+10.53)+(13.72+10.53)+(13.72+10.53+10.53)
Comp.	Number of Revolutions	r.p.m	(6300,2900)+(6300,2900)+(6300,2900,2900)	(6300,2900)+(6300,2900)+(7980,2900,2900)
Comp.	Motor Output×Number of Units	kW	((2.5+4.5)×1)+((2.5+4.5)×1)+((1.4+4.5+4.5)×1)	((2.5+4.5)×1)+((2.5+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft start	Soft start
	Туре		Propeller Fan	Propeller Fan
Fon.	Motor Output	kW	(0.35×2)+(0.35×2)+(0.35×2)	(0.35×2)+(0.35×2)+(0.75×2)
ran	Air Flow Rate	m³/min	233+233+233	233+233+239
Fan	Drive		Direct Drive	Direct Drive
Connecting	cting Liquid Pipe mm Gas Pipe mm		φ19.1(Brazing Connection)	φ19.1(Brazing Connection)
Pipes			φ41.3(Brazing Connection)	φ41.3(Brazing Connection)
Product Mass	(Machine weight)	kg	285+285+329	285+285+341
Safety Device	es		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	od		Deicer	Deicer
Capacity Con	Capacity Control %		4~100	4~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge kg		10.0+10.0+12.5	10.0+10.0+12.7
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator C	Refrigerator Oil		Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acc	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				
			•	•

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

 $\bigstar 3 \quad \text{Indoor temp.}: 20^{\circ}\text{CDB / outdoor temp.}: 7^{\circ}\text{CDB, } 6^{\circ}\text{CWB / Equivalent piping length}: 7.5\text{m, level difference}$: 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Model Name			RXYQ44PHY1(E)	RXYQ46PHY1(E)	
Model Name	(Independent Unit)		RXYQ12PY1(E)+RXYQ16PY1(E)+RXYQ16PY1(E)	RXYQ12PY1(E)+RXYQ16PY1(E)+RXYQ18PY1(E)	
k		kcal / h	108,000	111,000	
		Btu / h	427,000	440,000	
		KW 125 y (19.0°CWB) kW 124 kcal / h 119,000 y Btu / h 471,000 kW 138 lvory White (5Y7. D) mm (1680×1240×765)+(1680×1240×76 Cross Fin Coil e		129	
★2 Cooling Ca	apacity (19.0°CWB)	kW	124	128	
		kcal / h	119,000	124,000	
★3 Heating Capacity		Btu / h	471,000	491,000	
		kW	138	144	
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	
Dimensions: (I	H×W×D)	mm	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	
Heat Exchang	er	•	Cross Fin Coil	Cross Fin Coil	
	Type		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type	
	Piston Displacement	m³/h	(13.72+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)	(13.72+10.53)+(13.72+10.53+10.53)+(13.72+10.53+10.53)	
Comp.	Number of Revolutions	r.p.m	(6300,2900)+(6300,2900,2900)+(6300,2900,2900)	(6300,2900)+(6300,2900,2900)+(7980,2900,2900)	
Comp.	Motor Output×Number of Units	kW	((2.5+4.5)×1)+((1.4+4.5+4.5)×1)+((1.4+4.5+4.5)×1)	((2.5+4.5)×1)+((1.4+4.5+4.5)×1)+((3.0+4.5+4.5)×1)	
	Starting Method		Soft start	Soft start	
	Type		Propeller Fan	Propeller Fan	
Eon	Motor Output	kW	(0.35×2)+(0.35×2)+(0.35×2)	(0.35×2)+(0.35×2)+(0.75×2)	
ган	Air Flow Rate	m³/min	233+233+233	233+233+239	
Fan	Drive		Direct Drive	Direct Drive	
Connecting	Liquid Pipe	mm	φ19.1(Brazing Connection)	φ19.1(Brazing Connection)	
Pipes	Connecting Liquid Pipe mm \$\\displays19.1(\text{Brazing Connection})\$\\displays19.1(\text{Brazing Connection})\$		φ41.3(Brazing Connection)		
Product Mass	(Machine weight)	kg	285+329+329	285+329+341	
Safety Devices	s		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	
Defrost Metho	d		Deicer	Deicer	
Capacity Cont	rol	%	4~100	3~100	
	Refrigerant Name		R-410A	R-410A	
Refrigerant	Charge kg		10.0+12.5+12.5	10.0+12.5+12.7	
Control			Electronic Expansion Valve	Electronic Expansion Valve	
Refrigerator O	il		Refer to the nameplate of compressor	Refer to the nameplate of compressor	
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps	
Drawing No.					

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
 ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference : 0m.

★3 Indoor temp. : 20°CDB / outdoor temp. : 7°CDB, 6°CWB / Equivalent piping length : 7.5m, level difference : 0m.

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Model Name			RXYQ50PHY1(E)	
Model Name (Independent Unit)			RXYQ16PY1(E)+RXYQ16PY1(E)+RXYQ16PY1(E)	RXYQ16PY1(E)+RXYQ16PY1(E)+RXYQ18PY1(E)
★1 Cooling Capacity (19.5°CWB) kc		kcal / h	117,000	120,000
		Btu / h	464,000	478,000
		kW	136	140
★2 Cooling Ca	pacity (19.0°CWB)	kW	135	139
		kcal / h	129,000	134,000
★3 Heating Ca	★3 Heating Capacity B		512,000	532,000
		kW	150	156
Casing Color		•	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)
Dimensions: (H	H×W×D)	mm	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)	(1680×1240×765)+(1680×1240×765)+(1680×1240×765)
Heat Exchange	er		Cross Fin Coil	Cross Fin Coil
	Туре		Hermetically Sealed Scroll Type	Hermetically Sealed Scroll Type
	Piston Displacement	m³/h	(13.72+10.53+10.53)+(13.72+10.53+10.53)+(13.72+10.53 +10.53)	(13.72+10.53+10.53)+(13.72+10.53+10.53)+(13.72+10.53 +10.53)
Comp.	Number of Revolutions	r.p.m	(6300,2900,2900)+(6300,2900,2900)+(6300,2900,2900)	(6300,2900,2900)+(6300,2900,2900)+(7980,2900,2900)
	Motor Output×Number of Units	kW	((1.4+4.5+4.5)×1)+((1.4+4.5+4.5)×1)+((1.4+4.5+4.5)×1)	((1.4+4.5+4.5)×1)+((1.4+4.5+4.5)×1)+((3.0+4.5+4.5)×1)
	Starting Method		Soft start	Soft start
	Туре		Propeller Fan	Propeller Fan
Fan	Motor Output	kW	(0.35×2)+(0.35×2)+(0.35×2)	(0.35×2)+(0.35×2)+(0.75×2)
ran	Air Flow Rate	m³/min	233+233+233	233+233+239
	Drive		Direct Drive	Direct Drive
Connecting			φ19.1(Brazing Connection)	φ19.1(Brazing Connection)
Pipes	Gas Pipe	mm	φ41.3(Brazing Connection)	φ41.3(Brazing Connection)
Product Mass	(Machine weight)	kg	329+329+329	329+329+341
Safety Devices	3		High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector	High Pressure Switch, Fan Driver Overload Protector, Over Current Relay, Inverter Overload Protector
Defrost Metho	d		Deicer	Deicer
Capacity Cont	Capacity Control %		3~100	3~100
	Refrigerant Name		R-410A	R-410A
Refrigerant	Charge	kg	12.5+12.5+12.5	12.5+12.5+12.7
Control			Electronic Expansion Valve	Electronic Expansion Valve
Refrigerator O	1		Refer to the nameplate of compressor	Refer to the nameplate of compressor
Standard Acce	essories		Installation Manual, Operation Manual, Connection Pipes, Clamps	Installation Manual, Operation Manual, Connection Pipes, Clamps
Drawing No.				

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference 0 m

4 The units with anti-corrosion treatment will be available as standard. Please specify the suffix "E" as RXYQ5PY1E.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

1.2 **Indoor Units**

Ceiling Mounted Cassette Type (Double Flow)

Dimensions: (H-Wk/D)	Model			FXCQ20MVE	FXCQ25MVE	FXCQ32MVE	FXCQ40MVE
Real			kcal/h	2,000	2,500	3,200	4,000
**3 Heating Capacity (19.0°CWB)			Btu/h	7,800	9,900	12,600	16,000
Real	_		kW	2.3	2.9	3.7	4.7
#3 Heating Capacity Bluth 8,500 10,900 13,600 17,100	★2 Cooling C	Capacity (19.0°CWB)	kW	2.2	2.8	3.6	4.5
Summersions: H-WW-D Summarsions: H-W-W-D Summarsions: H-W-W-D			kcal/h	2,200	2,800	3,400	4,300
Casing	★3 Heating C	Capacity	Btu/h	8,500	10,900	13,600	17,100
Dimensions: (H-Wk/D)	-		kW	2.5	3.2	4.0	5.0
Rows/StagesxFin Pitch	Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Face Area	Dimensions:	(H×W×D)	mm	305×775×600	305×775×600	305×775×600	305×990×600
Model	Coil (Cross	Rows×Stages×Fin Pitch	mm	2×10×1.5	2×10×1.5	2×10×1.5	2×10×1.5
Type	Fin Coil)	Face Area	m²	2×0.100	2×0.100	2×0.100	2×0.145
Motor Output × Number W		1 400 / 1104		D17K2AA1	D17K2AB1	D17K2AB1	2D17K1AA1
Fan				Sirocco Fan	Sirocco Fan	Sirocco Fan	Sirocco Fan
Air Flow Rate (H/L)	Fan	Motor Output × Number of Units	W	10×1	15×1	15×1	20×1
Competitive Direct Drive Direc		A' - E' (11/1)	m³/min	7/5	9/6.5	9/6.5	12/9
Temperature Control Microprocessor Thermostat for Cooling and Heating Sound Absorbing Thermal Insulation Material Glass Wool/Urethane Foam Glass W		Air Flow Rate (H/L)	cfm	247/177	318/230	318/230	424/318
Sound Absorbing Thermal Insulation Material Sound Absorbing Thermal Insulation Material Glass Wool/Urethane Foam Liquid Pipes mm 06.4 (Flare Connection) 06.4 (Flare		Drive		Direct Drive	Direct Drive	Direct Drive	Direct Drive
Liquid Pipes	Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Piping Connections Gas Pipes mm	Sound Absor	bing Thermal Insulation Ma	terial	Glass Wool/Urethane Foam	Glass Wool/Urethane Foam	Glass Wool/Urethane Foam	Glass Wool/Urethane Foam
Drain Pipe		Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)
Connections Drain Pipe mm (P25 (External Dia. 32) (Internal Dia. 32) VP25 (External Dia. 32) (Internal Dia. 25) External Dia. 32 (Internal Dia. 25) VP25 (External Dia. 32) (Internal Dia. 25) External Dia. 32 (Internal Dia. 25) Texternal Protector for Fan Motor External Dia. 32 (Internal Dia. 25) Texternal Dia. 25 (Internal Dia. 25) External Dia. 32 (Internal Dia. 25) External Dia. 25 (Internal Dia. 25) External Dia. 25 (Internal Dia. 25) Texternal Dia. 25 (Internal Dia. 25) External Dia. 25 (Internal Dia. 25) External Dia. 25 (Internal Dia. 25 (Internal Dia. 25) External Dia. 25 (Internal Dia. 25 (Internal Dia. 25) Texternal Dia. 25 (Internal Dia. 25 (Internal Dia. 25) Texternal Dia. 25 (Internal Dia. 25 (Internal Dia. 25 (Internal Dia. 25) Texternal Dia. 25 (I	Pining	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)
#5 Sound Level (H/L) (220V) dBA 32/27 34/28 34/28 34/28 34/29 Safety Devices Fuse, Thermal Protector for Fan Motor	Connections	Drain Pipe	mm	/ External Dia. 32 \	/ External Dia. 32 \	/ External Dia. 32 \	/ External Dia. 32 \
Safety Devices Fuse, Thermal Protector for Fan Motor Fan	Machine Wei	ght (Mass)	kg	26	26	26	31
Fan Motor Electronic Expansion Valve Factor Spansion Valve Factor Spansion Valve Factor Nation Valve Factor Spansion Valve Factor Span	★5 Sound Le	vel (H/L) (220V)	dBA	32/27	34/28	34/28	34/29
Connectable outdoor unit R-410A P Series R-410A P Serie	Safety Device	es					Fuse, Thermal Protector for Fan Motor
Model BYBC32G-W1 BYBC32G-W1 BYBC32G-W1 BYBC32G-W1 BYBC50G-W1	Refrigerant C	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Panel Color White (10Y9/0.5) White (10Y9	Connectable	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series
Decoration Panels (Option) Dimensions: (HxWxD) mm 53x1,030x680 53x1,030x680 53x1,030x680 53x1,030x680 53x1,030x680 53x1,245x680 Resin Net (with Mold Resistant) Resin Net (with Mold Resistant) Weight kg 8 8 8 8 8 8.5 Operation Manual, Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Titting, Washer Fixing Titting		Model		BYBC32G-W1	BYBC32G-W1	BYBC32G-W1	BYBC50G-W1
Panels (Option) Air Filter Resin Net (with Mold Resistant) Weight Resin Net (with Mold Resistant) Weight Resin Net (with Mold Resistant) Operation Manual, Installation Manual, Paper Pattern for Installation, Masher for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Dimensions: (HXWXD) Resin Net (with Mold Resistant) Operation Manual, Installation Manual, Paper Pattern for Installation, Masher for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Drain Hose, Insulation for Fitting, Washer Fixing		Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)
Coption Air Filter Resin Net (with Mold Resistant)		Dimensions: (H×W×D)	mm	53×1,030×680	53×1,030×680	53×1,030×680	53×1,245×680
Operation Manual, Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Operation Manual, Paper Pattern for Installation, Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Pattern for Installation, Washer Fixing Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Fixing Pattern for Installation, Washer Fixing Pattern for Installation, Pattern for Installation, Washer Fixing Pattern for Installation, Washer Fixing Pattern for Installation, Washer Fixing Pattern for Installation, Pattern for Installation, Washer Fixing Pattern for Installation, Pattern fo		Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)
Installation Manual, Paper Pattern for Installation, Manual, Paper Pattern for Installation, Washer for Hanging Standard Accessories Installation Manual, Paper Pattern for Installation, Washer for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer fixing		Weight	kg	8	8	8	8.5
Plates, Sealing Pads, Plates, Sealing Pads, Plates, Sealing Pads, Plates, Sealing Pads,	Standard Accessories			Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates, Sealing Pads.	Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates. Sealing Pads.	Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates, Sealing Pads.	Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing
Drawing No. 3D039413	Drawing No.				3D03	39413	

Notes:

 $\bigstar 1 \quad \text{Indoor temp.}: 27^{\circ}\text{CDB, } 19.5^{\circ}\text{CWB / outdoor temp.}: 35^{\circ}\text{CDB / Equivalent piping length: } 7.5\text{m, level }$ difference: 0m.

 $\bigstar 2 \quad \text{Indoor temp.} : 27^{\circ}\text{CDB, } 19.0^{\circ}\text{CWB / outdoor temp.} : 35^{\circ}\text{CDB / Equivalent piping length: } 7.5\text{m, level}$ difference: 0m.

 $\star 3$ Indoor temp. : 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: Om. (Heat pump only)
4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
*5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation,

these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Ceiling Mounted Cassette Type (Double Flow)

Model		FXCQ50MVE	FXCQ63MVE	FXCQ80MVE	FXCQ125MVE	
		kcal/h	5,000	6,300	8,000	12,500
★1 Cooling Capacity (19.5°CWB)		Btu/h	19,800	24,900	31,700	49,500
J	,	kW	5.8	7.3	9.3	14.5
★2 Cooling C	apacity (19.0°CWB)	kW	5.6	7.1	9.0	14.0
		kcal/h	5,400	6,900	8,600	13,800
★3 Heating Capacity Btu/		Btu/h	21,500	27,300	34,100	54,600
		kW	6.3	8.0	10.0	16.0
Casing		ı	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: (H×W×D)	mm	305×990×600	305×1,175×600	305×1,665×600	305×1,665×600
Coil (Cross	Rows×Stages×Fin Pitch	mm	2×10×1.5	2×10×1.5	2×10×1.5	2×10×1.5
Fin Coil)	Face Area	m²	2×0.145	2×0.184	2×0.287	2×0.287
	Model	L	2D17K1AA1	2D17K2AA1VE	3D17K2AA1	3D17K2AB1
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	Sirocco Fan
Fan	Motor Output × Number of Units	W	20×1	30×1	50×1	85×1
	Air Flour Date (U/L)	m³/min	12/9	16.5/13	26/21	33/25
	Air Flow Rate (H/L)	cfm	424/318	582/459	918/741	1,165/883
	Drive	•	Direct Drive	Direct Drive	Direct Drive	Direct Drive
Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	oing Thermal Insulation Ma	terial	Glass Wool/Urethane Foam	Glass Wool/Urethane Foam	Glass Wool/Urethane Foam	Glass Wool/Urethane Foam
	Liquid Pipes mm		φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)
Connections	Drain Pipe	mm	VP25 (External Dia. 32 \ Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)
Machine Weig	ght (Mass)	kg	32	35	47	48
★5 Sound Lev	vel (H/L)	dBA	34/29	37/32	39/34	44/38
Safety Device	es .		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Connectable of	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series
	Model		BYBC50G-W1	BYBC63G-W1	BYBC125G-W1	BYBC125G-W1
	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)
Decoration Panels	Dimensions: (H×W×D)	mm	53×1,245×680	53×1,430×680	53×1,920×680	53×1,920×680
(Option)	Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)
	Weight	kg	8.5	9.5	12	12
Standard Accessories		Operation Manual, Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Paper Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Paper Installation Manual, Paper Pattern for Installation, Washer for Hanging Brackets, Clamp Metal, Drain Hose, Insulation for Fitting, Washer Fixing Plates, Sealing Pads, Clamps, Screws, Washers.	
Drawing No.					39413	

Notes:

 \star 1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference: 0m.
★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference:
0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

*5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Ceiling Mounted Cassette Type (Multi-flow)

Model			FXFQ25MVE	FXFQ32MVE	FXFQ40MVE	FXFQ50MVE
		kcal/h	2,500	3,200	4,000	5,000
★3 Heating Capacity Casing Dimensions: (HxWxD) Coil (Cross Fin Coil) Face Area Model Type Motor Output × Number of Units Air Flow Rate (H/L)		Btu/h	9,900	12,600	16,000	19,800
		kW	2.9	3.7	4.7	5.8
★2 Cooling Capacity (19.0°CWB) ★3 Heating Capacity		kW	2.8	3.6	4.5	5.6
		kcal/h	2,800	3,400	4,300	5,400
★3 Heating Capacity		Btu/h	10,900	13,600	17,100	21,500
			3.2	4.0	5.0	6.3
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: (H×W×D)	mm	246×840×840	246×840×840	246×840×840	246×840×840
Coil (Cross	Rows×Stages×Fin Pitch	mm	2×8×1.2	2×8×1.2	2×8×1.2	2×8×1.2
Fin Coil)	Face Area	m²	0.363	0.363	0.363	0.363
	Model		QTS46D14M	QTS46D14M	QTS46D14M	QTS46D14M
	Туре		Turbo Fan	Turbo Fan	Turbo Fan	Turbo Fan
Fan		W	30×1	30×1	30×1	30×1
	Air Flour Date (LI/L)	m³/min	13/10	13/10	15/11	16/11
	Air Flow Rate (H/L)		459/353	459/353	530/388	565/388
	Drive		Direct Drive	Direct Drive	Direct Drive	Direct Drive
Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absort	oing Thermal Insulation Ma	terial	Polyurethane Form	Polyurethane Form	Polyurethane Form	Polyurethane Form
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)
Connections	Drain Pipe	mm	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32) (Internal Dia. 25)	VP25 (External Dia. 32) (Internal Dia. 25)	VP25 (External Dia. 32) Internal Dia. 25)
Machine Wei	ght (Mass)	kg	24	24	24	24
★5 Sound Le	vel (H/L) (220V)	dBA	30/27	30/27	31/27	32/27
Safety Device	es	•	Fuse	Fuse	Fuse	Fuse
Refrigerant C	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Connectable	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series
	Model		BYCP125D-W1	BYCP125D-W1	BYCP125D-W1	BYCP125D-W1
	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)
Decoration Panels	Dimensions: (H×W×D)	mm	45×950×950	45×950×950	45×950×950	45×950×950
(Option)	Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)
	Weight	kg	5.5	5.5	5.5	5.5
Standard Accessories		Operation manual, Installation manual, Paper pattern for installation, Drain nose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	Operation manual, Installation manual, Paper pattern for installation, Drain nose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	Operation manual, Installation manual, Paper pattern for installation, Drain nose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	Operation manual, Installation manual, Paper pattern for installation, Drain nose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	
Drawing No.			, , ,	3D09	38812	<u>. </u>

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

Chapacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Ceiling Mounted Cassette Type (Multi-flow)

Model			FXFQ63MVE	FXFQ80MVE	FXFQ100MVE	FXFQ125MVE
kcal/h		6,300	8,000	10,000	12,500	
★1 Cooling Capacity (19.5°CWB)		Btu/h	24,900	31.700	39.600	49.500
3 -	,	kW	7.3	9.3	11.6	14.5
★2 Cooling Capacity (19.0°CWB) ★3 Heating Capacity Casing Dimensions: (HxWxD) Coil (Cross Fin Coil) Face Area Model Tyne		kW	7.1	9.0	11.2	14.0
	,	kcal/h	6,900	8,600	10,800	13,800
		Btu/h	27,300	34,100	42,700	54,600
			8.0	10.0	12.5	16.0
Casing		l	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: (H×W×D)	mm	246×840×840	246×840×840	288×840×840	288×840×840
Coil (Cross	Rows×Stages×Fin Pitch	mm	2×10×1.2	2×10×1.2	2×12×1.2	2×12×1.2
Fin Coil)	Face Area	m²	0.454	0.454	0.544	0.544
	Model	l	QTS46D14M	QTS46D14M	QTS46C17M	QTS46C17M
	Туре		Turbo Fan	Turbo Fan	Turbo Fan	Turbo Fan
Fan	Motor Output × Number of Units	W	30×1	30×1	120×1	120×1
	Air Flam Data (UV)	m³/min	18.5/14	20/15	26/21	30/24
	Air Flow Rate (H/L)	cfm	653/494	706/530	918/741	1,059/847
Drive			Direct Drive	Direct Drive	Direct Drive	Direct Drive
Temperature Control		Microprocessor Thermostat for Cooling and Heating				
Sound Absorb	oing Thermal Insulation Mat	terial	Polyurethane Form	Polyurethane Form	Polyurethane Form	Polyurethane Form
	Liquid Pipes	mm	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)
Piping	Gas Pipes	mm	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)
Connections	Drain Pipe	mm	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)
Machine Weig	ht (Mass)	kg	25	25	29	29
★5 Sound Lev	vel (H/L)	dBA	33/28	36/31	39/33	42/36
Safety Device	S		Fuse	Fuse	Fuse	Fuse
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Connectable of	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series
	Model		BYCP125D-W1	BYCP125D-W1	BYCP125D-W1	BYCP125D-W1
_	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)
Decoration Panels	Dimensions: (H×W×D)	mm	45×950×950	45×950×950	45×950×950	45×950×950
(Option)	Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)
	Weight	kg	5.5	5.5	5.5	5.5
Standard Accessories		Operation manual, Installation manual, Paper pattern for installation, Drain hose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	Operation manual, Installation manual, Paper pattern for installation, Drain nose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	Operation manual, Installation manual, Paper pattern for installation, Drain hose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	Operation manual, Installation manual, Paper pattern for installation, Drain hose, Clamp metal, Washer fixing plate, Sealing pads, Clamps, Screws, Washer for hanging bracket, Insulation for fitting.	
Drawing No.				3D03	88812	

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae

kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

600×600 Ceiling Mounted Cassette Type (Multi Flow)

Model		FXZQ20M7V1B	FXZQ25M7V1B	FXZQ32M7V1B		
kcal/h		2,000	2,500	3,150		
★1 Cooling Capacity (19.5°CWB) ★2 Cooling Capacity (19.0°CWB)		Btu/h	7,900	9,900	12,500	
		kW	2.3	2.9	3.7	
★2 Cooling Ca	apacity (19.0°CWB)	kW	2.2	2.8	3.6	
		kcal/h	2,200	2,800	3,400	
★3 Heating Capacity Btu/h		Btu/h	8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing		•	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (I	H×W×D)	mm	260×575×575	260×575×575	260×575×575	
Coil (Cross	Rows×Stages×Fin Pitch	mm	2×10×1.5	2×10×1.5	2×10×1.5	
Fin Coil)	Face Area	m²	0.269	0.269	0.269	
	Model	•	QTS32C15M	QTS32C15M	QTS32C15M	
	Туре		Turbo Fan	Turbo Fan	Turbo Fan	
Fan	Motor Output × Number of Units	W	55×1	55×1	55×1	
	Air Flow Date (U/L)	m³/min	9/7	9/7	9.5/7.5	
	Air Flow Rate (H/L)	cfm	318/247	318/247	335/265	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature 0	emperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	terial	Foamed Polystyrene/ Foamed Polyethylene	Foamed Polystyrene/ Foamed Polyethylene	Foamed Polystyrene/ Foamed Polyethylene	
	Liquid Pipes mm		φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping	Gas Pipes mm		φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
Connections	Drain Pipe mm		VP20 (External Dia. 26) Internal Dia. 20	VP20 (External Dia. 26) Internal Dia. 20	VP20 (External Dia. 26) Internal Dia. 20)	
Machine Weig	ht (Mass)	kg	18	18	18	
★5 Sound Lev	/el (H/L) (230V)	dBA	30/25	30/25	32/26	
Safety Devices	S		Fuse	Fuse	Fuse	
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable of	outside unit		R-410A M(A) Series	R-410A M(A) Series	R-410A M(A) Series	
	Model		BYFQ60BW1	BYFQ60BW1	BYFQ60BW1	
	Panel Color		White (Ral 9010)	White (Ral 9010)	White (Ral 9010)	
Decoration Panels	Dimensions: (H×W×D)	mm	55×700×700	55×700×700	55×700×700	
(Option)	Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Weight	kg	2.7	2.7	2.7	
Standard Accessories		Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Washer Fixing Plate, Sealing Pads, Clamps, Screws, Washer for Hanging Bracket, Insulation for Fitting.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Washer Fixing Plate, Sealing Pads, Clamps, Screws, Washer for Hanging Bracket, Insulation for Fitting.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Washer Fixing Plate, Sealing Pads, Clamps, Screws, Washer for Hanging Bracket, Insulation for Fitting.		
Drawing No.			3D038929A			

Notes:

 $\bigstar 1 \quad \text{Indoor temp.}: 27^{\circ}\text{CDB, } 19.5^{\circ}\text{CWB / outside temp.}: 35^{\circ}\text{CDB / Equivalent piping length: } 7.5\text{m, level }$ difference: 0m. *2 Indoor temp.: 27°CDB, 19.0°CWB / outside temp.: 35°CDB / Equivalent piping length: 7.5m, level

difference: 0m.

 $\bigstar 3 \quad \text{Indoor temp.}: 20^{\circ}\text{CDB} \, / \, \, \text{outside temp.}: 7^{\circ}\text{CDB, } 6^{\circ}\text{CWB} \, / \, \, \text{Equivalent piping length; 7.5m, level difference;}$ 0m. (Heat pump only)

Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 Acpacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

600×600 Ceiling Mounted Cassette Type (Multi Flow)

Model			FXZQ40M7V1B	FXZQ50M7V1B	
		kcal/h	4,000	5,000	
★1 Cooling Ca	apacity (19.5°CWB)	Btu/h	15,900	19,900	
	kW		4.7	5.8	
★2 Cooling Ca	apacity (19.0°CWB)	kW	4.5	5.6	
		kcal/h	4,300	5,400	
★3 Heating C	apacity	Btu/h	17,000	21,500	
		kW	5.0	6.3	
Casing		•	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (H×W×D)	mm	260×575×575	260×575×575	
Coil (Cross	Rows×Stages×Fin Pitch	mm	2×10×1.5	2×10×1.5	
Fin Coil)	Face Area	m²	0.269	0.269	
	Model	•	QTS32C15M	QTS32C15M	
	Туре		Turbo Fan	Turbo Fan	
Fan	Motor Output × Number of Units	W	55×1	55×1	
	Air Flow Rate (H/L)	m³/min	11/8	14/10	
	All Flow hate (H/L)	cfm	388/282	494/353	
	Drive		Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	terial	Foamed Polystyrene/Foamed Polyethylene	Foamed Polystyrene/Foamed Polyethylene	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
Connections	Drain Pipe	mm	VP20 (External Dia. 26) Internal Dia. 20	VP20 (External Dia. 26) Internal Dia. 20	
Machine Weig	ht (Mass)	kg	18	18	
★5 Sound Lev	el (H/L) (230V)	dBA	36/28	41/33	
Safety Device	S		Fuse	Fuse	
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	
Connectable of	outside unit		R-410A M(A) Series	R-410A M(A) Series	
	Model		BYFQ60BW1	BYFQ60BW1	
	Panel Color		White (Ral 9010)	White (Ral 9010)	
Decoration Panels	Dimensions: (H×W×D)	mm	55×700×700	55×700×700	
(Option)	Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Weight	kg	2.7	2.7	
Standard Acce	Standard Accessories		Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Washer Fixing Plate, Sealing Pads, Clamps, Screws, Washer for Hanging Bracket, Insulation for Fitting. Operation Manual, Installation Manual, Paper Pat Installation, Drain Hose, Clamp Metal, Washer Fixing Plate, Sealing Pads, Clamps, Screws, Washer for Hanging Bracket, Insulation for Fitting.		
Drawing No.			3D038929A		

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outside temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m

★2 Indoor temp.: 27°CDB, 19.0°CWB / outside temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outside temp.: 7°CDB, 6°CWB / Equivalent piping length; 7.5m, level difference; 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Ceiling Mounted Cassette Corner Type

Model			FXKQ25MAVE	FXKQ32MAVE	FXKQ40MAVE	FXKQ63MAVE
		kcal/h	2.500	3.200	4.000	6.300
+1 Cooling (Capacity (19.5°CWB)	Btu/h	9,900	12,600	16,000	24,900
x i ocomig c	supuoity (10.0 OTTD)	kW	2.9	3.7	4.7	7.3
+2 Cooling (Capacity (19.0°CWB)	kW	2.8	3.6	4.5	7.1
AZ Oooming C	papacity (13.0 OVVD)	kcal/h	2,800	3,400	4,300	6,900
★3 Heating (Canacity	Btu/h	10.900	13.600	17,100	27,300
Ao i loating c	эараону	kW	3.2	4.0	5.0	8.0
Casing		IXVV	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions:	(H>W>D)	mm	215×1,110×710	215×1.110×710	215×1,110×710	215×1,310×710
	Rows×Stages×Fin Pitch	mm	2×11×1.75	2×11×1.75	2×11×1.75	3×11×1.75
Coil (Cross Fin Coil)	Face Area	m²	0.180	0.180	0.180	0.226
	Model	ш	3D12H1AN1V1	3D12H1AN1V1	3D12H1AP1V1	4D12H1AJ1V1
	Type		Sirocco Fan	Sirocco Fan	Sirocco Fan	Sirocco Fan
	Motor Output × Number	l				
Fan	of Units	W	15×1	15×1	20×1	45×1
	Air Flow Rate (H/L)	m³/min	11/9	11/9	13/10	18/15
	All Flow Flate (FVL)	cfm	388/318	388/318	459/353	635/530
	Drive		Direct Drive	Direct Drive	Direct Drive	Direct Drive
Temperature	Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating
Sound Absor	bing Thermal Insulation Ma	terial	Polyethylene Foam	Polyethylene Foam	Polyethylene Foam	Polyethylene Foam
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)
Pipina	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)
Piping Connections	Drain Pipe	mm	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)
Machine Wei	ght (Mass)	kg	31	31	31	34
★5 Sound Le	evel (H/L) (220V)	dBA	38/33	38/33	40/34	42/37
Safety Device	es		Fuse, Thermal Fuse for Fan Motor	Fuse, Thermal Fuse for Fan Motor	Fuse, Thermal Fuse for Fan Motor	Fuse, Thermal Fuse for Fan Motor
Refrigerant C	Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Connectable	Outdoor Units		R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series
	Model		BYK45FJW1	BYK45FJW1	BYK45FJW1	BYK71FJW1
	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)
Decoration Panels	Dimensions: (H×W×D)	mm	70×1,240×800	70×1,240×800	70×1,240×800	70×1,440×800
(Option)	Air Filter		Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)
	Weight	kg	8.5	8.5	8.5	9.5
Standard Accessories		Operation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Positioning Jig for Installation, Insulation for Hanger Bracket, Air Outlet Blocking Pad.	Operation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Positioning Jig for Installation, Insulation for Hanger Bracket, Air Outlet Blocking Pad.	Operation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Positioning Jig for Installation, Insulation for Hanger Bracket, Air Outlet Blocking Pad.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Positioning Jig for Installation, Insulation for Hanger Bracket, Air Outlet Blocking Pad.	
Drawing No.			<u> </u>		8813A	<u>. </u>
Diawing No.						

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

 $\bigstar 2$ Indoor temp. : 27°CDB, 19.0°CWB / outdoor temp. : 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured at a point 1m in front of the unit and 1m downward. During actual operation, these values are normally somewhat higher as a result of ambient conditions. Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Slim Ceiling Mounted Duct Type (with Drain Pump)

Model			FXDQ20NAVE FXDQ25NAVE		FXDQ32NAVE	
		kcal/h	2,000	2,500	3,200	
★1 Cooling Ca	apacity (19.5°CWB)	Btu/h	7,800	9,900	12,600	
		kW	2.3	2.3 2.9		
★2 Cooling Ca	apacity (19.0°CWB)	kW	2.2	2.8	3.6	
		kcal/h	2,200	2,800	3,400	
★3 Heating Ca	apacity	Btu/h	8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (I	H×W×D)	mm	200×900×620	200×900×620	200×900×620	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	2×12×1.5	2×12×1.5	2×12×1.5	
Fin Coil)	Face Area	m²	0.176	0.176	0.176	
	Model		_	_	_	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units		62×1	62×1	62×1	
	Air Flow Rate (H/L)	m³/min	9.5/7.5	9.5/7.5	10.5/8.5	
	External Static Pressure	Pa	44-15 ★5	44-15 ★5	44-15 ★5	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mate	erial	Foamed Polyethylene Foamed Polyethylene		Foamed Polyethylene	
Air Filter			Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
Connections	Drain Pipe	mm	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	
Machine Weig	ht (Mass)	kg	26	26	26	
★6 Sound Lev	el (H/L)	dBA	33/29	33/29	33/29	
Safety Devices		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor		
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Standard Accessories		Operation Manual, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	Operation Manual Operation Manual			
Drawing No.			Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Somewhat of the Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Somewhat of Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter 3D051253			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 External static pressure is changeable to set by the remote controller this pressure means "High static pressure - Standard static pressure".

★6 The operation sound levels are the conversion values in anechoic chamber. In practice, the sound tend to be larger than the specified values due to ambient noise or reflections. When the place of suction is changed to the bottom suction, the sound level will increase by approx. 5dBA. Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Slim Ceiling Mounted Duct Type (with Drain Pump)

Model			FXDQ40NAVE FXDQ50NAVE		FXDQ63NAVE	
		kcal/h	4,000	5,000	6,300	
★1 Cooling Ca	★1 Cooling Capacity (19.5°CWB) Btu/h		16,000	19,800	24,900	
kW		4.7	4.7 5.8			
★2 Cooling Ca	apacity (19.0°CWB)	kW	4.5	5.6	7.1	
		kcal/h	4,300	5,400	6,900	
★3 Heating Ca	apacity	Btu/h	17,100	21,500	27,300	
		kW	5.0	6.3	8.0	
Casing Color			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (I	H×W×D)	mm	200×900×620	200×900×620	200×1100×620	
Coil (Cross	Rows×Stages×Fin Pitch	mm	3×12×1.5	3×12×1.5	3×12×1.5	
Fin Coil)	Face Area	m²	0.176	0.176	0.227	
	Model		_	_	_	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units		62×1	130×1	130×1	
	Air Flow Rate (H/L)	m³/min	10.5/8.5	12.5/10.0	16.5/13.0	
	External Static Pressure	Pa	44-15 ★5	44-15 ★5	44-15 ★5	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	erial	Foamed Polyethylene	Foamed Polyethylene	Foamed Polyethylene	
Air Filter			Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	
Connections	Drain Pipe	mm	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	
Machine Weig	ht (Mass)	kg	27	28	31	
★6 Sound Lev	/el (H/L)	dBA	34/30	35/31	36/32	
Safety Devices		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor		
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Standard Accessories		Operation Manual, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	Operation Manual Operation Manual			
Drawing No.			Operation Manual, Warranty, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Operation Manual, Warranty, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Operation Manual, Warranty, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Operation Manual, Warranty, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

 $\bigstar 2$ Indoor temp. : 27°CDB, 19.0°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 External static pressure is changeable to set by the remote controller this pressure means "High static pressure - Standard static pressure".

★6 The operation sound levels are the conversion values in anechoic chamber. In practice, the sound tend to be larger than the specified values due to ambient noise or reflections. When the place of suction is changed to the bottom suction, the sound level will increase by approx. 5dBA. Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Slim Ceiling Mounted Duct Type (without Drain Pump)

Model			FXDQ20NVET FXDQ25NVET		FXDQ32NVET	
		kcal/h	2,000	,		
★1 Cooling Ca	apacity (19.5°CWB)	Btu/h	7,800	9,900	12,600	
		kW	2.3	2.9	3.7	
★2 Cooling Ca	apacity (19.0°CWB)	kW	2.2	2.8	3.6	
		kcal/h	2,200	2,800	3,400	
★3 Heating Ca	apacity	Btu/h	8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (I	H×W×D)	mm	200×900×620	200×900×620	200×900×620	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	2×12×1.5	2×12×1.5	2×12×1.5	
Fin Coil)	Face Area	m²	0.176	0.176	0.176	
	Model		_	_	_	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units		62×1	62×1	62×1	
	Air Flow Rate (H/L)	m³/min	9.5/7.5	9.5/7.5	10.5/8.5	
	External Static Pressure	Pa	44-15 ★5	44-15 ★5	44-15 ★5	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	erial	Foamed Polyethylene	Foamed Polyethylene	Foamed Polyethylene	
Air Filter			Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
Connections	Drain Pipe	mm	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	
Machine Weig	ht (Mass)	kg	26	26	26	
★6 Sound Lev	/el (H/L)	dBA	33/29	33/29	33/29	
Safety Device	S		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Standard Accessories		Operation Manual, Installation Manual, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	stallation Manual, ain Hose, Sealing Pads, Clamps, ashers legitating for Fitting			
Drawing No.			Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter Screws for Duct Flanges, Air Filter 3D049693			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length; 7.5m, level difference; 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 External static pressure is changeable to set by the remote controller this pressure means "High static pressure - Standard static pressure".

★6 The operation sound levels are the conversion values in anechoic chamber. In practice, the sound tend to be larger than the specified values due to ambient noise or reflections. When the place of suction is changed to the bottom suction, the sound level will increase by approx. 5dBA. Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Slim Ceiling Mounted Duct Type (without Drain Pump)

Model			FXDQ40NVET FXDQ50NVET		FXDQ63NVET		
kcal/h		4,000	5,000	6,300			
★1 Cooling Ca	apacity (19.5°CWB)	Btu/h	16,000	19,800	24,900		
		kW	4.7	4.7 5.8			
★2 Cooling Ca	apacity (19.0°CWB)	kW	4.5	5.6	7.1		
		kcal/h	4,300	5,400	6,900		
★3 Heating Ca	apacity	Btu/h	17,100	21,500	27,300		
		kW	5.0	6.3	8.0		
Casing Color			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate		
Dimensions: (I	H×W×D)	mm	200×900×620	200×900×620	200×1100×620		
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×12×1.5	3×12×1.5	3×12×1.5		
Fin Coil)	Face Area	m²	0.176	0.176	0.227		
	Model		_	_	_		
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan		
Fan	Motor Output × Number of Units		62×1	130×1	130×1		
	Air Flow Rate (H/L)	m³/min	10.5/8.5	12.5/10.0	16.5/13.0		
	External Static Pressure	Pa	44-15 ★5	44-15 ★5	44-15 ★5		
	Drive		Direct Drive	Direct Drive	Direct Drive		
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating		
Sound Absorb	ing Thermal Insulation Mat	erial	Foamed Polyethylene	Foamed Polyethylene	Foamed Polyethylene		
Air Filter			Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof		
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)		
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)		
Connections	Drain Pipe	mm	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)		
Machine Weig	ht (Mass)	kg	27	28	31		
★6 Sound Lev	/el (H/L)	dBA	34/30	35/31	36/32		
Safety Devices		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor			
Refrigerant Co	ontrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve		
Standard Accessories		Operation Manual, Installation Manual, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	Operation Manual, Installation Manual, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	Operation Manual, Installation Manual, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter			
Drawing No.				3D049693			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

 $\bigstar 2$ Indoor temp. : 27°CDB, 19.0°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length; 7.5m, level difference; 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 External static pressure is changeable to set by the remote controller this pressure means "High static pressure - Standard static pressure".

★6 The operation sound levels are the conversion values in anechoic chamber. In practice, the sound tend to be larger than the specified values due to ambient noise or reflections. When the place of suction is changed to the bottom suction, the sound level will increase by approx. 5dBA. Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Slim Ceiling Mounted Duct Type (PVE: with Drain Pump PVET: without Drain Pump)

Model			FXDQ20PVE FXDQ20PVET	FXDQ25PVE FXDQ25PVET	FXDQ32PVE FXDQ32PVET	
		kcal/h	2,000	2,500	3,200	
★1 Cooling Ca	pacity (19.5°CWB)	Btu/h	7,800	9,900	12,600	
		kW	2.3	2.9	3.7	
★2 Cooling Ca	pacity (19.0°CWB)	kW	2.2	2.8	3.6	
		kcal/h	2,200	2,800	3,400	
★3 Heating Ca	apacity	Btu/h	8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (H	H×W×D)	mm	200×900×620	200×900×620	200×900×620	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	2×12×1.5	2×12×1.5	2×12×1.5	
Fin Coil)	Face Area	m²	0.176	0.176	0.176	
	Model		_	_	_	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	62×1	62×1	62×1	
	Air Flow Rate (H/L)	m³/min	9.5/7.5	9.5/7.5	10.5/8.5	
	External Static Pressure	Pa	44-15 ★5	44-15 ★5	44-15 ★5	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature C	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorbi	ng Thermal Insulation Mate	erial	Foamed Polyethylene	Foamed Polyethylene	Foamed Polyethylene	
Air Filter			Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	Removal / Washable / Mildew Proof	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
Connections	Drain Pipe	mm	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	
Machine Weigh	ht (Mass)	kg	26	26	26	
★6 Sound Lev	el (H/L)	dBA	33/29	33/29	33/29	
Safety Devices	3		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Co	ntrol		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Standard Accessories			Operation Manual, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	Operation Manual, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	Operation Manual, Installation Manual, Warranty, Drain Hose, Sealing Pads, Clamps, Washers, Insulation for Fitting, Clamp Metal, Washer Fixing Plate, Screws for Duct Flanges, Air Filter	
Drawing No.			3D052136			

Notes:

5dBA.

- ★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- *3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference:
- 4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
- ★5 External static pressure is changeable to set by the remote controller this pressure means "High static pressure Standard static pressure".
- ★6 The operation sound levels are the conversion values in anechoic chamber. In practice, the sound tend to be larger than the specified values due to ambient noise or reflections.
 When the place of suction is changed to the bottom suction, the sound level will increase by approx.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Ceiling Mounted Built-in Type

Model			FXSQ20MVE FXSQ25MVE		FXSQ32MVE
		kcal/h	2,000	2,500	3,200
★1 Cooling Capacity (19.5°CWB) Btu/h			7,800	9,900	12,600
kW		2.3 2.9		3.7	
★2 Cooling C	Capacity (19.0°CWB)	kW	2.2	2.8	3.6
		kcal/h	2,200	2,800	3,400
★3 Heating C	Capacity	Btu/h	8,500	10,900	13,600
		kW	2.5	3.2	4.0
Casing		•	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions:	(H×W×D)	mm	300×550×800	300×550×800	300×550×800
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×14×1.75	3×14×1.75	3×14×1.75
Fin Coil)	Face Area	m²	0.088	0.088	0.088
	Model		D18H3A	D18H3A	D18H3A
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan
Fan	Motor Output × Number of Units	W	50×1	50×1	50×1
ran	Air Flow Rate (H/L)	m³/min	9/6.5	9/6.5	9.5/7
	★4 External static pressure	Pa	88-39-20	88-39-20	64-39-15
	Drive		Direct Drive	Direct Drive	Direct Drive
Temperature	Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating
Sound Absor	bing Thermal Insulation Mate	erial	Glass Fiber	Glass Fiber	Glass Fiber
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)
Connections	Drain Pipe	mm	VP25 (External Dia. 32 Internal Dia. 25)	VP25 (External Dia. 32 Internal Dia. 25)	VP25 (External Dia. 32 Internal Dia. 25)
Machine Wei	ght (Mass)	kg	30	30	30
★6 Sound Le	evel (H/L) (220V)	dBA	37/32	37/32	38/32
Safety Device	es		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor
Refrigerant C	Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Connectable	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series
	Model		BYBS32DJW1	BYBS32DJW1	BYBS32DJW1
Decoration Panel (Option)	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)
	Dimensions: (HxWxD)	mm	55×650×500	55×650×500	55×650×500
•	Weight	kg	3	3	3
Standard Accessories		Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	
Drawing No.				3D039431	

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

★4 External static pressure is changeable to change over the connectors inside electrical box, this pressure means

"High static pressure-Standard -Low static pressure".

5 Capacities are net, including a deduction for cooling (an additional for heating) for indoor fan motor heat.

*6 Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values are normally somewhat higher during actual operation as a result of ambient conditions. Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Ceiling Mounted Built-in Type

Model			FXSQ40MVE FXSQ50MVE		FXSQ63MVE	
		kcal/h	4,000	5,000	6,300	
★1 Cooling C	Capacity (19.5°CWB)	Btu/h	16,000	19,800	24,900	
		kW	4.7	5.8	7.3	
★2 Cooling C	Capacity (19.0°CWB)	kW	4.5	5.6	7.1	
		kcal/h	4,300	5,400	6,900	
★3 Heating C	Capacity	Btu/h	17,100	21,500	27,300	
		kW	5.0	6.3	8.0	
Casing		•	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: ((H×W×D)	mm	300×700×800	300×700×800	300×1,000×800	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×14×1.75	3×14×1.75	3×14×1.75	
Fin Coil)	Face Area	m²	0.132	0.132	0.221	
	Model	•	D18H2A	D18H2A	2D18H2A	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	65×1	85×1	125×1	
ган	Air Flow Rate (H/L)	m³/min	11.5/9	15/11	21/15.5	
	★4 External static pressure	Pa	88-49-20	88-59-29	88-49-20	
	Drive		Direct Drive Direct Drive		Direct Drive	
Temperature	Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absort	bing Thermal Insulation Mate	rial	Glass Fiber	Glass Fiber	Glass Fiber	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	
Connections	Drain Pipe	mm	VP25 (External Dia. 32 Internal Dia. 25)	VP25 (External Dia. 32 Internal Dia. 25)	VP25 (External Dia. 32 Internal Dia. 25)	
Machine Wei	ght (Mass)	kg	30	31	41	
★6 Sound Le	evel (H/L)	dBA	38/32	41/36	42/35	
Safety Device	es		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant C	Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	
	Model		BYBS45DJW1	BYBS45DJW1	BYBS71DJW1	
Decoration Panel	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	
(Option)	Dimensions: (H×W×D)	mm	55×800×500	55×800×500	55×1,100×500	
	Weight	kg	3.5	3.5	4.5	
Standard Acc	Standard Accessories		Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers. Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.		Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	
Drawing No.			3D039431			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

- ★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)
- ★4 External static pressure is changeable to change over the connectors inside electrical box, this pressure means
 - "High static pressure-Standard -Low static pressure".
- 5 Capacities are net, including a deduction for cooling (an additional for heating) for indoor fan motor heat.
- *6 Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values are normally somewhat higher during actual operation as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Ceiling Mounted Built-in Type

Model			FXSQ80MVE FXSQ100MVE		FXSQ125MVE	
		kcal/h	8,000	10,000	12,500	
★1 Cooling (Capacity (19.5°CWB)	Btu/h	31,700	39,600	49,500	
		kW	9.3	11.6	14.5	
★2 Cooling (Capacity (19.0°CWB)	kW	9.0	11.2	14.0	
		kcal/h	8,600	10,800	13,800	
★3 Heating (Capacity	Btu/h	34,100	42,700	54,600	
		kW	10.0	12.5	16.0	
Casing		•	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions:	(H×W×D)	mm	300×1,400×800	300×1,400×800	300×1,400×800	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×14×1.75	3×14×1.75	3×14×1.75	
Fin Coil)	Face Area	m²	0.338	0.338	0.338	
	Model		3D18H2A	3D18H2A	3D18H2A	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Eon	Motor Output × Number of Units	W	225×1	225×1	225×1	
Fan	Air Flow Rate (H/L)	m³/min	27/21.5	28/22	38/28	
	★4 External static pressure	Pa	113-82	107-75	78-39	
	Drive		Direct Drive Direct Drive		Direct Drive	
Temperature	Temperature Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Abso	rbing Thermal Insulation Mat	erial	Glass Fiber	Glass Fiber	Glass Fiber	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Liquid Pipes	mm	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	
Piping	Gas Pipes	mm	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	
Connections	Drain Pipe	mm	VP25 (External Dia. 32 Internal Dia. 25)	VP25 (External Dia. 32 Internal Dia. 25)	VP25 (External Dia. 32 Internal Dia. 25)	
Machine We	ight (Mass)	kg	51	51	52	
★6 Sound Le	evel (H/L)	dBA	43/37	43/37	46/41	
Safety Device	es		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant (Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	
	Model		BYBS125DJW1	BYBS125DJW1	BYBS125DJW1	
Decoration	Panel Color		White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	
Panel (Option)	Dimensions: (HxWxD)	mm	55×1,500×500	55×1,500×500	55×1,500×500	
	Weight	kg	6.5	6.5	6.5	
Standard Accessories			Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers.	
Drawing No.			3D039431			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

- ★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)
- ★4 External static pressure is changeable to change over the connectors inside electrical box, this pressure means

"High static pressure-Standard".

- 5 Capacities are net, including a deduction for cooling (an additional for heating) for indoor fan motor heat.
- *6 Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values are normally somewhat higher during actual operation as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Ceiling Mounted Duct Type

Model			FXMQ40MAVE	FXMQ50MAVE	FXMQ63MAVE	FXMQ80MAVE
		kcal/h	4,000	5,000	6,300	8,000
★1 Cooling C	Capacity (19.5°CWB)	Btu/h	16,000	19,800	24,900	31,700
		kW	4.7	5.8	7.3	9.3
★2 Cooling C	Capacity (19.0°CWB)	kW	4.5	5.6	7.1	9.0
		kcal/h	4,300	5,400	6,900	8,600
★3 Heating C	Capacity	Btu/h	17,100	21,500	27,300	34,100
		kW	5.0	6.3	8.0	10.0
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: ((H×W×D)	mm	390×720×690	390×720×690	390×720×690	390×720×690
Coil (Cross	Rows×Stages×Fin Pitch	mm	3×16×2.0	3×16×2.0	3×16×2.0	3×16×2.0
Fin Coil)	Face Area	m²	0.181	0.181	0.181	0.181
	Model		D11/2D3AB1VE	D11/2D3AB1VE	D11/2D3AB1VE	D11/2D3AA1VE
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	Sirocco Fan
	Motor Output × Number of Units	W	100×1	100×1	100×1	160×1
Fan	Air Flour Date (LI/L)	m³/min	14/11.5	14/11.5	14/11.5	19.5/16
	Air Flow Rate (H/L)	cfm	494/406	494/406	494/406	688/565
	External Static Pressure 50 / 60Hz	Pa	157/157-118/108 ★4	157/157-118/108 ★4	157/157-118/108 ★4	157/160-108/98 ★4
	Drive		Direct Drive	Direct Drive	Direct Drive	Direct Drive
Temperature	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating
Sound Absort	bing Thermal Insulation Ma	terial	Glass Fiber	Glass Fiber	Glass Fiber	Glass Fiber
Air Filter			★ 5	★ 5	★ 5	★ 5
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)
Connections	Drain Pipe	mm	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)
Machine Wei	ght (Mass)	kg	44	44	44	45
★7 Sound Le	vel (H/L)	dBA	39/35	39/35	39/35	42/38
Safety Devices		Fuse, Thermal Fuse for Fan Motor				
Refrigerant Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories		Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws.	Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws.	Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws.	Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws.	
Drawing No.			3D038814A			

Notes:

- ★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)
- ★4 External static pressure is changeable to change over the connectors inside electrical box, this pressure means
 - "High static pressure-Standard".
- ★5 Air filter is not standard accessory, but please mount it in the duct system of the suction side. Select its colorimetric method (gravity method) 50% or more.
- 6 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
- *7 Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values are normally somewhat higher during actual operation as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Ceiling Mounted Duct Type

Model			FXMQ100MAVE	FXMQ125MAVE	FXMQ200MAVE	FXMQ250MAVE
		kcal/h	10,000	12,500	19,800	24,800
★1 Cooling C	apacity (19.5°CWB)	Btu/h	39,600	49,500	78,500	98,300
		kW	11.6	14.5	23.0	28.8
★2 Cooling C	apacity (19.0°CWB)	kW	11.2	14.0	22.4	28.0
		kcal/h	10,800	13,800	21,500	27,100
★3 Heating C	apacity	Btu/h	42,700	54,600	85,300	107,000
		kW	12.5	16.0	25.0	31.5
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: (H×W×D)	mm	390×1,110×690	390×1,110×690	470×1,380×1,100	470×1,380×1,100
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×16×2.0	3×16×2.0	3×26×2.0	3×26×2.0
Fin Coil)	Face Area	m²	0.319	0.319	0.68	0.68
	Model		2D11/2D3AG1VE	2D11/2D3AF1VE	D13/4G2DA1×2	D13/4G2DA1×2
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	Sirocco Fan
	Motor Output × Number of Units	W	270×1	430×1	380×2	380×2
Fan	Air Flow Rate (H/L)	m³/min	29/23	36/29	58/50	72/62
	All Flow hate (H/L)	cfm	1,024/812	1,271/1,024	2,047/1,765	2,542/2,189
	External Static Pressure 50 / 60Hz		157/172-98/98 ★4	191/245-152/172 ★4	221/270-132 ★4	270/191-147 ★4
	Drive		Direct Drive	Direct Drive	Direct Drive	Direct Drive
Temperature	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating
Sound Absort	oing Thermal Insulation Ma	terial	Glass Fiber	Glass Fiber	Glass Fiber	Glass Fiber
Air Filter			★ 5	★ 5	★ 5	★ 5
	Liquid Pipes	mm	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)
Piping	Gas Pipes	mm	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	φ19.1(Brazing Connection)	φ22.2 (Brazing Connection)
Connections	Drain Pipe	mm	VP25 (External Dia. 32) (Internal Dia. 25)	VP25 (External Dia. 32 (Internal Dia. 25)	PS1B	PS1B
Machine Weig	ght (Mass)	kg	63	65	137	137
★7 Sound Le	vel (H/L)	dBA	43/39	45/42	48/45	48/45
Safety Devices		Fuse, Thermal Fuse for Fan Motor	Fuse, Thermal Fuse for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable outdoor unit			R-410A P Series	R-410A P Series	R-410A P Series	R-410A P Series
Standard Accessories		Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws.	Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws.	Operation Manual, Installation Manual, Sealing Pads, Connection Pipes, Screws, Clamps.	Operation Manual, Installation Manual, Sealing Pads, Connection Pipes, Screws, Clamps.	
Drawing No.				3D03	8814A	

Notes:

- **★1** Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)
- ★4 External static pressure is changeable to change over the connectors inside electrical box, this pressure means
 - "High static pressure-Standard".
- ★5 Air filter is not standard accessory, but please mount it in the duct system of the suction side. Select its colorimetric method (gravity method) 50% or more.
- 6 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
- ★7 Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values are normally somewhat higher during actual operation as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Ceiling Suspended Type

Model			FXHQ32MAVE	FXHQ63MAVE	FXHQ100MAVE	
	Cooling Capacity (19.5°CWB) kcal/h Btu/h		3,200	6,300	10,000	
★1 Cooling C			12,600	24,900	39,600	
k		kW	3.7	7.3	11.6	
★2 Cooling C	apacity (19.0°CWB)	kW	3.6	7.1	11.2	
		kcal/h	3,400	6,900	10,800	
★3 Heating C	apacity	Btu/h	13,600	27,300	42,700	
		kW	4.0	8.0	12.5	
Casing Color			White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)	
Dimensions: (H×W×D)	mm	195×960×680	195×1,160×680	195×1,400×680	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	2×12×1.75	3×12×1.75	3×12×1.75	
Fin Coil)	Face Area	m²	0.182	0.233	0.293	
	Model		3D12K1AA1	4D12K1AA1	3D12K2AA1	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	62×1	62×1	130×1	
	Air Flow Rate (H/L)	m³/min	12/10	17.5/14	25/19.5	
		cfm	424/353	618/494	883/688	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absort	oing Thermal Insulation Mat	erial	Glass Wool	Glass Wool	Glass Wool	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	
Connections	Drain Pipe	mm	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	VP20 (External Dia. 26 Internal Dia. 20)	
Machine Wei	ght (Mass)	kg	24	28	33	
★5 Sound Le	vel (H/L)	dBA	36/31	39/34	45/37	
Safety Devices		Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor		
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable of	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Clamps, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Clamps, Washers.	Operation Manual, Installation Manual, Paper Pattern for Installation, Drain Hose, Clamp Metal, Insulation for Fitting, Clamps, Washers.	
Drawing No.			3D038815A			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

 $\star 3$ Indoor temp. : 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 ★5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation,

these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Wall Mounted Type

Model		FXAQ20MAVE	FXAQ25MAVE	FXAQ32MAVE		
	Cooling Capacity (19.5°CWB) kca		2,000 2,500		3,200	
★1 Cooling C			7,800	9,900	12,600	
		kW	2.3	2.9	3.7	
★2 Cooling C	apacity (19.0°CWB)	kW	2.2	2.8	3.6	
		kcal/h	2,200	2,800	3,400	
★3 Heating C	apacity	Btu/h	8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing Color			White (3.0Y8.5/10.5)	White (3.0Y8.5/10.5)	White (3.0Y8.5/10.5)	
Dimensions: (H×W×D)	mm	290×795×230	290×795×230	290×795×230	
Coil (Cross	Rows×Stages×Fin Pitch	mm	2×14×1.4	2×14×1.4	2×14×1.4	
Fin Coil)	Face Area	m²	0.161	0.161	0.161	
	Model		QCL9661M	QCL9661M	QCL9661M	
	Туре		Cross Flow Fan	Cross Flow Fan	Cross Flow Fan	
Fan	Motor Output × Number of Units	W	40×1	40×1	40×1	
	Air Flow Rate (H/L)	m³/min	7.5/4.5	8/5	9/5.5	
		cfm	265/159	282/177	318/194	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	oing Thermal Insulation Mat	erial	Foamed Polystyrene / Foamed Polyethylene	Foamed Polystyrene / Foamed Polyethylene	Foamed Polystyrene / Foamed Polyethylene	
Air Filter			Resin Net (Washable)	Resin Net (Washable)	Resin Net (Washable)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
Connections	Drain Pipe	mm	VP13 (External Dia. 18 Internal Dia. 13)	VP13 (External Dia. 18 Internal Dia. 13)	VP13 (External Dia. 18 Internal Dia. 13)	
Machine Weig	ght (Mass)	kg	11	11	11	
★5 Sound Lev	vel (H/L)	dBA	35/29	36/29	37/29	
Safety Devices		Fuse	Fuse	Fuse		
Refrigerant Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve		
Connectable of	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Installation Panel, Paper Pattern for Installation, Insulation Tape, Clamps, screws.	Operation Manual, Installation Manual, Installation Panel, Paper Pattern for Installation, Insulation Tape, Clamps, screws.	Operation Manual, Installation Manual, Installation Panel, Paper Pattern for Installation, Insulation Tape, Clamps, screws.	
Drawing No.			3D039370B			

- ★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level
- ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length:7.5m, level difference: 0m.
- $\star 3$ Indoor temp. : 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)
- 4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 ★5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation,
- these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Wall Mounted Type

Model		FXAQ40MAVE	FXAQ50MAVE	FXAQ63MAVE		
	kcal/h Cooling Capacity (19.5°CWB) kcal/h Btu/h		4,000	5,000	6,300	
★1 Cooling C			16,000	19,800	24,900	
		kW	4.7	5.8	7.3	
★2 Cooling Capacity (19.0°CWB) kW		4.5	5.6	7.1		
		kcal/h	4,300	5,400	6,900	
★3 Heating C	apacity	Btu/h	17,100	21,500	27,300	
		kW	5.0	6.3	8.0	
Casing Color			White (3.0Y8.5/10.5)	White (3.0Y8.5/10.5)	White (3.0Y8.5/10.5)	
Dimensions: (H×W×D)	mm	290×1,050×230	290×1,050×230	290×1,050×230	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	2×14×1.4	2×14×1.4	2×14×1.4	
Fin Coil)	Face Area	m²	0.213	0.213	0.213	
	Model		QCL9686M	QCL9686M	QCL9686M	
	Туре		Cross Flow Fan	Cross Flow Fan	Cross Flow Fan	
Fan	Motor Output × Number of Units	W	43×1	43×1	43×1	
	Air Flow Rate (H/L)	m³/min	12/9	15/12	19/14	
		cfm	424/318	530/424	671/494	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature Control			Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	oing Thermal Insulation Mat	erial	Foamed Polystyrene / Foamed Polyethylene	Foamed Polystyrene / Foamed Polyethylene	Foamed Polystyrene / Foamed Polyethylene	
Air Filter			Resin Net (Washable)	Resin Net (Washable)	Resin Net (Washable)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	
Piping	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	
Connections	Drain Pipe	mm	VP13 (External Dia. 18 Internal Dia. 13)	VP13 (External Dia. 18 Internal Dia. 13)	VP13 (External Dia. 18 Internal Dia. 13)	
Machine Weig	ght (Mass)	kg	14	14	14	
★5 Sound Lev	vel (H/L)	dBA	39/34	42/36	46/39	
Safety Device	s		Fuse	Fuse	Fuse	
Refrigerant Control		Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve		
Connectable of	outdoor unit		R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Installation Panel, Paper Pattern for Installation, Insulation Tape, Clamps, screws.	Operation Manual, Installation Manual, Installation Panel, Paper Pattern for Installation, Insulation Tape, Clamps, screws.	Operation Manual, Installation Manual, Installation Panel, Paper Pattern for Installation, Insulation Tape, Clamps, screws.	
Drawing No.			3D039370B			

 \star 1 Indoor temp. : 27°CDB, 19.5°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp; 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

 $\star 3$ Indoor temp. : 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.
 ★5 Anechoic chamber conversion value, measured under JISB8616 conditions. During actual operation,

these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Floor Standing Type

Model		FXLQ20MAVE	FXLQ25MAVE	FXLQ32MAVE		
	kcal/h Cooling Capacity (19.5°CWB) Btu/h kW		2,000	2,500	3,200	
★1 Cooling C			7,800	9,900	12,600	
			2.3	2.9	3.7	
****		2.2	2.8	3.6		
	kcal/h ★3 Heating Capacity Btu/h		2,200	2,800	3,400	
★3 Heating C			8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	
Dimensions: ((H×W×D)	mm	600×1,000×222	600×1,000×222	600×1,140×222	
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×14×1.5	3×14×1.5	3×14×1.5	
Fin Coil)	Face Area	m²	0.159	0.159	0.200	
	Model		D14B20	D14B20	2D14B13	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	15×1	15×1	25×1	
	Air Flow Rate (H/L)	m³/min	7/6	7/6	8/6	
		cfm	247/212	247/212	282/212	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	oing Thermal Insulation Ma	terial	Glass Fiber/ Urethane Foam	Glass Fiber/ Urethane Foam	Glass Fiber/ Urethane Foam	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
	Drain Pipe	mm	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	
Machine Weig	ght (Mass)	kg	25	25	30	
★5 Sound Le	vel (H/L)	dBA	35/32	35/32	35/32	
Safety Devices			Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable Outdoor Unit			R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	
Drawing No.			3D038816A			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured at a point 1.5 m in front of the unit at a height of 1.5 m. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Floor Standing Type

Model			FXLQ40MAVE	FXLQ50MAVE	FXLQ63MAVE	
	★1 Cooling Capacity (19.5°CWB) kcal/h Btu/h kW		4,000	5,000	6,300	
★1 Cooling Ca			16,000	19,800	24,900	
			4.7	5.8	7.3	
★2 Cooling Capacity (19.0°CWB) kW		4.5	5.6	7.1		
		kcal/h	4,300	5,400	6,900	
★3 Heating Ca	apacity	Btu/h	17,100	21,500	27,300	
		kW	5.0	6.3	8.0	
Casing Color			Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	Ivory White (5Y7.5/1)	
Dimensions: (I	H×W×D)	mm	600×1,140×222	600×1,420×222	600×1,420×222	
Coil (Cross	Rows×Stages×Fin Pitch	mm	3×14×1.5	3×14×1.5	3×14×1.5	
Fin Coil)	Face Area	m²	0.200	0.282	0.282	
	Model		2D14B13	2D14B20	2D14B20	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	25x1	35×1	35×1	
	Air Flow Rate (H/L)	m³/min	11/8.5	14/11	16/12	
		cfm	388/300	494/388	565/424	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	erial	Glass Fiber/ Urethane Foam	Glass Fiber/ Urethane Foam	Glass Fiber/ Urethane Foam	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	
00111100110110	Drain Pipe	mm	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	
Machine Weig	ht (Mass)	kg	30	36	36	
★5 Sound Lev	vel (H/L)	dBA	38/33	39/34	40/35	
Safety Devices			Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable Outdoor Unit			R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	
Drawing No.			3D038816A			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured at a point 1.5 m in front of the unit at a height of 1.5 m. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Concealed Floor Standing Type

Model			FXNQ20MAVE	FXNQ25MAVE	FXNQ32MAVE	
	★1 Cooling Capacity (19.5°CWB) kcal/h Btu/h kW		2,000	2,500	3,200	
★1 Cooling Ca			7,800	9,900	12,600	
			2.3	2.9	3.7	
★2 Cooling Ca	apacity (19.0°CWB)	kW	2.2	2.8	3.6	
		kcal/h	2,200	2,800	3,400	
★3 Heating Ca	apacity	Btu/h	8,500	10,900	13,600	
		kW	2.5	3.2	4.0	
Casing Color			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (I	H×W×D)	mm	610×930×220	610×930×220	610×1,070×220	
Coil (Cross	Rows×Stages×Fin Pitch	mm	3×14×1.5	3×14×1.5	3×14×1.5	
Fin Coil)	Face Area	m²	0.159	0.159	0.200	
	Model		D14B20	D14B20	2D14B13	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	15x1	15×1	25x1	
	Air Flow Rate (H/L)	m³/min	7/6	7/6	8/6	
		cfm	247/212	247/212	282/212	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature 0	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	erial	Glass Fiber/ Urethane Foam	Glass Fiber/ Urethane Foam	Glass Fiber/ Urethane Foam	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
5	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	
	Drain Pipe	mm	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	
Machine Weig	nht (Mass)	kg	19	19	23	
★5 Sound Lev	/el (H/L)	dBA	35/32	35/32	35/32	
Safety Devices			Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable C	Outdoor Unit		R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	
Drawing No.	·		3D038817A			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured at a point 1.5 m in front of the unit at a height of 1.5 m. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

Concealed Floor Standing Type

Model			FXNQ40MAVE	FXNQ50MAVE	FXNQ63MAVE	
	★1 Cooling Capacity (19.5°CWB) kcal/h Btu/h kW		4,000	5,000	6,300	
★1 Cooling Ca			16,000	19,800	24,900	
			4.7	5.8	7.3	
★2 Cooling Capacity (19.0°CWB) kW		4.5	5.6	7.1		
		kcal/h	4,300	5,400	6,900	
★3 Heating Ca	apacity	Btu/h	17,100	21,500	27,300	
		kW	5.0	6.3	8.0	
Casing Color			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate	
Dimensions: (I	H×W×D)	mm	610×1,070×220	610×1,350×220	610×1,350×220	
Coil (Cross	Rows×Stages×Fin Pitch	mm	3×14×1.5	3×14×1.5	3×14×1.5	
Fin Coil)	Face Area	m²	0.200	0.282	0.282	
	Model		2D14B13	2D14B20	2D14B20	
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan	
Fan	Motor Output × Number of Units	W	25x1	35×1	35×1	
	Air Flow Rate (H/L)	m³/min	11/8.5	14/11	16/12	
	All Flow hate (H/L)	cfm	388/300	494/388	565/424	
	Drive		Direct Drive	Direct Drive	Direct Drive	
Temperature (Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	
Sound Absorb	ing Thermal Insulation Mat	erial	Glass Fiber / Urethane Foam	Glass Fiber / Urethane Foam	Glass Fiber / Urethane Foam	
Air Filter			Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	Resin Net (with Mold Resistant)	
	Liquid Pipes	mm	φ6.4 (Flare Connection)	φ6.4 (Flare Connection)	φ9.5 (Flare Connection)	
Piping Connections	Gas Pipes	mm	φ12.7 (Flare Connection)	φ12.7 (Flare Connection)	φ15.9 (Flare Connection)	
30.11.001.01.0	Drain Pipe	mm	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	φ21 O.D (Vinyl Chloride)	
Machine Weig	ht (Mass)	kg	23	27	27	
★5 Sound Lev	vel (H/L)	dBA	38/33	39/34	40/35	
Safety Devices			Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	Fuse, Thermal Protector for Fan Motor	
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve	
Connectable Outdoor Unit			R-410A P Series	R-410A P Series	R-410A P Series	
Standard Accessories			Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	Operation Manual, Installation Manual, Insulation for Fitting, Drain Hose, Clamps, Screws, Washers, Level Adjustment Screw.	
Drawing No.			3D038817A			

Notes:

★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.

★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)

4 Capacities are net, including a deduction for cooling (an addition for heating) for indoor fan motor heat.

★5 Anechoic chamber conversion value, measured at a point 1.5 m in front of the unit at a height of 1.5 m. During actual operation, these values are normally somewhat higher as a result of ambient conditions.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Ceiling Suspended Cassette Type

Madal	Indoor Ur Connection		por Unit FXUQ71MAV1		FXUQ100MAV1	FXUQ125MAV1		
Model			Unit	BEVQ71MAVE	BEVQ100MAVE	BEVQ125MAVE		
		kca				7,100	10,000	12,500
★1 Cooling Ca	apacity (19.5°	CWB)	Btu/h	28,300	39,600	49,500		
			kW	8.3	11.6	14.5		
★2 Cooling Ca	apacity (19.0°	CWB)	kW	8.0	11.2	14.0		
			kcal/h	7,700	10,800	12,000		
★3 Heating Ca	apacity		Btu/h	30,700	42,700	47,800		
			kW	9.0	12.5	14.0		
Casing Color			•	White (10Y9/0.5)	White (10Y9/0.5)	White (10Y9/0.5)		
Dimensions: (I	H×W×D)		mm	165×895×895	230×895×895	230×895×895		
Coil (Cross	Rows×Stag	es×Fin Pitch	mm	3×6×1.5	3×8×1.5	3×8×1.5		
Fin Coil)	Face Area		m²	0.265	0.353	0.353		
	Model	l .		QTS48A10M	QTS50B15M	QTS50B15M		
	Type			Turbo Fan	Turbo Fan	Turbo Fan		
Fan	Motor Output × Number of Units		W	45×1	90×1	90×1		
	A: El D-	Air Flow Rate (H/L)		19/14	29/21	32/23		
	All Flow Ha			671/494	1,024/741	1,130/812		
	Drive	•		Direct Drive	Direct Drive	Direct Drive		
Temperature (Control			Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating		
Sound Absorb	ing Thermal	Insulation Mat	erial	Heat Resistant Foamed Polyethylene, Regular Foamed Polyethylene	Heat Resistant Foamed Polyethylene, Regular Foamed Polyethylene	Heat Resistant Foamed Polyethylene, Regular Foamed Polyethylene		
	Liquid Pipe	S	mm	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)	φ9.5 (Flare Connection)		
Piping Connections	Gas Pipes		mm	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)	φ15.9 (Flare Connection)		
00111100110110	Drain Pipe		mm	I.Dφ20×O.Dφ26	I.Dφ20×O.Dφ26	I.Dφ20×O.Dφ26		
Machine Weig	ht (Mass)		kg	25	31	31		
★5 Sound Lev	/el (H/L)		dBA	40/35	43/38	44/39		
Safety Devices			Thermal Protector for Fan Motor	Thermal Protector for Fan Motor	Thermal Protector for Fan Motor			
Standard Accessories				Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Holding Plate.	Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Holding Plate.	Operation Manual, Installation Manual, Drain Hose, Clamp Metal, Insulation for Fitting, Sealing Pads, Clamps, Screws, Washers, Holding Plate.		
Drawing No.				C:4D045395A				

Notes:

- ★1 Indoor temp.: 27°CDB, 19.5°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★2 Indoor temp.: 27°CDB, 19.0°CWB / outdoor temp.: 35°CDB / Equivalent piping length: 7.5m, level difference: 0m.
- ★3 Indoor temp.: 20°CDB / outdoor temp.: 7°CDB, 6°CWB / Equivalent piping length: 7.5m, level difference: 0m. (Heat pump only)
- 4 Capacities are net, including a deduction for cooling (an additional for heating) for indoor fan motor heat.
- ★5 Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values are normally somewhat higher during actual operation as a result of ambient conditions.

Conversion Formulae kcal/h=kWx860 Btu/h=kWx3412 cfm=m³/minx35.3

BEV Units

Model				BEVQ71MAVE	BEVQ100MAVE	BEVQ125MAVE
Power Supply				1 Phase 50Hz 220~240V	1 Phase 50Hz 220~240V	1 Phase 50Hz 220~240V
Casing				Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: (H×W×D)		mm	100×350×225	100×350×225	100×350×225
Sound Absorbing Thermal Insulation Material		Flame and Heat Resistant Foamed Polyethylene	Flame and Heat Resistant Foamed Polyethylene	Flame and Heat Resistant Foamed Polyethylene		
	Indoor	Liquid Pipes		9.5mm (Flare Connection)	9.5mm (Flare Connection)	9.5mm (Flare Connection)
Piping	Unit	Gas Pipes		15.9mm (Flare Connection)	15.9mm (Flare Connection)	15.9mm (Flare Connection)
Connection	Outdoor	Liquid Pipes		9.5mm (Flare Connection)	9.5mm (Flare Connection)	9.5mm (Flare Connection)
	Unit	Suction Gas	Pipes	15.9mm (Flare Connection)	15.9mm (Flare Connection)	15.9mm (Flare Connection)
Machine Weig	ht (Mass)	•	kg	3.0	3.0	3.5
Standard Accessories				Installation manual, Gas piping connections, Insulation for fitting, Sealing material, Clamps	Installation manual, Gas piping connections, Insulation for fitting, Sealing material, Clamps	Installation manual, Gas piping connections, Insulation for fitting, Sealing material, Clamps
Drawing No.		•		4D045387A	4D045387A	4D045388A

Outdoor Air Processing Unit

Model		FXMQ125MFV1	FXMQ200MFV1	FXMQ250MFV1	
kcal/h		12,000	19,300	24,100	
★1 Cooling Ca	Cooling Capacity Btu/h		47,800	76,400	95,500
kW		14.0	22.4	28.0	
		kcal/h	7,700	12,000	15,000
★1 Heating Ca	apacity	Btu/h	30,400	47,400	59,400
		kW	8.9	13.9	17.4
Casing			Galvanized Steel Plate	Galvanized Steel Plate	Galvanized Steel Plate
Dimensions: (H	H×W×D)	mm	470×744×1,100	470×1,380×1,100	470×1,380×1,100
Coil (Cross Fin Coil)	Rows×Stages×Fin Pitch	mm	3×26×2.0	3x26x2.0	3×26×2.0
FIII COII)	Face Area	m²	0.28	0.65	0.65
	Model		D13/4G2DA1	D13/4G2DA1	D13/4G2DA1
	Туре		Sirocco Fan	Sirocco Fan	Sirocco Fan
	Motor Output × Number of Units	W	380×1	380×1	380×1
Fan	Air Flow Rate (H/L)	m³/min	18	28	35
	All Flow hate (H/L)	cfm	635	988	1,236
	External Static Pressure ★4	Pa	185	225	205
	Drive		Direct Drive	Direct Drive	Direct Drive
Temperature 0	Control		Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating	Microprocessor Thermostat for Cooling and Heating
Sound Absorb	ing Thermal Insulation M	laterial	Glass Fiber	Glass Fiber	Glass Fiber
Air Filter			* 2	★ 2	★ 2
	Liquid Pipes		9.5mm (Flare Connection)	9.5mm (Flare Connection)	9.5mm (Flare Connection)
Piping Connections	Gas Pipes		15.9mm (Flare Connection)	19.1mm (Brazing Connection)	22.2mm (Brazing Connection)
	Drain Pipe	(mm)	PS1B (female thread)	PS1B (female thread)	PS1B (female thread)
Machine Weig	ht (Mass)	kg	86	123	123
Sound Level (2	220V) ★3,★4	dBA	42	47	47
Safety Devices			Fuse Thermal Protector for Fan Motor	Fuse Thermal Protector for Fan Motor	Fuse Thermal Protector for Fan Motor
Refrigerant Control			Electronic Expansion Valve	Electronic Expansion Valve	Electronic Expansion Valve
Standard Acce			Operation Manual, Installation Manual, Sealing Pads, Screws, Clamps.	Operation Manual, Installation Manual, Sealing Pads, Connection Pipes, Screws, Clamps.	Operation Manual, Installation Manual, Sealing Pads, Connection Pipes, Screws, Clamps.
Connectable C	Outdoor Units ★5,★6		RXYQ8~54PY1	RXYQ8~54PY1	RXYQ10~54PY1
Drawing No.			C:3D046147A	C:3D046147A	C:3D046147A

Notes:

- ★1. Specifications are based on the following conditions:
 Cooling: Outdoor temp. of 33°CDB, 28°CWB (68% RH). and discharge temp. of 18°CDB
 Heating: Outdoor temp. of 0°CDB, -2.9°CWB (50% RH). and discharge temp. of 25°CDB

 - · Equivalent reference piping length: 7.5m (0m Horizontal)
- *2. Air intake filter is not supplied, so be sure to install the optional long-life filter or high-efficiency filter. Please mount it in the duct system of the suction side. Select its colorimetric method (gravity method) 50% or more.
- $\bigstar 3$. Anechoic chamber conversion value, measured at a point 1.5m downward from the unit center. These values (measured at 220V) are normally somewhat higher during actual operation as a result of ambient conditions.
- ★4. Valves measured at 220 V.
- \star 5. Within the range that the total capacity of indoor units is 50 to 100%, it is possible to connect to the outdoor unit.
- \bigstar 6. It is not possible to connect to the 5 HP outdoor unit. Not available for Heat Recovery type and VRV II-S
 - · This equipment cannot be incorporated into the refrigerant piping system or remote group control of the VRV II system.

Conversion Formulae kcal/h=kW×860 Btu/h=kW×3412 cfm=m³/min×35.3

Part 3 Refrigerant Circuit

1.	Retr	igerant Circuit	6C
		RXYQ5P	
	1.2	RXYQ8P	62
	1.3	RXYQ10P, 12P	64
	1.4	RXYQ14P, 16P, 18P	66
	1.5	Outdoor air processing unit FXMQ125MFV1~250MFV1	68
2.	Fund	ctional Parts Layout	69
	2.1	RXYQ5P	69
	2.2	RXYQ8P	70
	2.3	RXYQ10P, 12P (12P: EUROPE)	71
		RXYQ12P	
	2.5	RXYQ14P, 16P, 18P	73
3.	Refr	igerant Flow for Each Operation Mode	74

Refirgerant Circuit 59

Refrigerant Circuit Si34-601A

1. Refrigerant Circuit


1.1 **RXYQ5P**

No. in refrigerant system diagram	Symbol	Name	Major Function
А	M1C	Inverter compressor (INV)	Inverter compressor is operated on frequencies between 52Hz and 188Hz by using the inverter. The number of operating steps is as follows when Inverter compressor is operated. RXYQ5P: 18 steps
D	M1F	Inverter fan	Since the system is of air heat exchanging type, the fan is operated at 9-step rotation speed by using the inverter.
E	Y1E	Electronic expansion valve (Main: EV1)	While in heating operation, PI control is applied to keep the outlet superheated degree of air heat exchanger constant.
G	Y1S	Solenoid valve (Hot gas: SVP)	Used to prevent the low pressure from transient falling.
J	Y2S	Solenoid valve (Oil return: SVO)	Used to return oil from the accumulator to the compressor.
K	Y4S	Solenoid valve (Injection) SVT	Used to cool the compressor by injecting refrigerant when the compressor discharge temperature is high.
М	Y3S	4-way valve	Used to switch the operation mode between cooling and heating.
N	S1NPH	High pressure sensor	Used to detect high pressure.
0	S1NPL	Low pressure sensor	Used to detect low pressure.
Р	S1PH	HP pressure switch (For INV compressor)	In order to prevent the increase of high pressure when a malfunction occurs, this switch is activated at high pressure of 4.0 MPa or more to stop the compressor operation.
Т	_	Pressure regulating valve 1	This valve opens at a pressure of 4.0 MPa for prevention of pressure increase, thus resulting in no damage of functional parts due to the increase of pressure in transportation or storage.
W	_	Capillary tube	Used to return the refrigerating oil separated through the oil separator to the compressor.
1	R1T	Thermistor (Outdoor air: Ta)	Used to detect outdoor temperature, correct discharge pipe temperature, and others.
2	R2T	Thermistor (Suction pipe: Ts)	Used to detect suction pipe temperature.
3	R3T	Thermistor (INV discharge pipe: Tdi)	Used to detect discharge pipe temperature, make the temperature protection control of compressor, and others.
4	R4T	Thermistor (Heat exchanger deicer: Tb)	Used to detect liquid pipe temperature of air heat exchanger, determine defrosting operation, and others.
5	R6T	Thermistor (Liquid pipe TI)	Used to detect liquid pipe temperature.
6	R7T	Thermistor (Accumulator inlet Ts1)	Used to detect gas pipe temperature at the accumulator inlet. Keep the suction superheated degree constant in heating operation, and others.

Refirgerant Circuit

Si34-601A Refrigerant Circuit

RXYQ5P



3D050782

Refirgerant Circuit 61


Refrigerant Circuit Si34-601A

1.2 RXYQ8P

No. in refrigerant system diagram	Symbol	Name	Major Function	
А	A M1C Inverter compressor (INV)		Inverter compressor is operated on frequencies between 52Hz and 266Hz by using the inverter, while Standard compressor is operated with commercial power supply only. The number of operating steps is as follows when Inverter compressor is operated in combination with Standard compressor. RXYQ8P: 24 steps	
D	M1F	Inverter fan	Since the system is of air heat exchanging type, the fan is operated at 9-step rotation speed by using the inverter.	
E	Y1E	Electronic expansion valve (Main: EV1)	While in heating operation, PI control is applied to keep the outlet superheated degree of air heat exchanger constant.	
F	Y2E	Electronic expansion valve (Subcool: EV2)	PI control is applied to keep the outlet superheated degree of subcooling heat exchanger constant.	
G	Y1S	Solenoid valve (Hot gas: SVP)	Used to prevent the low pressure from transient falling.	
J	Y2S	Solenoid valve (Oil return: SVO)	Used to return oil from the accumulator to the compressor.	
М	Y3S	4-way valve	Used to switch the operation mode between cooling and heating.	
N	S1NPH	High pressure sensor	Used to detect high pressure.	
0	O S1NPL Low pressure sensor P S1PH HP pressure switch (For INV compressor)		Used to detect low pressure.	
Р			In order to prevent the increase of high pressure when a malfunction occurs, this switch is activated at high pressure of 4.0 MPa or more to stop the compressor operation.	
Т	l	Pressure regulating valve (Liquid pipe)	This valve opens at a pressure of 4.0 MPa for prevention of pressure increase, thus resulting in no damage of functional parts due to the increase of pressure in transportation or storage.	
V	_	Subcooling heat exchanger	Used to subcool liquid refrigerant from the electronic expansion valve (cooling) or indoor units (heating).	
W	_	Capillary tube	Used to return the refrigerating oil separated through the oil separator to the INV compressor.	
1	R1T	Thermistor (Outdoor air: Ta)	Used to detect outdoor temperature, correct discharge pipe temperature, and others.	
2	R2T	Thermistor (Suction pipe: Ts)	Used to detect suction pipe temperature.	
3	R3T	Thermistor (INV discharge pipe: Tdi)	Used to detect discharge pipe temperature, make the temperature protection control of compressor, and others.	
4	4 R4T Thermistor (Heat exchanger deicer: Tb)		Used to detect liquid pipe temperature of air heat exchanger, determine defrosting operation, and others.	
5	5 R5T Thermistor (Subcooling heat exchanger gas pipe: Tsh)		Used to detect gas pipe temperature on the evaporation side of subcooling heat exchanger, keep the superheated degree at the outlet of subcooling heat exchanger constant, and others.	
6	R6T	Thermistor (Receiver outlet liquid pipe: TI)	Used to detect receiver outlet liquid pipe temperature.	
7	7 R7T Thermistor (Accumulator inlet)		Used to detect gas pipe temperature at the accumulator inlet. Keep the suction superheated degree constant in heating operation, and others.	

Si34-601A Refrigerant Circuit

RXYQ8P



3D050783


Refrigerant Circuit Si34-601A

1.3 RXYQ10P, 12P

No. in				
refrigerant system diagram	Symbol	Name	Major Function	
Α	M1C	Inverter compressor (INV)	Inverter compressor is operated on frequencies between 52Hz and 210Hz by using	
В	M2C	Standard compressor 1 (STD1)	the inverter, while Standard compressor is operated with commercial power supply only. The number of operating steps is as follows when Inverter compressor is operated in combination with Standard compressor. RXYQ10, 12P: 37 steps	
D	M1F	Inverter fan	Since the system is of air heat exchanging type, the fan is operated at 9-step rotation speed by using the inverter.	
E	Y1E	Electronic expansion valve (Main: EV1)	While in heating operation, PI control is applied to keep the outlet superheated degree of air heat exchanger constant.	
F	Y2E	Electronic expansion valve (Subcool: EV3)	PI control is applied to keep the outlet superheated degree of subcooling heat exchanger constant.	
G	Y1S	Solenoid valve (Hot gas: SVP)	Used to prevent the low pressure from transient falling.	
J	Y2S	Solenoid valve (Oil return: SVO)	Used to return oil from the accumulator to the compressor.	
М	Y3S	4-way valve	Used to switch the operation mode between cooling and heating.	
N	S1NPH	High pressure sensor	Used to detect high pressure.	
0	S1NPL	Low pressure sensor	Used to detect low pressure.	
Р	S1PH	HP pressure switch (For INV compressor)	In order to prevent the increase of high pressure when a malfunction occurs, this switch is activated at high pressure of 4.0 MPa or more to stop the compressor	
Q	S2PH	HP pressure switch (For STD compressor 1)	operation.	
U		Pressure regulating valve (Liquid pipe)	This valve opens at a pressure of 4.0 MPa for prevention of pressure increase, thus resulting in no damage of functional parts due to the increase of pressure in transportation or storage.	
٧	_	Subcooling heat exchanger	Used to subcool liquid refrigerant from the electronic expansion valve (cooling) or indoor units (heating).	
W	_	Capillary tube	Used to return the refrigerating oil separated through the oil separator to the INV compressor.	
Х	_	Capillary tube	Used to return the refrigerating oil separated through the oil separator to the STD1 compressor.	
1	R1T	Thermistor (Outdoor air: Ta)	Used to detect outdoor temperature, correct discharge pipe temperature, and others.	
2	R2T	Thermistor (Suction pipe: Ts)	Used to detect suction pipe temperature.	
3	R31T	Thermistor (INV discharge pipe: Tdi)	Used to detect discharge pipe temperature, make the temperature protection control of	
4	R32T	Thermistor (STD1 discharge pipe: Tds1)	compressor, and others.	
5	R4T	Thermistor (Heat exchanger deicer: Tb)	Used to detect liquid pipe temperature of air heat exchanger, determine defrosting operation, and others.	
6	R5T	Thermistor (Subcooling heat exchanger gas pipe: Tsh)	Used to detect gas pipe temperature on the evaporation side of subcooling heat exchanger, keep the superheated degree at the outlet of subcooling heat exchanger constant, and others.	
7	R6T	Thermistor (Liquid pipe: TI)	Used to detect liquid pipe temperature.	
8	R7T	Thermistor (Accumulator inlet)	inlet) Used to detect gas pipe temperature at the accumulator inlet. Keep the suction superheated degree constant in heating operation, and others.	

Si34-601A Refrigerant Circuit

RXYQ10P, 12P



3D050784


Refrigerant Circuit Si34-601A

1.4 RXYQ14P, 16P, 18P

			<u> </u>	
No. in refrigerant system diagram	Symbol	Name	Major Function	
Α	M1C	Inverter compressor (INV)	Inverter compressor is operated on frequencies between 52Hz and 266Hz by using	
В	M2C	Standard compressor 1 (STD1)	the inverter, while Standard compressor is operated with commercial power supply only. The number of operating steps is as follows when Inverter compressor is operated in combination with Standard compressor.	
С	МЗС	Standard compressor 1 (STD2)	operated in combination with Standard compressor. RXYQ14P or 16P : 51 steps, RXYQ18P : 55 steps	
D	M1F	Inverter fan	Since the system is of air heat exchanging type, the fan is operated at 8-step rotation speed by using the inverter.	
E	Y1E	Electronic expansion valve (Main: EV1)	While in heating operation, PI control is applied to keep the outlet superheated degree of air heat exchanger constant.	
F	Y2E	Electronic expansion valve (Subcool: EV3)	PI control is applied to keep the outlet superheated degree of subcooling heat exchanger constant.	
G	Y1S	Solenoid valve (Hot gas: SVP)	Used to prevent the low pressure from transient falling.	
J	Y2S	Solenoid valve (Oil return: SVO)	Used to return oil from the accumulator to the compressor.	
М	Y3S	4-way valve	Used to switch the operation mode between cooling and heating.	
N	S1NPH	High pressure sensor	Used to detect high pressure.	
0	S1NPL	Low pressure sensor	Used to detect low pressure.	
Р	S1PH	HP pressure switch (For INV compressor)		
Q	S2PH	HP pressure switch (For STD compressor 1)	In order to prevent the increase of high pressure when a malfunction occurs, this switch is activated at high pressure of 4.0 MPa or more to stop the compressor operation.	
R	S3PH	HP pressure switch (For STD compressor 2)	operation.	
U	_	Pressure regulating valve (Liquid pipe)	This valve opens at a pressure of 4.0 MPa for prevention of pressure increase, thus resulting in no damage of functional parts due to the increase of pressure in transportation or storage.	
V		Subcooling heat exchanger	Used to subcool liquid refrigerant from the electronic expansion valve (cooling) or indoor units (heating).	
W	_	Capillary tube	Used to return the refrigerating oil separated through the oil separator to the INV compressor.	
Х		Capillary tube	Used to return the refrigerating oil separated through the oil separator to the STD1 compressor.	
Υ	1	Capillary tube	Used to return the refrigerating oil separated through the oil separator to the STD2 compressor.	
1	R1T	Thermistor (Outdoor air: Ta)	Used to detect outdoor temperature, correct discharge pipe temperature, and others.	
2	R2T	Thermistor (Suction pipe: Ts)	Used to detect suction pipe temperature.	
3	R31T	Thermistor (INV discharge pipe: Tdi)		
4	R32T	Thermistor (STD1 discharge pipe: Tds1)	Used to detect discharge pipe temperature, make the temperature protection control of compressor, and others.	
5	R33T	Thermistor (STD2 discharge pipe: Tds2)		
6	R4T	Thermistor (Heat exchanger deicer: Tb)	Used to detect liquid pipe temperature of air heat exchanger, determine defrosting operation, and others.	
7	R5T	Thermistor (Subcooling heat exchanger gas pipe: Tsh)	at Used to detect gas pipe temperature on the evaporation side of subcooling heat exchanger, keep the superheated degree at the outlet of subcooling heat exchanger constant, and others.	
8	R6T	Thermistor (Liquid pipe: TI)	TI) Used to detect liquid pipe temperature.	
9	R7T	Thermistor (Accumulator inlet)	et) Used to detect gas pipe temperature at the accumulator inlet. Keep the suction superheated degree constant in heating operation, and others.	

Si34-601A Refrigerant Circuit

RXYQ14P, 16P, 18P




3D050785

Refrigerant Circuit Si34-601A

1.5 Outdoor air processing unit FXMQ125MFV1~250MFV1

1.5.1 Refrigerant System



Main Control Equipment

Code	Symbol	Name	Main function		
А	A Y1E Motorized valve		Used to control the flow rate of refrigerant, and make the SH control while in cooling or the SC control while in heating.*		
В	B Y1S Solenoid valve		Used to bypass hot gas while in heating with thermostat OFF.		
С	_	Capillary tube	Used to reduce pressure from high to low in bypassing hot gas.		

^{*}SH control: Superheated control of heat exchanger outlet

SC control: Subcooling control of heat exchanger outlet


Thermistor

Code	Symbol	Name	Main function	
Th1	R1T	Suction air temperature thermistor	Used to turn ON or OFF the thermostat and select cooling or heating operation.	
Th2	Th2 R2T Liquid pipe temperature thermistor		Used to control the opening degree of EV (Y1F) under the SC control.	
Th3 R3T		Gas pipe temperature thermistor	Used to control the opening degree of EV (Y1E) under the SH control.	
Th4	R4T	Discharge air temperature thermistor	Used to control the electric expansion valve opening and thermostat ON/OFF so as to keep the discharge air temperature at the set temperature.	


2. Functional Parts Layout

2.1 **RXYQ5P**

Plan




Front View




Functional Parts Layout Si34-601A

2.2 RXYQ8P

Plan




Front View




2.3 RXYQ10P, 12P (12P: EUROPE)

Plan




Front View




Functional Parts Layout Si34-601A

2.4 RXYQ12P

Plan




Front View




2.5 RXYQ14P, 16P, 18P

Plan




Front View




3. Refrigerant Flow for Each Operation Mode

RXYQ5P


Cooling Operation




Cooling Oil Return Operation




Heating Oil Return & Defrost Operation




Heating Operation




RXYQ8P Cooling Operation




Cooling Oil Return



Heating Oil Return & Defrost




Heating Operation




RXYQ10P, 12P


Cooling Operation




Cooling Oil Return



Heating Oil Return & Defrost




Heating Operation




RXYQ14P, 16P, 18P


Cooling Operation




Cooling Oil Return Operation



Heating Oil Return & Defrost Operation



Heating Operation



Part 4 Function

1.	Fund	tion general	92
	1.1	Symbol	92
	1.2	Operation Mode	93
2.	Basic	c Control	94
	2.1	Normal Operation	
	2.2	Compressor PI Control	
	2.3	Electronic Expansion Valve PI Control	
	2.4	Step Control of Outdoor Unit Fans	
	2.5	Outdoor Unit Fan Control in Cooling Operation	
3.	Spec	cial Control	109
٠.	3.1	Startup Control	
	3.2	Large capacity start up control (Heating)	
	3.3	Oil Return Operation	
	3.4	Defrosting Operation	
	3.5	Pump-down Residual Operation	
	3.6	Standby	
	3.7	Stopping Operation	116
4.	Prote	ection Control	
	4.1	High Pressure Protection Control	
	4.2	Low Pressure Protection Control	
	4.3	Discharge Pipe Protection Control	
	4.4	Inverter Protection Control	
	4.5	STD Compressor Overload Protection	
	4.6	Injection Control (only for RXYQ5P)	
5.	Othe	r Control	
٥.	5.1	Outdoor Unit Rotation	
	5.2	Emergency Operation	
	5.3	Demand Operation	
	5.4	Heating Operation Prohibition	
6	Outli	ne of Control (Indoor Unit)	
Ο.	6.1	Drain Pump Control	
		Louver Control for Preventing Ceiling Dirt	
	6.3	Thermostat Sensor in Remote Controller	
	6.4	Thermostat Control While in Normal Operation	
	6.5	Thermostat Control in Dry Operation	
	6.6	Electronic Expansion Valve Control	
	6.7	Hot Start Control (In Heating Operation Only)	
	6.8	Freeze Prevention	
	6.9	Heater Control	
		List of Swing Flap Operations	
		Control of Outdoor Air Processing Unit	
		(Unique Control for Outdoor Air Processing Unit)	138
		• • • • • • • • • • • • • • • • • • • •	

Function general Si34-601A


1. Function general

1.1 Symbol

Symbol	Electric symbol	Description or function	
20S1	Y3S	Four way valve (Energize during heating)	
DSH	-	Discharge pipe superheated degree	
DSHi	-	Discharge pipe superheat of inverter compressor	
DSHs	_	Discharge pipe superheat of standard compressor	
EV	_	Opening of electronic expansion valve	
EV1	Y1E	Electronic expansion valve for main heat exchanger	
EV2	Y2E	Electronic expansion valve for sub-coolig heat exchanger	
HTDi	_	Value of INV compressor discharge pipe temperature (R31T) compensated with outdoor air temperature	
HTDs	_	Value of STD compressor discharge pipe temperature (R32T, R33T) compensated with outdoor air temperature	
Pc	S1NPH	Value detected by high pressure sensor	
Pe	S1NPL	Value detected by low pressure sensor	
SH	_	Evaporator outlet superheat	
SHS	_	Target evaporator outlet superheat	
SVO	Y2S	Solenoid valve for oil return	
SVP	Y1S	Solenoid valve for hot gas bypass	
SVT	Y4S	Solenoid valve for injection	
Та	R1T (A1P)	Outdoor air temperature	
Tb	R4T	Heat exchanger outlet temperature at cooling	
Ts2	R2T	Suction pipe temperature detected with the suction pipe thermistor (R2T)	
Tsh	R5T (–)	Temperature detected with the subcooling heat exchanger outlet thermistor (R5T)	
Tc	_	High pressure equivalent saturation temperature	
TcS	_	Target temperature of Tc	
Te	_	Low pressure equivalent saturation temperature	
TeS	_	Target temperature of Te	
Tfin	R1T	Inverter fin temperature	
TI	R6T	Liquid pipe temperature detected with the liquid pipe thermistor (R6T)	
Тр	_	Calculated value of compressor port temperature	
Ts1	R7T	Suction pipe temperature detected with the accumulator inlet thermistor	

Si34-601A Function general

1.2 Operation Mode



Basic Control Si34-601A

2. Basic Control

2.1 Normal Operation

2.1.1 List of Functions in Normal Operation

Part Name	Symbol	(Electric	Function of Functional Part	
Fait Name	Syllibol	Symbol)	Normal Cooling	Normal Heating
Compressor	_	(M1C, M2C)	PI control, High pressure protection, Low pressure protection, Td protection, INV protection,	PI control, High pressure protection, Low pressure protection, Td protection, INV protection,
Outdoor unit fan		(M1F)	Cooling fan control	Step 7 or 8
Four way valve	20S1	(Y1R)	OFF	ON
Main motorized valve	EV1	(Y1E)	480 pls	PI control
Subcool heat exchanger electronic expansion valve	EV2	(Y2E)	PI control	PI control
Hot gas bypass valve	SVP	(Y1S)	OFF	Energized when the system is set to low pressure control mode
Accumulator oil return valve	SV0	(Y2S)	ON	ON

Indoor unit actuator		Normal cooling	Normal heating
	Thermostat ON unit	Remote controller setting	Remote controller setting
Fan	Stopping unit	OFF	OFF
	Thermostat OFF unit	Remote controller setting	LL
Electronic	Thermostat ON unit	Normal opening *1	Normal opening *2
expansion	Stopping unit	0 pls	200 pls
valve	Thermostat OFF unit	0 pls	200 pls

^{*1.} PI control: Evaporator outlet superheated degree (SH) constant.

^{*2.} PI control: Condenser outlet subcooled degree (SC) constant.

^{*1} and 2: Refer "6.6 Electronic expansion valve control" on page 135.

Si34-601A Basic Control

2.2 Compressor PI Control

Compressor PI Control

Carries out the compressor capacity PI control to maintain Te at constant during cooling operation and Tc at constant during heating operation to ensure stable unit performance.

[Cooling operation]

Controls compressor capacity to adjust Te to achieve target value (TeS).

Te set value (Make this setting while in Setting mode 2.)

Te setting

	L	M (Normal) (factory setting)	Ι
ſ	3	6	9

Te: Low pressure equivalent saturation temperature (°C)

TeS: Target Te value

(Varies depending on Te setting, operating frequency, etc.)

*On multi-outdoor-unit systems, this control is made according to values of the first-priority unit, which is detected with the pressure sensor.

[Heating operation]

Controls compressor capacity to adjust Tc to achieve target value (TcS).

Te set value (Make this setting while in Setting mode 2.)

Tc setting

L	L M (Normal) (factory setting)	
43	46	49

c: High pressure equivalent saturation temperature (°C)


TcS: Target Tc value

(Varies depending on Tc setting, operating frequency, etc.)

*On multi-outdoor-unit systems, this control is made according to values of the first-priority unit, which is detected with the pressure sensor.


Basic Control Si34-601A

Operating Priority and Rotation of Compressors (For multi standard connection system)




Si34-601A Basic Control






RXYQ46P, 48P



RXYQ50P, 52P, 54P



- *
- In the case of combination of 3 outdoor units, the above diagram shows master unit, slave unit 1, and slave unit 2 from left to right.
- Compressors may operate in any pattern other than those mentioned above according to the operating status.

Basic Control Si34-601A

■ Compressor Step Control (Multi outdoor unit connection is available on the standard connection system) Compressor operations vary with the following steps according to information in "2.2 Compressor PI Control". Furthermore, the operating priority of compressors is subject to information in "■ Operating Priority and Rotation of Compressors".

Stand-alone installation

RXY	Q5	PY1
-----	----	-----

RXYQ8PY1

1XYQ5	PYI	TAT QOFTI				
STEP No.	INV	STEP No.	IN\			
1	52 Hz	1	52 F			
2	56 Hz	2	56 F			
3	62 Hz		62 F			
4	68 Hz	4	68 F			
4 5 6 7	74 Hz	4 5 6	74 F			
6	80 Hz	6	80 F			
7	88 Hz	7	88 F			
8	96 Hz	8 9	96 F			
9	104 Hz	9	104			
10	110 Hz	10 11	110			
11	116 Hz	11	116			
11 12	124 Hz	12	124			
13	132 Hz	13	132			
14	144 Hz	14 15	144			
15	158 Hz	15	158			
16	166 Hz	16	166			
17	176 Hz	17	176			
18	188 Hz	18	188			
		19	202			
		20	210			
		21	218			

STEP No.	INV	STD1
1	52 Hz	OFF
2	56 Hz	OFF
3	62 Hz	OFF
4	68 Hz	OFF
5	74 Hz	OFF
6	80 Hz	ÖFF
7	88 Hz	OFF
8	96 Hz	OFF
9	104 Hz	OFF
10	110 Hz	OFF
11	116 Hz	OFF
12 13	124 Hz 132 Hz	OFF
13	132 Hz	OFF
14	144 Hz	OFF
15	158 Hz	OFF
16	166 Hz	OFF
17	176 Hz	OFF
18	188 Hz	OFF
19	202 Hz	OFF
20	210 Hz	OFF
21	52 Hz	ON
22	62 Hz	ON
23	68 Hz	ON
24	74 Hz	ON
25	80 Hz	ON ON
26	88 Hz	ON
27	96 Hz	ON
28	104 Hz	ON
29	116 Hz	ON
30	124 Hz	ON ON
31	132 Hz	
32 33	144 Hz	ON ON
33	158 Hz	ON
	176 Hz	ON
35	188 Hz 202 Hz	ON
<u>36</u> 37	202 Hz	ON
٥/	210 HZ	ON

DVVO14DV1 16DV1

STEP No.	INV	STD1	STD2
1	52 Hz	OFF	OFF
2	56 Hz	OFF	OFF
3	62 Hz	ÖFF	ÖFF
4	68 Hz	OFF	OFF
5	74 Hz	OFF	OFF
6	80 Hz	OFF	ÖFF
7	88 Hz	OFF	ÖFF
8	96 Hz	OFF	OFF
9	104 Hz	ÖFF	ÖFF
10	110 Hz	OFF	OFF
11	116 Hz	OFF	ÖFF
12	124 Hz	ÖFF	ÖFF
13	132 Hz	OFF	OFF
14	144 Hz	OFF	OFF
15	158 Hz	OFF	OFF
16	166 Hz	OFF	OFF
17	176 Hz	OFF	OFF
18	188 Hz	OFF	OFF
19	202 Hz	OFF	OFF
20	210 Hz	OFF	OFF
21	52 Hz	ON	OFF
22	62 Hz	ON	OFF
23	68 Hz	ON	OFF
24	74 Hz	ON	OFF
25	80 Hz	ON	OFF
26	88 Hz	ON	OFF
27	96 Hz	ON	OFF
28	104 Hz	ON	OFF
29	116 Hz	ON	OFF
30	124 Hz	ON	OFF
31	132 Hz	ON	OFF
	144 Hz	ON	OFF
32 33	158 Hz	ON	OFF
			OFF
34	176 Hz	ON ON	OFF
35	188 Hz		OFF
36	202 Hz	ON	OFF
37	210 Hz	ON	OFF
38	52 Hz	ON	ON
39	62 Hz	ON	ON ON
40	74 Hz	ON	
41	88 Hz	ON	ON
42	96 Hz	ON	ON
43	104 Hz	ON	ON
44	124 Hz	ON	ON
45	144 Hz	ON	ON
46	158 Hz	ON	ON
47	166 Hz	ON	ON
48	176 Hz	ON	ON
49	188 Hz	ON	ON
50	202 Hz	ON	ON
51	210 Hz	ON	ON

RXYQ18PY1

	STEP No.	INV	STD1	STD2
7	1	52 Hz	OFF	OFF
7	2	56 Hz	OFF	OFF
	3	62 Hz	OFF	OFF
	4	68 Hz	OFF	OFF
	5	74 Hz	OFF	OFF
	6	80 Hz	OFF	OFF
	7	88 Hz	OFF	OFF
	8	96 Hz	OFF	OFF
	9	104 Hz	OFF	OFF
	10	110 Hz	OFF	OFF
	11	116 Hz	OFF	OFF
	12	124 Hz	OFF	OFF
	13	132 Hz	OFF	OFF
	14	144 Hz	OFF	OFF
	15	158 Hz	OFF	OFF
	16	166 Hz	OFF	OFF
	17	176 Hz	OFF	OFF
	18	188 Hz	OFF	OFF
	19	202 Hz	OFF	OFF
	20	210 Hz	OFF	OFF
	21	52 Hz	ON	OFF
	22	62 Hz	ON	OFF
	23	68 Hz	ON	OFF
_	24	74 Hz	ON	OFF
_	25	80 Hz	ON ON	OFF OFF
_	26	88 Hz		
_	27 28	96 Hz 104 Hz	ON ON	OFF OFF
_	29	116 Hz	ON	OFF
_	30	124 Hz	ON	OFF
_	31	132 Hz	ON	OFF
-	32	144 Hz	ON	OFF
-	33	158 Hz	ON	OFF
-	34	176 Hz	ON	OFF
-	35	188 Hz	ON	OFF
-	36	202 Hz	ON	OFF
-	37	210 Hz	ON	OFF
	38	52 Hz	ON	ON
	39	62 Hz	ON	ON
-	40	74 Hz	ON	ON
	41	88 Hz	ON	ÖN
	42	96 Hz	ON	ON
	43	104 Hz	ON	ON
	44	124 Hz	ON	ON
	45	144 Hz	ON	ON
	46	158 Hz	ON	ON
	47	166 Hz	ON	ON
	48	176 Hz	ON	ON
	49	188 Hz	ON	ON
	50	202 Hz	ON	ON
	51	210 Hz	ON	ON
	52	218 Hz	ON	ON
	53	232 Hz	ON	ON
	54	248 Hz	ON	ON
	55	266 Hz	ON	ON

Notes:

1. INV: Inverter compressor

STD1: Standard compressor 1 STD2 : Standard compressor 2

2. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Si34-601A Basic Control

Two-unit multi system

RXYQ20PY1 (8+12HP)

(To increase Step No.) (To decrease Step No.) Master STEP No. STEP No. STD unit INV OFF OFF unit INV 52 Hz 56 Hz unit INV 62 Hz 62 Hz 66 Hz 66 Hz 74 Hz 74 Hz 80 Hz 80 Hz 88 Hz 88 Hz 96 Hz 96 Hz 104 Hz 104 Hz 110 Hz 110 Hz 116 Hz 116 Hz 124 Hz 124 Hz 132 Hz 132 Hz 144 Hz 144 Hz 62 Hz 66 Hz 158 Hz 158 Hz 166 Hz 166 Hz 176 Hz 176 Hz 80 Hz 80 Hz 88 Hz 88 Hz 96 Hz 96 Hz 124 Hz 124 Hz 132 Hz 132 Hz 144 Hz 144 Hz 158 Hz 158 Hz 124 Hz 132 Hz 52 Hz 62 Hz ON ON ON ON ON 80 Hz 80 Hz 210 Hz 210 Hz 218 Hz 210 Hz 232 Hz 210 Hz 124 Hz 124 Hz 132 Hz 132 Hz 144 Hz 144 Hz 158 Hz 158 Hz 176 Hz 176 Hz 188 Hz 188 Hz 202 Hz 202 Hz 210 Hz 210 Hz 218 Hz 210 Hz 232 Hz 210 Hz 248 Hz 210 Hz ON ON ON ON ON ON 248 Hz | 210 Hz 266 Hz | 210 Hz

represents the range in which "Hz" is not stepped up. RXYQ22PY1 (10+12HP)

(To increase Step No.)						(To decrease Step No.)				
TEP	Master	Slave		A	OTED	CTED Master Slave				
No.	unit	unit	STD	١Ŧ.	STEP	unit	unit	STD		
	INV	INV		Ш	No.	INV	INV	_		
1	52 Hz	52 Hz	OFF	Ш	1	52 Hz	OFF	OFF		
2	56 Hz	56 Hz	OFF	Ш	2	56 Hz	OFF	OFF		
3	62 Hz	62 Hz	OFF	Ш	3	62 Hz	OFF	ÖFF		
4	66 Hz	66 Hz	OFF	Ш	4	68 Hz	OFF	OFF		
5	70 Hz	70 Hz	OFF	Ш	5	74 Hz	OFF	OFF		
6	74 Hz	74 Hz	OFF	Ш	6	80 Hz	OFF	OFF		
7	80 Hz	80 Hz	OFF	Ш	7	88 Hz	OFF	OFF		
8	88 Hz	88 Hz	OFF	Ш	8	96 Hz	OFF	OFF		
9	96 Hz	96 Hz	OFF	Ш	9	104 Hz	OFF	ÖFF		
10	104 Hz	104 Hz	OFF	Ш	10	52 Hz	52 Hz	OFF		
11	110 Hz	110 Hz	OFF	Ш	11	56 Hz	56 Hz	ÖFF		
12	116 Hz	116 Hz	OFF	Ш	12	62 Hz	62 Hz	ÖFF		
13	124 Hz	124 Hz	OFF	Ш	13	66 Hz	66 Hz	OFF		
14	132 Hz	132 Hz	OFF	Ш	14	70 Hz	70 Hz	ÖFF		
15	144 Hz	144 Hz	OFF	Ш	15	74 Hz	74 Hz	ÖFF		
16	158 Hz	158 Hz	OFF	Ш	16	80 Hz	80 Hz	ÖFF		
17	166 Hz	166 Hz	OFF	Ш	17	88 Hz	88 Hz	ÖFF		
18	176 Hz	176 Hz	OFF	Ш	18	92 Hz	92 Hz	ÖFF		
19	80 Hz	80 Hz	ON 1	Ш	19	96 Hz	96 Hz	OFF		
20	88 Hz	88 Hz	ON 1	Ш	20	104 Hz	104 Hz	OFF		
21	96 Hz	96 Hz	ON 1	Ш	21	110 Hz	110 Hz	OFF		
22	104 Hz	104 Hz	ON 1	Ш	22	116 Hz	116 Hz	OFF		
23	116 Hz	116 Hz	ON 1	Ш	23	124 Hz	124 Hz	OFF		
24	124 Hz	124 Hz	ON 1	Ш	24	132 Hz	132 Hz	OFF		
25	132 Hz	132 Hz	ON 1	Ш	25	52 Hz	52 Hz	ON 1		
26	88 Hz	88 Hz	ON 2	Ш	26	62 Hz	62 Hz	ON 1		
27	96 Hz	96 Hz	ON 2	Ш	27	68 Hz	68 Hz	ON 1		
28	104 Hz	104 Hz	ON 2	Ш	28	74 Hz	74 Hz	ON 1		
29	124 Hz	124 Hz	ON 2	Ш	29	80 Hz	80 Hz	ON 1		
30	144 Hz	144 Hz	ON 2	Ш	30	88 Hz	88 Hz	ON 1		
31	158 Hz	158 Hz	ON 2	Ш	31	96 Hz	96 Hz	ON 1		
32	166 Hz	166 Hz	ON 2	Ш	32	104 Hz	104 Hz	ON 1		
33	176 Hz	176 Hz	ON 2	Ш	33	52 Hz	52 Hz	ON 2		
34	188 Hz	188 Hz	ON 2	П	34	62 Hz	62 Hz	ON 2		
35	202 Hz	202 Hz	ON 2	П	35	74 Hz	74 Hz	ON 2		
36	210 Hz	210 Hz	ON 2	П	36	88 Hz	88 Hz	ON 2		
				1	37	96 Hz	96 Hz	ON 2		
				Т	38	104 Hz	104 Hz	ON 2		
				Т	39	124 Hz	124 Hz	ON 2		
				1	40	144 Hz	144 Hz	ON 2		
				1	41	158 Hz	158 Hz	ON 2		
				1	42	166 Hz	166 Hz	ON 2		
				1	43	176 Hz	176 Hz	ON 2		
				1	44	188 Hz	188 Hz	ON 2		
				1	45	202 Hz	202 Hz	ON 2		
				1	46	210 Hz	210 Hz	ON 2		
				-1	70	LIVIIZ	Z1011Z	0112		

Notes:

1. INV: Inverter compressor

STD: Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Basic Control Si34-601A

RXYQ26PY1 (8+18HP)

represents the range in which "Hz" is not stepped up.

RXYQ24PY1 (8+16HP)

(To increase Step No.) (To increase Step No.) (To decrease Step No.) (To decrease Step No.) Master Master Master STEP STEP STD STD STD STD unit unit INV unit INV INV INV INV INV INV 56 Hz 88 Hz 88 Hz 96 Hz 96 Hz 104 Hz 104 Hz 110 Hz 110 Hz 96 HZ 96 HZ 104 HZ 104 HZ 110 HZ 110 HZ 116 HZ 116 HZ 124 HZ 124 HZ 52 Hz 56 Hz 62 Hz 66 Hz 10 10 116 Hz 116 Hz 124 Hz 124 Hz 132 Hz 132 Hz 144 Hz 144 Hz 158 Hz 158 Hz 166 Hz 166 Hz 176 Hz 176 Hz OFF OFF 15 158 Hz 158 Hz 166 Hz 166 Hz 176 Hz 176 Hz 16 16 80 Hz 80 Hz 80 Hz 80 Hz 80 Hz 80 Hz 96 Hz 80 Hz 80 Hz 96 Hz 90 Hz 90 Hz 9N H 96 Hz 96 Hz 9N 1 104 Hz 104 Hz 9N 1 116 Hz 116 Hz 9N 1 124 Hz 124 Hz 9N 1 132 Hz 132 Hz 9N 1 98 Hz 98 Hz 9N 2 104 Hz 104 Hz 110 Hz 110 Hz 100 Hz 100 Hz OFF 110 Hz 110 Hz OFF 116 Hz 116 Hz OFF 124 Hz 124 Hz OFF 132 Hz 132 Hz OFF 52 Hz 52 Hz ON 1 62 Hz 62 Hz ON 1 74 Hz 74 Hz ON 1 88 Hz 88 Hz ON 1 104 Hz 104 Hz ON 2 62 Hz 62 Hz ON 2 64 Hz 65 Hz ON 1 104 Hz 104 Hz ON 2 88 Hz 88 Hz ON 2 74 Hz 74 Hz ON 2 88 Hz 88 Hz ON 2 104 Hz 104 Hz ON 2 105 Hz 96 Hz ON 2 104 Hz 104 Hz ON 2 105 Hz 144 Hz ON 2 115 Hz 158 Hz ON 2 116 Hz 116 Hz 124 Hz 124 Hz 132 Hz 132 Hz 132 Hz 132 Hz ON 1 88 Hz 88 Hz ON 2 96 Hz 96 Hz ON 2 104 Hz 104 Hz ON 2 124 Hz 124 Hz ON 2 144 Hz 124 Hz ON 2 158 Hz 158 Hz ON 2 166 Hz 166 Hz ON 2 176 Hz 176 Hz ON 2 202 Hz 202 Hz ON 2 218 Hz 210 Hz ON 2 2248 Hz 210 Hz ON 2 266 Hz 210 Hz ON 2 80 Hz 80 Hz 88 Hz 88 Hz 96 Hz 96 Hz 104 Hz 104 Hz 52 Hz 52 Hz 62 Hz 62 Hz 38 39 40 144 Hz 144 Hz 158 Hz 158 Hz 166 Hz 166 Hz 176 Hz 176 Hz 188 Hz 188 Hz 202 Hz 202 Hz 210 Hz 210 Hz 218 Hz 218 Hz 232 Hz 232 Hz 41 45

Notes:

1. INV: Inverter compressor

STD: Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Si34-601A Basic Control

represents the range in which "Hz" is not stepped up.

RXYQ28PY1, 30PY1 (10/12+18HP)

RXYQ 32PY1 (16+16HP)

(To increase Step No.)	(To decrease Step No.)	(To increase Step No.)	(To decrease Step No.)
OTED Master Slave	Master Slave	STEP Massiter Slave CTD	A Master I Oleve I
STEF unit unit STD	T STEF unit unit STD	SIEF unit unit STD 1	T No unit STD
II INV I INV I	I I IIV I IIV I	II INV I INV I	I IIIV I IIIV I
1 52 Hz 52 Hz OFF 2 56 Hz 56 Hz OFF	1 52 Hz OFF OFF 2 56 Hz OFF OFF	1 52 Hz 52 Hz OFF 2 56 Hz 56 Hz OFF	1 52 Hz OFF OFF 2 56 Hz OFF OFF
3 62 Hz 62 Hz OFF	3 62 Hz OFF OFF	3 62 Hz 62 Hz OFF	3 62 Hz OFF OFF
4 66 Hz 66 Hz OFF	4 68 Hz OFF OFF	4 66 Hz 66 Hz OFF	4 68 Hz OFF OFF
5 70 Hz 70 Hz OFF	5 74 Hz OFF OFF	5 70 Hz 70 Hz OFF	5 74 Hz OFF OFF
6 74 Hz 74 Hz OFF 7 80 Hz 80 Hz OFF	6 80 Hz OFF OFF 7 88 Hz OFF OFF	6 74 Hz 74 Hz OFF 7 80 Hz 80 Hz OFF	6 80 Hz OFF OFF 7 88 Hz OFF OFF
7 80 Hz 80 Hz OFF 8 88 Hz 88 Hz OFF	7 88 Hz OFF OFF 8 96 Hz OFF OFF	7 80 Hz 80 Hz OFF 8 88 Hz 88 Hz OFF	7 88 Hz OFF OFF 8 96 Hz OFF OFF
9 96 Hz 96 Hz OFF	9 104 Hz OFF OFF	9 96 Hz 96 Hz OFF	9 104 Hz OFF OFF
10 104 Hz 104 Hz OFF	10 52 Hz 52 Hz OFF	10 104 Hz 104 Hz OFF	10 52 Hz 52 Hz OFF
11 110 Hz 110 Hz OFF	11 56 Hz 56 Hz OFF	11 110 Hz 110 Hz OFF	11 56 Hz 56 Hz OFF
12 116 Hz 116 Hz OFF 13 124 Hz 124 Hz OFF	12 62 Hz 62 Hz OFF 13 66 Hz 66 Hz OFF	12 116 Hz 116 Hz OFF 13 124 Hz 124 Hz OFF	12 62 Hz 62 Hz OFF 13 66 Hz 66 Hz OFF
14 132 Hz 132 Hz OFF	14 70 Hz 70 Hz OFF	14 132 Hz 132 Hz OFF	14 70 Hz 70 Hz OFF
15 144 Hz 144 Hz OFF	15 74 Hz 74 Hz OFF	15 144 Hz 144 Hz OFF	15 74 Hz 74 Hz OFF
16 158 Hz 158 Hz OFF	16 80 Hz 80 Hz OFF	16 158 Hz 158 Hz OFF	16 80 Hz 80 Hz OFF
17 166 Hz 166 Hz OFF	17 88 Hz 88 Hz OFF	17 166 Hz 166 Hz OFF	17 88 Hz 88 Hz OFF 18 92 Hz 92 Hz OFF
18 176 Hz 176 Hz OFF 19 80 Hz 80 Hz ON 1	18 92 Hz 92 Hz OFF 19 96 Hz 96 Hz OFF	18 176 Hz 176 Hz OFF 19 80 Hz 80 Hz ON 1	18 92 Hz 92 Hz OFF 19 96 Hz 96 Hz OFF
20 88 Hz 88 Hz ON 1	20 104 Hz 104 Hz OFF	20 88 Hz 88 Hz ON 1	20 104 Hz 104 Hz OFF
21 96 Hz 96 Hz ON 1	21 110 Hz 110 Hz OFF	21 96 Hz 96 Hz ON 1	21 110 Hz 110 Hz OFF
22 104 Hz 104 Hz ON 1	22 116 Hz 116 Hz OFF	22 104 Hz 104 Hz ON 1	22 116 Hz 116 Hz OFF
23 116 Hz 116 Hz ON 1 24 124 Hz 124 Hz ON 1	23 124 Hz 124 Hz OFF 24 132 Hz 132 Hz OFF	23 116 Hz 116 Hz ON 1 24 124 Hz 124 Hz ON 1	23 124 Hz 124 Hz OFF 24 132 Hz 132 Hz OFF
25 132 Hz 132 Hz ON 1	25 52 Hz 52 Hz ON 1	25 132 Hz 132 Hz ON 1	25 52 Hz 52 Hz OPF
26 88 Hz 88 Hz ON 2	26 62 Hz 62 Hz ON 1	26 88 Hz 88 Hz ON 2 27 96 Hz 96 Hz ON 2	26 62 Hz 62 Hz ON 1
27 96 Hz 96 Hz ON 2	27 68 Hz 68 Hz ON 1	27 96 Hz 96 Hz ON 2	27 68 Hz 68 Hz ON 1
28 104 Hz 104 Hz ON 2 29 124 Hz 124 Hz ON 2	28 74 Hz 74 Hz ON 1	28 104 Hz 104 Hz ON 2	28 74 Hz 74 Hz ON 1
29 124 Hz 124 Hz ON 2 30 144 Hz 144 Hz ON 2	29 80 Hz 80 Hz ON 1 30 88 Hz 88 Hz ON 1	29 124 Hz 124 Hz ON 2 30 144 Hz 144 Hz ON 2	29 80 Hz 80 Hz ON 1 30 88 Hz 88 Hz ON 1
31 92 Hz 92 Hz ON 3	31 96 Hz 96 Hz ON 1	31 92 Hz 96 Hz ON 3	31 96 Hz 96 Hz ON 1
32 104 Hz 104 Hz ON 3	32 104 Hz 104 Hz ON 1	32 104 Hz 104 Hz ON 3	32 104 Hz 104 Hz ON 1
33 116 Hz 116 Hz ON 3	33 52 Hz 52 Hz ON 2	33 116 Hz 116 Hz ON 3	33 52 Hz 52 Hz ON 2
34 124 Hz 124 Hz ON 3 35 144 Hz 144 Hz ON 3	34 62 Hz 62 Hz ON 2 35 74 Hz 74 Hz ON 2	34 124 Hz 124 Hz ON 3 35 144 Hz 144 Hz ON 3	34 62 Hz 62 Hz ON 2 35 74 Hz 74 Hz ON 2
36 158 Hz 158 Hz ON 3	36 88 Hz 88 Hz ON 2	36 96 Hz 96 Hz ON 4	36 88 Hz 88 Hz ON 2
37 166 Hz 166 Hz ON 3	37 96 Hz 96 Hz ON 2	37 104 Hz 104 Hz ON 4	37 96 Hz 96 Hz ON 2
38 176 Hz 176 Hz ON 3	38 52 Hz 52 Hz ON 3	38 116 Hz 116 Hz ON 4	38 52 Hz 52 Hz ON 3
39 188 Hz 188 Hz ON 3 40 202 Hz 202 Hz ON 3	39 62 Hz 62 Hz ON 3	39 124 Hz 124 Hz ON 4 40 144 Hz 144 Hz ON 4	39 62 Hz 62 Hz ON 3 40 74 Hz 74 Hz ON 3
40 202 Hz 202 Hz ON 3 41 210 Hz 210 Hz ON 3	40 74 Hz 74 Hz ON 3 41 92 Hz 92 Hz ON 3	40 144 Hz 144 Hz ON 4 41 158 Hz 158 Hz ON 4	40 74 Hz 74 Hz ON 3 41 92 Hz 92 Hz ON 3
42 210 Hz 218 Hz ON 3	42 104 Hz 104 Hz ON 3	42 166 Hz 166 Hz ON 4	42 104 Hz 104 Hz ON 3
43 210 Hz 232 Hz ON 3	43 116 Hz 116 Hz ON 3	43 176 Hz 176 Hz ON 4	43 52 Hz 52 Hz ON 4
44 210 Hz 248 Hz ON 3	44 124 Hz 124 Hz ON 3	44 188 Hz 188 Hz ON 4	II 44 62 Hz 62 Hz ON 4
45 210 Hz 266 Hz ON 3	45 144 Hz 144 Hz ON 3	45 202 Hz 202 Hz ON 4	45 74 Hz 74 Hz ON 4 46 96 Hz 96 Hz ON 4
	46 158 Hz 158 Hz ON 3 47 166 Hz 166 Hz ON 3	▼ 46 210 Hz 210 Hz ON 4	46 96 Hz 96 Hz ON 4 47 104 Hz 104 Hz ON 4
	48 176 Hz 176 Hz ON 3		48 116 Hz 116 Hz ON 4
	49 188 Hz 188 Hz ON 3		49 124 Hz 124 Hz ON 4
	50 202 Hz 202 Hz ON 3		50 144 Hz 144 Hz ON 4
	51 210 Hz 210 Hz ON 3 52 210 Hz 218 Hz ON 3		51 158 Hz 158 Hz ON 4 52 166 Hz 166 Hz ON 4
	52 210 Hz 216 Hz ON 3		52 166 Hz 166 Hz ON 4 53 176 Hz 176 Hz ON 4
	54 210 Hz 248 Hz ON 3		54 188 Hz 188 Hz ON 4
	55 210 Hz 266 Hz ON 3		55 202 Hz 202 Hz ON 4
			56 210 Hz 210 Hz ON 4

Notes:

1. INV: Inverter compressor

STD: Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Basic Control Si34-601A

represents the range in which "Hz" is not stepped up.

RXYQ 34PY1 (16+18HP)

RXYQ36PY1 (18+18HP)

(To in	ncrease Step N	o) ,			To decrea	ise Sten N	lo)		(To increas	` se Sten No)		(To decrea	se Sten N	Jo)
1	aster Slave	J	A		Master	Slave		-1		Master	Slave	<i>,</i>	A		Master	Slave	
SIEF L	ınit unit	STD	Ī	STEP No.	unit	unit	STD	-	STEP No.	unit	unit	STD	Ī	STEP No.	unit	unit	STD
	NV INV 2 Hz 52 Hz	OFF		1	INV 52 Hz	INV OFF	OFF		1	INV 52 Hz	INV 52 Hz	OFF	1	1	INV 52 Hz	INV OFF	OFF
2 56	6 Hz 56 Hz	OFF		2	56 Hz	OFF	OFF		2	56 Hz	56 Hz	OFF	1	2	56 Hz	OFF	OFF
3 62	2 Hz 62 Hz	OFF		3	62 Hz	OFF	OFF		3	62 Hz	62 Hz	OFF	1	3	62 Hz	OFF	OFF
	66 Hz	OFF		4	68 Hz	OFF	OFF		4	66 Hz	66 Hz	OFF	1	4	68 Hz	OFF	OFF
	Hz 70 Hz Hz 74 Hz	OFF OFF		<u>5</u>	74 Hz 80 Hz	OFF OFF	OFF OFF		<u>5</u>	70 Hz 74 Hz	70 Hz 74 Hz	OFF OFF	1	<u>5</u>	74 Hz 80 Hz	OFF OFF	OFF OFF
	Hz 80 Hz	OFF		7	88 Hz	OFF	OFF		7	80 Hz	80 Hz	OFF	1	7	88 Hz	OFF	OFF
8 88	Hz 88 Hz	OFF		8	96 Hz	OFF	OFF		8	88 Hz	88 Hz	OFF	1	8	96 Hz	OFF	OFF
9 96	6 Hz 96 Hz 4 Hz 104 Hz	OFF OFF		9 10	104 Hz	OFF	OFF OFF		9 10	96 Hz 104 Hz	96 Hz 104 Hz	OFF OFF	1	9 10	104 Hz 52 Hz	OFF 52 Hz	OFF OFF
	4 Hz 104 Hz 0 Hz 110 Hz	OFF		11	52 Hz 56 Hz	52 Hz 56 Hz	OFF		11	110 Hz	110 Hz	OFF	1	11	56 Hz	56 Hz	OFF
	6 Hz 116 Hz	OFF		12	62 Hz	62 Hz	OFF		12	116 Hz	116 Hz	OFF	1	12	62 Hz	62 Hz	OFF
	4 Hz 124 Hz	OFF		13	66 Hz	66 Hz	OFF		13	124 Hz	124 Hz	OFF	1	13	66 Hz	66 Hz 70 Hz	OFF
	2 Hz 132 Hz 4 Hz 144 Hz	OFF OFF		14 15	70 Hz 74 Hz	70 Hz 74 Hz	OFF OFF		14 15	132 Hz 144 Hz	132 Hz 144 Hz	OFF OFF	1	14 15	70 Hz 74 Hz	70 Hz 74 Hz	OFF
	8 Hz 158 Hz	OFF		16	80 Hz	80 Hz	OFF		16	158 Hz	158 Hz	OFF	1	16	80 Hz	80 Hz	OFF OFF
17 16	6 Hz 166 Hz	OFF		17	88 Hz	88 Hz	OFF		17	166 Hz	166 Hz	OFF	1	17	88 Hz	88 Hz	OFF
	6 Hz 176 Hz	OFF		18	92 Hz	92 Hz	OFF		18	176 Hz	176 Hz	OFF	1	18	92 Hz	92 Hz	OFF
	Hz 80 Hz Hz 88 Hz	ON 1 ON 1		19 20	96 Hz 104 Hz	96 Hz 104 Hz	OFF OFF		19 20	80 Hz 88 Hz	80 Hz 88 Hz	ON 1 ON 1	1	19 20	96 Hz 104 Hz	96 Hz 104 Hz	OFF OFF
21 96	6 Hz 96 Hz	ON 1		21 22	110 Hz	110 Hz	OFF		21	96 Hz	96 Hz	ON 1	1	21	110 Hz	110 Hz	OFF
22 10	4 Hz 104 Hz	ON 1			116 Hz	116 Hz	OFF		22	104 Hz	104 Hz	ON 1	1	21 22	116 Hz	116 Hz	OFF
	6 Hz 116 Hz 4 Hz 124 Hz	ON 1 ON 1		23	124 Hz 132 Hz	124 Hz	OFF OFF		23 24	116 Hz 124 Hz	116 Hz	ON 1 ON 1	1	23	124 Hz 132 Hz	124 Hz	OFF OFF
	2 Hz 132 Hz	ON 1		24 25	52 Hz	132 Hz 52 Hz	ON 1		25	132 Hz	124 Hz 132 Hz	ON 1	1	24 25	52 Hz	132 Hz 52 Hz	ON 1
	8 Hz 88 Hz	ON 2		26	62 Hz	62 Hz	ON 1		26	88 Hz	88 Hz	ON 2	1	26	62 Hz	62 Hz	ON 1
27 96	6 Hz 96 Hz	ON 2		27	68 Hz	68 Hz	ON 1		27	96 Hz	96 Hz	ON 2	1	27	68 Hz	68 Hz	ON 1
	4 Hz 104 Hz 4 Hz 124 Hz	ON 2 ON 2		28 29	74 Hz 80 Hz	74 Hz 80 Hz	ON 1 ON 1		28 29	104 Hz 124 Hz	104 Hz 124 Hz	ON 2 ON 2	1	28 29	74 Hz 80 Hz	74 Hz 80 Hz	ON 1 ON 1
	4 Hz 144 Hz	ON 2		30	88 Hz	88 Hz	ON 1		30	144 Hz	144 Hz	ON 2	1	30	88 Hz	88 Hz	ON 1
31 92	2 Hz 96 Hz	ON 3		31	96 Hz	96 Hz	ON 1		31	92 Hz	96 Hz	ON 3	1	31	96 Hz	96 Hz	ON 1
	4 Hz 104 Hz	ON 3		32	104 Hz	104 Hz	ON 1		32	104 Hz	104 Hz	ON 3	1	32	104 Hz	104 Hz	ON 1
	6 Hz 116 Hz 4 Hz 124 Hz	ON 3 ON 3		33 34	52 Hz 62 Hz	52 Hz 62 Hz	ON 2 ON 2		33 34	116 Hz 124 Hz	116 Hz 124 Hz	ON 3 ON 3	1	33 34	52 Hz 62 Hz	52 Hz 62 Hz	ON 2 ON 2
	4 Hz 144 Hz	ON 3		35	74 Hz	74 Hz	ON 2		35	144 Hz	144 Hz	ON 3	1	35	74 Hz	74 Hz	ON 2
36 96	Hz 96 Hz	ON 4		36	88 Hz	88 Hz	ON 2		36	96 Hz	96 Hz	ON 3 ON 4 ON 4 ON 4	1	36	88 Hz	88 Hz	ON 2
	4 Hz 104 Hz 6 Hz 116 Hz	ON 4 ON 4		37 38	96 Hz 52 Hz	96 Hz 52 Hz	ON 2 ON 3		37 38	104 Hz 116 Hz	104 Hz 116 Hz	ON 4	1	37 38	96 Hz 52 Hz	96 Hz 52 Hz	ON 2 ON 3
	4 Hz 124 Hz	ON 4		39	62 Hz	62 Hz	ON 3		39	124 Hz	124 Hz	ON 4	1	39	62 Hz	62 Hz	ON 3
40 14	4 Hz 144 Hz	ON 4		40	74 Hz	74 Hz	ON 3		40	144 Hz	144 Hz	ON 4	1	40	74 Hz	74 Hz	ON 3
	8 Hz 158 Hz	ON 4		41	92 Hz	92 Hz	ON 3		41	158 Hz	158 Hz	ON 4	1	41	92 Hz	92 Hz	ON 3
	6 Hz 166 Hz 6 Hz 176 Hz	ON 4 ON 4		42 43	104 Hz 52 Hz	104 Hz 52 Hz	ON 3 ON 4		42 43	166 Hz 176 Hz	166 Hz 176 Hz	ON 4 ON 4	1	42 43	104 Hz 52 Hz	104 Hz 52 Hz	ON 3 ON 4
	8 Hz 188 Hz	ON 4		44	62 Hz	62 Hz	ON 4		44	188 Hz	188 Hz	ON 4	1	44	62 Hz	62 Hz	ON 4
	2 Hz 202 Hz	ON 4		45	74 Hz	74 Hz	ON 4		45	202 Hz	202 Hz	ON 4	1	45	74 Hz	74 Hz	ON 4
	0 Hz 210 Hz 0 Hz 218 Hz	ON 4 ON 4		46 47	96 Hz 104 Hz	96 Hz 104 Hz	ON 4 ON 4		46 47	210 Hz 218 Hz	210 Hz	ON 4 ON 4	1	46 47	96 Hz 104 Hz	96 Hz 104 Hz	ON 4 ON 4
	0 Hz 232 Hz	ON 4		48	116 Hz	116 Hz	ON 4		48	232 Hz	232 Hz	ON 4	1	48	116 Hz	116 Hz	ON 4
49 21	0 Hz 248 Hz	ON 4		49	124 Hz	124 Hz	ON 4	Ι	49	248 Hz	248 Hz	ON 4	1	49	124 Hz	124 Hz	ON 4
50 21	0 Hz 266 Hz	ON 4	П	50	144 Hz	144 Hz	ON 4	•	50	266 Hz	266 Hz	ON 4	1	50	144 Hz	144 Hz	ON 4
				51 52	158 Hz 166 Hz	158 Hz 166 Hz	ON 4 ON 4						-	51 52	158 Hz 166 Hz	158 Hz 166 Hz	ON 4 ON 4
				53	176 Hz	176 Hz	ON 4						-	53	176 Hz	176 Hz	ON 4
				54	188 Hz	188 Hz	ON 4						-	54	188 Hz	188 Hz	ON 4
				55 56	202 Hz 210 Hz	202 Hz 210 Hz	ON 4 ON 4							55 56	202 Hz 210 Hz	202 Hz 210 Hz	ON 4 ON 4
				57	210 Hz	218 Hz	ON 4							57	218 Hz	218 Hz	ON 4
				58	210 Hz	232 Hz	ON 4						-	58	232 Hz	232 Hz	ON 4
				59	210 Hz	248 Hz	ON 4							59	248 Hz	248 Hz	ON 4
			ı	60	210 Hz	266 Hz	ON 4						I	60	266 Hz	266 Hz	ON 4

Notes:

1. INV: Inverter compressor

STD: Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Si34-601A Basic Control

Three-unit multi system

represents the range in which "Hz" is not stepped up.

RXYQ38PY1 (8+12+18HP) F

RXYQ 40PY1 (8+16+16HP)

(To increase Step No.) (To decrease Step No.)

STEP Master Slave Slav	(To increase Step No.)	(To decrease Step No.)	(To increase Step No.)	(To decrease Step No.)
1 1 52 16 52 16 52 16 0F	STEF unit unit1 unit2 STD	T No unit unit1 unit2 STD	STEF unit unit1 unit2 STD	T No unit unit1 unit2 STD
3 62 Hz 62 Hz 62 Hz 0FF	1 52 Hz 52 Hz 52 Hz OFF	1 52 Hz OFF OFF OFF	1 52 Hz 52 Hz 52 Hz OFF	1 52 Hz OFF OFF OFF
6 70 Hz 70 Hz 70 Hz 70 Hz 0FF 6 88 0 Hz 0FF 0FF 0FF 0FF 6 FF 9 10 Hz 10 FF 10 FF 0FF 0FF 10 FF 0 F	3 62 Hz 62 Hz 62 Hz OFF	3 62 Hz OFF OFF OFF	3 62 Hz 62 Hz 62 Hz OFF	3 62 Hz OFF OFF OFF
8 80 Hz 80 Hz 80 Hz 60 Hz 0 FF 6 FF 0 FF 0 FF 10	5 68 Hz 68 Hz 68 Hz OFF	5 74 Hz OFF OFF OFF	4 66 Hz 66 Hz 66 Hz OFF 5 68 Hz 68 Hz 68 Hz OFF	5 74 Hz OFF OFF OFF
11 104 12 104 12 104 12 104 12 104 12 105 12 105 12 105 12 105 12 105 10	6 70 Hz 70 Hz 70 Hz OFF 7 74 Hz 74 Hz 74 Hz OFF	7 88 Hz OFF OFF OFF	6 70 Hz 70 Hz 70 Hz OFF 7 74 Hz 74 Hz 74 Hz OFF	7 88 Hz OFF OFF OFF
11 104 12 104 12 104 12 104 12 104 12 105 12 105 12 105 12 105 12 105 10	9 88 Hz 88 Hz 88 Hz OFF	8 96 Hz OFF OFF OFF 9 104 Hz OFF OFF OFF	8 80 Hz 80 Hz 80 Hz OFF 9 88 Hz 88 Hz 88 Hz OFF	9 104 Hz OFF OFF OFF
12 110	10 96 Hz 96 Hz 96 Hz OFF 11 104 Hz 104 Hz 104 Hz OFF	10 52 Hz 52 Hz OFF OFF OFF 11 156 Hz 56 Hz OFF OFF	I I 11 I104 HZI104 HZI104 HZI OFF I	11 56 Hz 56 Hz OFF OFF
14 124 121 124	12 110 Hz 110 Hz 110 Hz OFF	12 62 Hz 62 Hz OFF OFF 13 66 Hz 66 Hz OFF OFF	12 110 Hz 110 Hz 110 Hz OFF 13 116 Hz 116 Hz 116 Hz OFF	12 62 Hz 62 Hz OFF OFF 13 66 Hz 66 Hz OFF OFF
16 88 Hz 88 Hz 88 Hz CN	14 124 Hz 124 Hz 124 Hz OFF	14 70 Hz 70 Hz OFF OFF	14 124 Hz 124 Hz 124 Hz OFF	14 70 Hz 70 Hz OFF OFF
18 104 Hz; 104	16 88 Hz 88 Hz 88 Hz ON 1	16 52 Hz 52 Hz 52 Hz OFF	16 88 Hz 88 Hz 88 Hz ON 1	16 52 Hz 52 Hz 52 Hz OFF
20 124 Hz 124 Hz 124 Hz 10A Hz	18 104 Hz 104 Hz 104 Hz ON 1	18 62 Hz 62 Hz 62 Hz OFF	18 104 Hz 104 Hz 104 Hz ON 1	18 62 Hz 62 Hz 62 Hz OFF
22 88 Hz 88 Hz 188 Hz 1	20 124 Hz 124 Hz 124 Hz ON 1	20 68 Hz 68 Hz 68 Hz OFF	20 124 Hz 124 Hz 124 Hz ON 1	20 68 Hz 68 Hz 68 Hz OFF
24 104 Hz 104 Hz 104 Hz 0N 2 25 39 Hz 38 Hz 88 Hz 0FF 25 194 Hz 96 Hz 96 Hz 96 Hz 0FF 26 Hz 0FF 26 Hz 96 Hz 96 Hz 0FF 26 Hz 0FF 26 Hz 96 Hz 96 Hz 0FF 26 Hz 0FF 27 39 Hz 91 Hz 104 Hz 10	22 88 Hz 88 Hz 88 Hz ON 2	22 74 Hz 74 Hz 74 Hz OFF	22 88 Hz 88 Hz 88 Hz ON 2	22 74 Hz 74 Hz 74 Hz OFF
26 144 Hz 144 Hz 144 Hz 142 Hz 152 Hz 10N1 27 92 Hz 92 Hz 10N3 28 104 Hz 104 Hz 104 Hz 104 Hz 10N3 29 116 Hz 116 Hz 116 Hz 10N3 30 124 Hz 124 Hz 124 Hz 10N3 31 134 Hz 124 Hz 124 Hz 10N3 32 158 Hz 158 Hz 158 Hz 158 Hz 10N3 33 104 Hz 104 Hz 104 Hz 104 Hz 10H Hz 10N3 32 158 Hz 158 Hz 158 Hz 158 Hz 10N3 33 104 Hz 104 Hz 10Hz 10Hz 10Hz 10Hz 10N3 33 104 Hz 104 Hz 10Hz 10Hz 10Hz 10N3 33 104 Hz 10Hz 11Hz 12N3 34 176 Hz 176 Hz 176 Hz 176 Hz 176 Hz 10N3 35 188 Hz	24 104 Hz 104 Hz 104 Hz ON 2	24 88 Hz 88 Hz 88 Hz OFF	24 104 Hz 104 Hz 104 Hz ON 2	24 88 Hz 88 Hz 88 Hz OFF
29 116 Hz 116 Hz 106 Hz 10 Hz 10 N3 30 124 Hz 124 Hz 10 N3 130 124 Hz 124 Hz 10 N3 130 134 Hz 124 Hz 10 N3 130 13 Hz 80	26 144 Hz 144 Hz 144 Hz ON 2	25 96 Hz 96 Hz 96 Hz OFF 26 52 Hz 52 Hz 52 Hz ON 1	26 144 Hz 144 Hz 144 Hz ON 2	25 96 Hz 96 Hz 96 Hz OFF 26 52 Hz 52 Hz 52 Hz ON 1
32 158 Hz 1158 Hz 108 Hz 106 Hz 106 Hz 1166 Hz 1166 Hz 1166 Hz 106 Hz 108 Hz 10	28 104 Hz 104 Hz 104 Hz ON 3	27 62 Hz 62 Hz 62 Hz ON 1 28 68 Hz 68 Hz 68 Hz ON 1	LL 28 I104 HzI104 HzI104 HzI ON 3 I	28 68 Hz 68 Hz 68 Hz ON 1
32 158 Hz 1158 Hz 108 Hz 108 Hz 108 Hz 108 Hz 108 Hz 106 Hz 106 Hz 106 Hz 1166 Hz 1166 Hz 1166 Hz 106 Hz 108 Hz 10	29 116 Hz 116 Hz 116 Hz ON 3 30 124 Hz 124 Hz 124 Hz ON 3	29 74 Hz 74 Hz 74 Hz ON 1 30 80 Hz 80 Hz 80 Hz ON 1	29 116 Hz 116 Hz 116 Hz ON 3 30 124 Hz 124 Hz 124 Hz ON 3	29 74 Hz 74 Hz 74 Hz ON 1 30 80 Hz 80 Hz 80 Hz ON 1
35 188 Hz 188 Hz 0N 3 36 62 Hz 62 Hz 62 Hz 60 Hz 0N 2 36 202 Hz 202 Hz 200 Hz 201 H	I I 32 1158 Hzl158 Hzl158 Hzl ON 3	32 96 Hz 96 Hz 96 Hz ON 1		32 96 Hz 96 Hz 96 Hz ON 1
35 188 Hz 188 Hz 0N 3 36 62 Hz 62 Hz 62 Hz 60 Hz 0N 2 36 202 Hz 202 Hz 200 Hz 201 H	33 166 Hz 166 Hz 166 Hz ON 3 34 176 Hz 176 Hz 176 Hz ON 3	34 52 Hz 52 Hz 52 Hz ON 2	33 104 Hz 104 Hz 104 Hz ON 4 34 116 Hz 116 Hz 116 Hz ON 4	34 52 Hz 52 Hz 52 Hz ON 2
38 218 Hz 210 Hz 218 Hz ON 3 38 96 Hz 96 Hz ON 2 39 Hz CON 2 39 232 Hz 210 Hz 232 Hz ON 3 40 248 Hz 210 Hz 248 Hz ON 3 40 62 Hz 62 Hz 62 Hz 62 Hz ON 3 41 74 Hz 74 Hz 74 Hz ON 3 42 92 Hz 202 Hz ON 3 43 104 Hz 104 Hz 104 Hz 104 Hz ON 3 44 116 Hz 116 Hz 116 Hz ON 3 45 124 Hz 124 Hz 124 Hz ON 3 46 144 Hz 144 Hz 144 Hz 144 Hz ON 3 47 158 Hz 158 Hz 158 Hz 0N 3 48 166 Hz 166 Hz ON 3 49 176 Hz 176 Hz 176 Hz 176 Hz 176 Hz 170 Hz ON 3 45 124 Hz 124 Hz ON 3 46 144 Hz 144 Hz 144 Hz 0N 3 47 158 Hz 158 Hz 158 Hz 0N 3 49 176 Hz 176 Hz 0N 3 40 126 Hz 0N 3 40 12	35 188 Hz 188 Hz 188 Hz ON 3	35 62 Hz 62 Hz 62 Hz ON 2	35 124 Hz 124 Hz 124 Hz ON 4	35 62 Hz 62 Hz 62 Hz ON 2
39 \$23 \ Hz \$210 \ Hz \$232 \ Hz \$0 \ N 3 \ 40 \$248 \ Hz \$210 \ Hz \$248 \ Hz \$0 \ N 3 \ 40 \$248 \ Hz \$210 \ Hz \$266 \ Hz \$0 \ N 3 \ 40 \$248 \ Hz \$210 \ Hz \$266 \ Hz \$0 \ N 3 \ 41 \$266 \ Hz \$210 \ Hz \$266 \ Hz \$0 \ N 3 \ 42 \$22 \ Hz \$24 \ Hz \$0 \ N 3 \ 43 \$104 \ Hz \$104	37 210 Hz 210 Hz 210 Hz ON 3	37 88 Hz 88 Hz 0N 2 38 96 Hz 96 Hz 96 Hz 0N 2	37 158 Hz 158 Hz 158 Hz ON 4 38 166 Hz 166 Hz 166 Hz ON 4	37 88 Hz 88 Hz 88 Hz ON 2
41 74 Hz 74 Hz 74 Hz ON 3 42 92 Hz 92 Hz ON 3 42 92 Hz 92 Hz ON 3 43 104 Hz 104 Hz ON 3 44 116 Hz 116 Hz 116 Hz ON 3 45 124 Hz 124 Hz 124 Hz ON 3 46 144 Hz 144 Hz 144 Hz ON 3 47 158 Hz 158 Hz 158 Hz ON 3 48 166 Hz 166 Hz 166 Hz 166 Hz ON 3 49 176 Hz 176 Hz 176 Hz ON 3 49 176 Hz 176 Hz 176 Hz ON 3 50 188 Hz 188 Hz 0N 3 51 202 Hz 202 Hz 202 Hz ON 3 52 210 Hz 210 Hz 210 Hz 210 Hz ON 4 52 210 Hz 210 Hz 16 Hz 164 Hz ON 4 46 266 Hz 210 Hz 210 Hz ON 4 47 96 Hz 96 Hz 96 Hz ON 4 48 104 Hz 104 Hz 104 Hz ON 4 49 116 Hz 116 Hz ON 4 50 124 Hz 124 Hz ON 4 50 124 Hz	39 232 Hz 210 Hz 232 Hz ON 3	39 52 Hz 52 Hz 52 Hz ON 3 40 62 Hz 62 Hz 62 Hz ON 3	39 176 Hz 176 Hz 176 Hz ON 4	39 52 Hz 52 Hz 52 Hz ON 3
45 124 Hz 124 Hz 20 Hz	41 266 Hz 210 Hz 266 Hz ON 3	41 74 Hz 74 Hz 74 Hz ON 3	1 41 1202 Hz1202 Hz1202 Hz1 ON 4	41 74 Hz 74 Hz 74 Hz ON 3
45 124 Hz 124 Hz 20 Hz		43 104 Hz 104 Hz 104 Hz ON 3	43 218 Hz 210 Hz 210 Hz ON 4	43 104 Hz 104 Hz 104 Hz ON 3
47 158 Hz 158 Hz 158 Hz 0N 3 48 166 Hz 166 Hz 166 Hz 166 Hz 176 Hz 0N 3 49 176 Hz 176 Hz 176 Hz 0N 3 49 116 Hz 176 Hz 176 Hz 0N 3 49 116 Hz 114 Hz 0N 4 50 124 Hz 124 Hz 0N 4 50 124 Hz 124 Hz 0N 4 50 124 Hz 124 Hz 0N 4 50 126 Hz 158 Hz 158 Hz 158 Hz 0N 4 50 126 Hz 166 Hz 167 Hz 176 Hz 0N 4 50 126 Hz 120 Hz 210 Hz 210 Hz 210 Hz 200		45 124 Hz 124 Hz 124 Hz ON 3	1 45 1248 HZ1210 HZ1210 HZ1 ON 4	45 62 Hz 62 Hz 62 Hz ON 4
49 176 Hz 176 Hz 176 Hz 0N 3 50 188 Hz 188 Hz 188 Hz 188 Hz 0N 3 51 202 Hz 202 Hz 202 Hz 0N 3 52 210 Hz 210 Hz 210 Hz 0N 3 53 218 Hz 210 Hz 218 Hz 0N 3 54 232 Hz 210 Hz 232 Hz 0N 3 55 248 Hz 210 Hz 248 Hz 0N 3 56 266 Hz 210 Hz 266 Hz 0N 3 56 266 Hz 210 Hz 266 Hz 0N 3 57 210 Hz 210 Hz 0N 4 58 218 Hz 210 Hz 210 Hz 0N 3 59 232 Hz 210 Hz 232 Hz 0N 3 50 248 Hz 210 Hz 248 Hz 0N 3 50 248 Hz 210 Hz 248 Hz 0N 3 51 144 Hz		46 144 HZ 144 HZ 144 HZ 0N 3 47 158 HZ 158 HZ 158 HZ 0N 3	1 40 200 HZ Z U HZ Z U HZ UN 4	40 74 HZ 74 HZ 74 HZ ON 4 47 96 HZ 96 HZ 96 HZ ON 4
51		49 176 Hz 176 Hz 176 Hz ON 3		49 116 Hz 116 Hz 116 Hz ON 4
53 218 Hz 210 Hz 218 Hz ON 3 54 232 Hz 210 Hz 232 Hz ON 3 55 248 Hz 210 Hz 248 Hz ON 3 56 266 Hz 210 Hz 266 Hz ON 3 56 266 Hz 210 Hz 266 Hz ON 3 57 210 Hz 210 Hz 210 Hz ON 4 58 218 Hz 210 Hz 210 Hz ON 4 59 232 Hz 210 Hz 210 Hz ON 4 60 248 Hz 210 Hz 210 Hz ON 4		51 202 Hz 202 Hz 202 Hz ON 3		51 144 Hz 144 Hz 144 Hz ON 4
55 248 Hz 210 Hz 248 Hz ON 3 56		53 218 Hz 210 Hz 218 Hz ON 3		53 166 Hz 166 Hz 166 Hz ON 4
57 210 Hz 210 Hz 210 Hz ON 4 58 218 Hz 210 Hz 210 Hz ON 4 59 232 Hz 210 Hz 210 Hz ON 4 60 248 Hz 210 Hz ON 4		55 248 Hz 210 Hz 248 Hz ON 3		
58 218 Hz 210 Hz 210 Hz ON 4 59 232 Hz 210 Hz 210 Hz ON 4 60 248 Hz 210 Hz 210 Hz ON 4		56 266 Hz 210 Hz 266 Hz ON 3		57 210 Hz 210 Hz 210 Hz ON 4
60 248 Hz 210 Hz 210 Hz ON 4				58 218 Hz 210 Hz 210 Hz ON 4 59 232 Hz 210 Hz 210 Hz ON 4
				60 248 Hz 210 Hz 210 Hz ON 4

Notes:

1. INV: Inverter compressor STD: Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Basic Control Si34-601A

(To decrease Step No.)

INN

INV

STEP

INV

represents the range in which "Hz" is not stepped up.

RXYQ 42PY1 (8+16+18HP) (To increase Step No.)

unit1

INV

INV

Slave unit2

INV

STD

RXYQ44PY1 (8+18+18HP) (To increase Step No.) (To decrease Step No.) Slave unit1 Vlaste Slave unit2 STD STD INV INN INV INV

Notes:

1. INV: Inverter compressor

STD: Standard compressor

104 Hz 104 Hz 104 Hz 0N 4 116 Hz 116 Hz 116 Hz 0N 4 124 Hz 124 Hz 124 Hz 0N 4 144 Hz 144 Hz 124 Hz 0N 4 158 Hz 158 Hz 158 Hz 0N 4 166 Hz 166 Hz 166 Hz 0N 4 176 Hz 176 Hz 176 Hz 0N 4 188 Hz 188 Hz 188 Hz 0N 4 188 Hz 188 Hz 188 Hz 0N 4 202 Hz 202 Hz 202 Hz 0N 4 210 Hz 210 Hz 210 Hz 0N 4 218 Hz 210 Hz 218 Hz 0N 4 232 Hz 210 Hz 218 Hz 0N 4 248 Hz 210 Hz 232 Hz 0N 4 248 Hz 210 Hz 248 Hz 0N 4 266 Hz 210 Hz 248 Hz 0N 4

266 Hz 210 Hz 266 Hz ON 4

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Si34-601A **Basic Control**

> represents the range in which "Hz" is not stepped up. RXYQ50PY1, 52PY1 (14/16+18+18HP)

RXYQ46PY1, 48PY1 (10/12+18+18HP)

(To increase Step No.)	(To decrease Step No.)	(To increase Step No.)	(To decrease Step No.)
CTTD Master Slave Slave	Master Slave Slave	STEP Master Slave Slave CTD	STEP Master Slave Slave
STEF unit unit1 unit2 STD	T No unit unit1 unit2 STD	No unit unit1 unit2 STD	STEF unit unit1 unit2 STD
1 S2 Hz S2 Hz S2 Hz OFF	1 52 Hz OFF OFF OFF	1 52 Hz 52 Hz 52 Hz OFF	1 52 Hz OFF OFF OFF
2 56 Hz 56 Hz 56 Hz OFF	2 56 Hz OFF OFF OFF	2 56 Hz 56 Hz 56 Hz OFF	2 56 Hz OFF OFF OFF
3 62 Hz 62 Hz 62 Hz OFF 4 66 Hz 66 Hz 66 Hz OFF	3 62 Hz OFF OFF OFF OFF 4 68 Hz OFF OFF OFF	3 62 Hz 62 Hz 62 Hz OFF 4 66 Hz 66 Hz 66 Hz OFF	3 62 Hz OFF OFF OFF 4 68 Hz OFF OFF OFF
5 68 Hz 68 Hz 68 Hz OFF	5 74 Hz OFF OFF OFF	4 66 Hz 66 Hz 66 Hz OFF 5 68 Hz 68 Hz 68 Hz OFF	5 74 Hz OFF OFF OFF
6 70 Hz 70 Hz 70 Hz OFF	6 80 Hz OFF OFF OFF	6 70 Hz 70 Hz 70 Hz OFF	6 80 Hz OFF OFF OFF
7 74 Hz 74 Hz 74 Hz OFF 8 80 Hz 80 Hz 80 Hz OFF	7 88 Hz OFF OFF OFF 8 96 Hz OFF OFF	7 74 Hz 74 Hz 74 Hz OFF 8 80 Hz 80 Hz 80 Hz OFF	7 88 Hz OFF OFF OFF 8 96 Hz OFF OFF OFF
9 88 Hz 88 Hz 88 Hz OFF	9 104 Hz OFF OFF OFF	9 88 Hz 88 Hz 88 Hz OFF	9 104 Hz OFF OFF OFF
10 96 Hz 96 Hz 96 Hz OFF 11 104 Hz 104 Hz 104 Hz OFF	10 52 Hz 52 Hz OFF OFF 11 56 Hz 56 Hz OFF OFF	10 96 Hz 96 Hz 96 Hz OFF 11 104 Hz 104 Hz 104 Hz OFF	10 52 Hz 52 Hz OFF OFF 11 56 Hz 56 Hz OFF OFF
11 104 Hz 104 Hz 104 Hz OFF 12 110 Hz 110 Hz 110 Hz OFF	11 56 Hz 56 Hz OFF OFF 12 62 Hz 62 Hz OFF OFF	11 104 Hz 104 Hz 104 Hz OFF 12 110 Hz 110 Hz 110 Hz OFF	11 56 Hz 56 Hz OFF OFF 12 62 Hz 62 Hz OFF OFF
13 116 Hz 116 Hz 116 Hz OFF	13 66 Hz 66 Hz OFF OFF	13 116 Hz 116 Hz 116 Hz OFF	13 66 Hz 66 Hz OFF OFF
14 124 Hz 124 Hz 124 Hz OFF 15 80 Hz 80 Hz 80 Hz ON 1	14 70 Hz 70 Hz OFF OFF 1 15 74 Hz 74 Hz OFF OFF	14 124 Hz 124 Hz 124 Hz OFF 15 80 Hz 80 Hz 80 Hz ON 1	14 70 Hz 70 Hz OFF OFF 15 74 Hz 74 Hz OFF OFF
16 88 Hz 88 Hz 88 Hz ON 1	16 52 Hz 52 Hz 52 Hz OFF	16 88 Hz 88 Hz 88 Hz ON 1	16 52 Hz 52 Hz 52 Hz OFF
17 96 Hz 96 Hz 96 Hz ON 1 18 104 Hz 104 Hz 104 Hz ON 1	17 56 Hz 56 Hz 56 Hz OFF 18 62 Hz 62 Hz 62 Hz OFF	17 96 Hz 96 Hz 96 Hz ON 1 18 104 Hz 104 Hz 104 Hz ON 1	17 56 Hz 56 Hz 56 Hz OFF 18 62 Hz 62 Hz 62 Hz OFF
18 104 Hz 104 Hz 104 Hz ON 1 19 116 Hz 116 Hz 116 Hz ON 1	18 62 Hz 62 Hz 62 Hz OFF 19 66 Hz 66 Hz 66 Hz OFF	19 116 Hz 116 Hz 116 Hz ON 1	<u>18 62 Hz 62 Hz 62 Hz OFF </u> 19 66 Hz 66 Hz 66 Hz OFF
20 124 Hz 124 Hz 124 Hz ON 1	20 68 Hz 68 Hz 68 Hz OFF	20 124 Hz 124 Hz 124 Hz ON 1	20 68 Hz 68 Hz 68 Hz OFF
21 132 Hz 132 Hz 132 Hz ON 1 22 88 Hz 88 Hz 88 Hz ON 2	21 70 Hz 70 Hz 70 Hz OFF 22 74 Hz 74 Hz 74 Hz OFF	21 132 Hz 132 Hz 132 Hz ON 1	21 70 Hz 70 Hz 70 Hz OFF 22 74 Hz 74 Hz 74 Hz OFF
23 96 Hz 96 Hz 96 Hz ON 2	23 80 Hz 80 Hz 80 Hz OFF	23 96 Hz 96 Hz 96 Hz ON 2	23 80 Hz 80 Hz 80 Hz OFF
24 104 Hz 104 Hz 104 Hz ON 2 25 124 Hz 124 Hz 124 Hz ON 2	24 88 Hz 88 Hz 88 Hz OFF 25 96 Hz 96 Hz 96 Hz OFF	24 104 Hz 104 Hz 104 Hz ON 2 25 124 Hz 124 Hz 124 Hz ON 2	24 88 Hz 88 Hz 88 Hz OFF 25 96 Hz 96 Hz 96 Hz OFF
26 144 Hz 144 Hz 144 Hz ON 2	26 52 Hz 52 Hz 52 Hz ON 1	26 144 Hz 144 Hz 144 Hz ON 2	26 52 Hz 52 Hz 52 Hz ON 1
27 92 Hz 92 Hz 92 Hz ON 3	27 62 Hz 62 Hz 62 Hz ON 1	27 92 Hz 92 Hz 92 Hz ON 3	27 62 Hz 62 Hz 62 Hz ON 1
28 104 Hz 104 Hz 104 Hz ON 3 29 116 Hz 116 Hz 116 Hz ON 3	28 68 Hz 68 Hz 68 Hz ON 1 29 74 Hz 74 Hz 74 Hz ON 1	28 104 Hz 104 Hz 104 Hz ON 3 29 116 Hz 116 Hz 116 Hz ON 3	28 68 Hz 68 Hz 68 Hz ON 1 29 74 Hz 74 Hz 74 Hz ON 1
30 124 Hz 124 Hz 124 Hz ON 3	30 80 Hz 80 Hz 80 Hz ON 1	30 124 Hz 124 Hz 124 Hz ON 3	30 80 Hz 80 Hz 80 Hz ON 1
31 144 Hz 144 Hz 144 Hz ON 3 32 96 Hz 96 Hz 96 Hz ON 4	31 88 Hz 88 Hz 88 Hz ON 1 32 96 Hz 96 Hz 96 Hz ON 1	31 144 Hz 144 Hz 144 Hz ON 3 32 96 Hz 96 Hz 96 Hz ON 4	31 88 Hz 88 Hz 88 Hz ON 1 32 96 Hz 96 Hz 96 Hz ON 1
33 104 Hz 104 Hz 104 Hz ON 4	33 104 Hz 104 Hz 104 Hz ON 1	33 104 Hz 104 Hz 104 Hz ON 4	33 104 Hz 104 Hz 104 Hz ON 1
34 116 Hz 116 Hz 116 Hz ON 4	34 52 Hz 52 Hz 52 Hz ON 2	34 116 Hz 116 Hz 116 Hz ON 4	34 52 Hz 52 Hz 52 Hz ON 2
35 124 Hz 124 Hz 124 Hz ON 4 36 144 Hz 144 Hz 144 Hz ON 4	35 62 Hz 62 Hz 62 Hz ON 2 36 74 Hz 74 Hz 74 Hz ON 2	35 124 Hz 124 Hz 124 Hz ON 4 36 144 Hz 144 Hz 144 Hz ON 4	35 62 Hz 62 Hz 62 Hz ON 2 36 74 Hz 74 Hz 74 Hz ON 2
52 96 Hz 96 Hz 96 Hz ON 5	37 88 Hz 88 Hz 88 Hz ON 2	37 96 Hz 96 Hz 96 Hz ON 5	37 88 Hz 88 Hz 88 Hz ON 2
53 104 Hz 104 Hz 104 Hz ON 5 54 116 Hz 116 Hz 116 Hz ON 5	38 96 Hz 96 Hz 96 Hz ON 2 39 52 Hz 52 Hz 52 Hz ON 3	38 104 Hz 104 Hz 104 Hz ON 5 39 116 Hz 116 Hz 116 Hz ON 5	38 96 Hz 96 Hz 96 Hz ON 2 39 52 Hz 52 Hz 52 Hz ON 3
55 124 Hz 124 Hz 124 Hz ON 5	40 62 Hz 62 Hz 62 Hz ON 3	40 124 Hz 124 Hz 124 Hz ON 5	40 62 Hz 62 Hz 62 Hz ON 3
56 144 Hz 144 Hz 144 Hz ON 5	41 74 Hz 74 Hz 74 Hz ON 3	41 144 Hz 144 Hz 144 Hz ON 5	41 74 Hz 74 Hz 74 Hz ON 3
57 158 Hz 158 Hz 158 Hz ON 5 58 166 Hz 166 Hz 166 Hz ON 5	42 92 Hz 92 Hz 92 Hz ON 3 43 104 Hz 104 Hz 104 Hz ON 3	42 96 Hz 96 Hz 96 Hz ON 6 43 104 Hz 104 Hz 104 Hz ON 6	42 92 Hz 92 Hz 92 Hz 0N 3 43 104 Hz 104 Hz 104 Hz 0N 3
59 176 Hz 176 Hz 176 Hz ON 5	44 52 Hz 52 Hz 52 Hz ON 4	44 116 Hz 116 Hz 116 Hz ON 6	44 52 Hz 52 Hz 52 Hz ON 4
60 188 Hz 188 Hz 188 Hz ON 5 61 202 Hz 202 Hz 202 Hz ON 5	45 62 Hz 62 Hz 62 Hz ON 4 46 74 Hz 74 Hz 74 Hz ON 4	45 124 Hz 124 Hz 124 Hz ON 6 46 144 Hz 144 Hz 144 Hz ON 6	45 62 Hz 62 Hz 62 Hz ON 4 46 74 Hz 74 Hz 74 Hz ON 4
62 210 Hz 210 Hz 210 Hz ON 5	47 96 Hz 96 Hz 96 Hz ON 4	47 158 Hz 158 Hz 158 Hz ON 6	47 96 Hz 96 Hz 96 Hz ON 4
63 210 Hz 218 Hz 218 Hz ON 5	48 104 Hz 104 Hz 104 Hz ON 4	48 166 Hz 166 Hz 166 Hz ON 6	48 104 Hz 104 Hz 104 Hz ON 4
64 210 Hz 232 Hz 232 Hz ON 5 65 210 Hz 248 Hz 248 Hz ON 5	49 52 Hz 52 Hz 52 Hz ON 5 50 68 Hz 68 Hz 68 Hz ON 5	49 176 Hz 176 Hz 176 Hz ON 6 50 188 Hz 188 Hz 188 Hz ON 6	49 52 Hz 52 Hz 52 Hz ON 5 50 68 Hz 68 Hz 68 Hz ON 5
66 210 Hz 266 Hz 266 Hz ON 5	51 80 Hz 80 Hz 80 Hz ON 5	51 202 Hz 202 Hz 202 Hz ON 6	51 80 Hz 80 Hz 80 Hz ON 5
	52 96 Hz 96 Hz 96 Hz ON 5 53 104 Hz 104 Hz 104 Hz ON 5	52 210 Hz 210 Hz 210 Hz ON 6 53 210 Hz 218 Hz 218 Hz ON 6	52 96 Hz 96 Hz 96 Hz ON 5 53 104 Hz 104 Hz 104 Hz ON 5
	54 116 Hz 116 Hz 116 Hz ON 5	54 210 Hz 232 Hz 232 Hz ON 6	54 52 Hz 52 Hz 52 Hz ON 6
	55 124 Hz 124 Hz 124 Hz ON 5 V	55 210 Hz 248 Hz 248 Hz ON 6 56 210 Hz 266 Hz 266 Hz ON 6	55 68 Hz 68 Hz 68 Hz ON 6 56 80 Hz 80 Hz 80 Hz ON 6
	57 158 Hz 158 Hz 158 Hz ON 5	30 210112 200112 200112 0110	57 96 Hz 96 Hz 96 Hz ON 6
	58 166 Hz 166 Hz 166 Hz ON 5		58 104 Hz 104 Hz 104 Hz ON 6
	59 176 Hz 176 Hz 176 Hz ON 5 60 188 Hz 188 Hz 188 Hz ON 5		59 116 Hz 116 Hz 116 Hz ON 6 60 124 Hz 124 Hz 124 Hz ON 6
	61 202 Hz 202 Hz 202 Hz ON 5		61 144 Hz 144 Hz 144 Hz ON 6
	62 210 Hz 210 Hz 210 Hz ON 5 63 210 Hz 218 Hz 218 Hz ON 5		62 158 Hz 158 Hz 158 Hz ON 6 63 166 Hz 166 Hz 166 Hz ON 6
	64 210 Hz 232 Hz 232 Hz ON 5		64 176 Hz 176 Hz 176 Hz ON 6
	65 210 Hz 248 Hz 248 Hz ON 5 66 210 Hz 266 Hz 266 Hz ON 5		65 188 Hz 188 Hz 188 Hz ON 6 66 202 Hz 202 Hz 202 Hz ON 6
	66 210 Hz 266 Hz 266 Hz ON 5		66 202 Hz 202 Hz 202 Hz ON 6 67 210 Hz 210 Hz 210 Hz ON 6
			68 210 Hz 218 Hz 218 Hz ON 6
Motoc			69 210 Hz 232 Hz 232 Hz ON 6 70 210 Hz 248 Hz 248 Hz ON 6
Notes:			71 210 Hz 266 Hz 266 Hz ON 6
I INV Inverter compressor			·

Notes:

1. INV: Inverter compressor

STD: Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.
- 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those aforementioned.

Basic Control Si34-601A

RXYQ54PY1 (18+18+18HP)

11/(1)	(To inc	` _	ton No \		,		(To do	orogeo 9	Stop No	`
			tep No.)						Step No.)
STEP	Master	Slave unit1	Slave unit2	STD	4	STEP	Master	Slave unit1	Slave unit2	STD
No.	unit INV	INV	INV	310	- 1	No.	unit INV	INV	INV	310
1	52 Hz	52 Hz	52 Hz	OFF	- 1	1	52 Hz	ÖFF	ÖFF	OFF
2	56 Hz	56 Hz	56 Hz	OFF	- 1	2	56 Hz	OFF	OFF	OFF
3	62 Hz	62 Hz	62 Hz	OFF	- 1	3	62 Hz	OFF	OFF	OFF
4	66 Hz	66 Hz	66 Hz	OFF	- 1	4	68 Hz	OFF	OFF	OFF
5	68 Hz	68 Hz	68 Hz	OFF	- 1	5	74 Hz	OFF	OFF	OFF
6	70 Hz	70 Hz	70 Hz	OFF	- 1	6	80 Hz	OFF	OFF	OFF
8	74 Hz 80 Hz	74 Hz 80 Hz	74 Hz 80 Hz	OFF OFF	- 1	8	88 Hz 96 Hz	OFF OFF	OFF OFF	OFF OFF
9	88 Hz	88 Hz	88 Hz	OFF	- 1	9	104 Hz	OFF	OFF	OFF
10	96 Hz	96 Hz	96 Hz	OFF	- 1	10	52 Hz	52 Hz	OFF	OFF
11	104 Hz	104 Hz	104 Hz	OFF	- 1	11	56 Hz	56 Hz	OFF	OFF
12	110 Hz	110 Hz	110 Hz	OFF	- 1	12	62 Hz	62 Hz	OFF	OFF
13	116 Hz	116 Hz	116 Hz	OFF	-	13	66 Hz	66 Hz	OFF	OFF
14	124 Hz	124 Hz	124 Hz	OFF	- 1	14	70 Hz	70 Hz	OFF	OFF
15	80 Hz	80 Hz	80 Hz	ON 1	-	15	74 Hz	74 Hz	OFF	OFF
16	88 Hz	88 Hz	88 Hz	ON 1 ON 1	- 1	16	52 Hz	52 Hz	52 Hz	OFF OFF
17 18	96 Hz 104 Hz	96 Hz 104 Hz	96 Hz 104 Hz	ON 1	- 1	17 18	56 Hz 62 Hz	56 Hz 62 Hz	56 Hz 62 Hz	OFF
19	116 Hz	116 Hz	116 Hz	ON 1	-	19	66 Hz	66 Hz	66 Hz	OFF
20	124 Hz	124 Hz	124 Hz	ON 1	-	20	68 Hz	68 Hz	68 Hz	OFF
21	132 Hz	132 Hz	132 Hz	ON 1	- 1	21	70 Hz	70 Hz	70 Hz	OFF
22	88 Hz	88 Hz	88 Hz	ON 2	-	22	74 Hz	74 Hz	74 Hz	OFF
23	96 Hz	96 Hz	96 Hz	ON 2	- 1	23	80 Hz	80 Hz	80 Hz	OFF
24	104 Hz	104 Hz	104 Hz	ON 2	- 1	24	88 Hz	88 Hz	88 Hz	OFF
25 26	124 Hz 144 Hz	124 Hz 144 Hz	124 Hz 144 Hz	ON 2	- 1	25 26	96 Hz 52 Hz	96 Hz 52 Hz	96 Hz 52 Hz	OFF ON 1
27	92 Hz	92 Hz	92 Hz	ON 3	-	27	62 Hz	62 Hz	62 Hz	ON 1
28	104 Hz	104 Hz	104 Hz	ON 3	-	28	68 Hz	68 Hz	68 Hz	ON 1
29	116 Hz	116 Hz	116 Hz	ON 3	- 1	29	74 Hz	74 Hz	74 Hz	ON 1
30	124 Hz	124 Hz	124 Hz	ON 3	- 1	30	80 Hz	80 Hz	80 Hz	ON 1
31	144 Hz	144 Hz	144 Hz	ON 3	- 1	31	88 Hz	88 Hz	88 Hz	ON 1
32	96 Hz	96 Hz	96 Hz	ON 4	- 1	32	96 Hz	96 Hz	96 Hz	ON 1
<u>33</u> 34	104 Hz 116 Hz	104 Hz 116 Hz	104 Hz	ON 4	- 1	<u>33</u> 34	104 Hz	104 Hz	104 Hz	ON 1 ON 2
35	124 Hz	124 Hz	116 Hz 124 Hz	ON 4 ON 4	-	35	52 Hz 62 Hz	52 Hz 62 Hz	52 Hz 62 Hz	ON 2
36	144 Hz	144 Hz	144 Hz	ON 4	-	36	74 Hz	74 Hz	74 Hz	ON 2
37	96 Hz	96 Hz	96 Hz	ON 5	-	37	88 Hz	88 Hz	88 Hz	ON 2
38	104 Hz	104 Hz	104 Hz	ON 5	- 1	38	96 Hz	96 Hz	96 Hz	ON 2
39	116 Hz	116 Hz	116 Hz	ON 5	- 1	39	52 Hz	52 Hz	52 Hz	ON 3
40	124 Hz	124 Hz	124 Hz	ON 5	- 1	40	62 Hz	62 Hz	62 Hz	ON 3
41	144 Hz	144 Hz	144 Hz	ON 5	- 1	41	74 Hz	74 Hz	74 Hz	ON 3
42 43	96 Hz 104 Hz	96 Hz 104 Hz	96 Hz 104 Hz	ON 6	- 1	42	92 Hz 104 Hz	92 Hz 104 Hz	92 Hz 104 Hz	ON 3
44	116 Hz	116 Hz	116 Hz	ON 6	- 1	44	52 Hz	52 Hz	52 Hz	ON 4
45	124 Hz	124 Hz	124 Hz	ON 6	- 1	45	62 Hz	62 Hz	62 Hz	ON 4
46	144 Hz	144 Hz	144 Hz	ON 6	- 1	46	74 Hz	74 Hz	74 Hz	ON 4
47	158 Hz	158 Hz	158 Hz	ON 6	- 1	47	96 Hz	96 Hz	96 Hz	ON 4
48	166 Hz	166 Hz	166 Hz	ON 6	- 1	48	104 Hz	104 Hz	104 Hz	ON 4
49	176 Hz	176 Hz	176 Hz	ON 6	- 1	49	52 Hz	52 Hz	52 Hz	ON 5
<u>50</u> 51	188 Hz 202 Hz	188 Hz 202 Hz	188 Hz 202 Hz	ON 6 ON 6	- 1	<u>50</u> 51	68 Hz 80 Hz	68 Hz 80 Hz	68 Hz 80 Hz	ON 5 ON 5
52	210 Hz	210 Hz	210 Hz	ON 6	- 1	52	96 Hz	96 Hz	96 Hz	ON 5
53	218 Hz	218 Hz	218 Hz	ON 6	-	53	104 Hz	104 Hz	104 Hz	ON 5
54	232 Hz	232 Hz	232 Hz	ON 6	-	54	52 Hz	52 Hz	52 Hz	ON 6
55	248 Hz	248 Hz	248 Hz	ON 6	- 1	55	68 Hz	68 Hz	68 Hz	ON 6
56	266 Hz	266 Hz	266 Hz	ON 6	- 1	56	80 Hz	80 Hz	80 Hz	ON 6
					- 1	57	96 Hz	96 Hz	96 Hz	ON 6
					- 1	58	104 Hz	104 Hz	104 Hz	ON 6
					- 1	60			116 Hz 124 Hz	ON 6
					-	61			144 Hz	ON 6
					-	62			158 Hz	ON 6
					-	63	166 Hz	166 Hz	166 Hz	ON 6
					-	64	176 Hz	176 Hz	176 Hz	ON 6
					-	65			188 Hz	ON 6
					-	66	202 Hz	202 Hz	202 Hz	ON 6
					-	67 68			210 Hz 218 Hz	ON 6 ON 6
					-	69			232 Hz	ON 6
					-	70	248 Hz	248 Hz	248 Hz	ON 6
					-	71	266 Hz	266 Hz	266 Hz	ON 6

Notes:

1. INV: Inverter compressor STD : Standard compressor

Figures after ON represent the number of STD compressors in operation.

- 2. "Master unit", and "slave unit" in this section are the names for control, and they will be transferred according to the priority of rotation system.

 3. Depending on the operating conditions of compressors, the compressors may run in patterns other than those
- aforementioned.

Si34-601A **Basic Control**

Electronic Expansion Valve PI Control 2.3

Main Motorized Valve EV1 Control

Carries out the motorized valve (Y1E) PI control to maintain the evaporator outlet superheated degree (SH) at constant during heating operation to make maximum use of the outdoor unit heat exchanger (evaporator).

SH = Ts1 - Te SH: Evaporator outlet superheated degree (°C)

Ts1: Suction pipe temperature detected by thermistor R6T (R7T) (°C)

Te: Low pressure equivalent saturation

temperature (°C)

The optimum initial value of the evaporator outlet superheated degree is 5°C, but varies depending on the discharge pipe superheated degree of inverter compressor.

Subcooling Motorized Valve EV2 Control

Makes PI control of the motorized valve (Y2E) to keep the superheated degree of the outlet gas pipe on the evaporator side for the full use of the subcooling heat exchanger.

SH = Tsh -Te SH: Outlet superheated degree of evaporator (°C)

Tsh : Suction pipe temperature detected with the thermistor R5T (°C)

Te: Low pressure equivalent saturation temperature (°C)

Step Control of Outdoor Unit Fans

Used to control the revolutions of outdoor unit fans in the steps listed in table below, according to condition changes.


			Fa	n revolutions (rp	m)					
STEP No.	RXYQ5P	RXYQ8P	RXYQ10P	RXYQ12P (Europe)	(except	Q12P Europe) Q14P	RXYQ16P		RXYQ18P	
					FAN1	FAN2	FAN1	FAN2	FAN1	FAN2
0	0	0	0	0	0	0	0	0	0	0
1	285	350	350	350	230	0	230	0	395	0
2	315	370	370	370	380	0	380	0	460	0
3	360	400	400	400	290	260	290	260	570	0
4	450	450	460	460	375	345	375	345	385	355
5	570	540	560	560	570	540	570	540	550	520
6	710	670	680	680	720	690	720	690	800	770
7	Cooling: 951 Heating: 941	760	Cooling: 821 Heating: 800	870	1091	1061	1091	1061	1136	1106
8	Cooling: 951 Heating: 941	Cooling: 796 Heating: 780	Cooling: 821 Heating: 800	870	1136	1106	1136	1106	1166	1136

^{*} Figures listed above are all those controlled while in standard mode, which vary when the system is set to high static pressure or capacity precedence mode.

Basic Control Si34-601A

2.5 Outdoor Unit Fan Control in Cooling Operation

While in cooling operation, if the outdoor temperature is low, this mode provides high-pressure control using the outdoor unit fan to retain appropriate liquid pressure, thus ensuring refrigerant circulation rate to be supplied to indoor units.



Si34-601A Special Control

3. Special Control

3.1 Startup Control

This control is used to equalize the pressure in the front and back of the compressor prior to the startup of the compressor, thus reducing startup loads. Furthermore, the inverter is turned ON to charge the capacitor. In addition, to avoid stresses to the compressor due to oil return or else after the startup, the following control is made and the position of the four way valve is also determined. To position the four way valve, the master and slave units simultaneously start up.

3.1.1 Startup Control in Cooling Operation

√—Thermostat ON			
	Pressure equalization	Startup control	
	control prior to startup	STEP1	STEP2
Compressor	0 Hz	52 Hz + OFF + OFF	124 Hz + OFF + OFF +2 steps/20 sec. (until Pc - Pe>0.39MPa is achieved)
Outdoor unit fan	STEP4	Ta<20°C: OFF Ta≥20°C: STEP4	+1 step/15 sec. (when Pc>2.16MPa) -1 step/15 sec. (when Pc<1.77MPa)
Four way valve (20S1)	Holds	OFF	OFF
Main motorized valve (EV1)	0 pls	480 pls	480 pls
Subcooling motorized valve (EV2) (RXYQ8~)	0 pls	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF	OFF
Accumulator oil return valve (SVO)	OFF	OFF	OFF
Injection (SVT) (RXYQ5P model)	OFF	OFF	OFF
Ending conditions	A lapse of one minute	A lapse of 10 sec.	OR • A lapse of 130 sec. • Pc - Pe>0.39MPa


3.1.2 Startup Control in Heating Operation

-	Thermostat ON	-	
	Pressure equalization	Startup control	
	control prior to startup	STEP1	STEP2
Compressor	0 Hz	52 Hz + OFF + OFF	124 Hz + OFF + OFF +2 steps/20 sec. (until Pc - Pe>0.39MPa is achieved)
Outdoor unit fan	STEP4	STEP8	STEP8
Four way valve	Holds	ON	ON
Main motorized valve (EV1)	0 pls	0 pls	0 pls
Subcooling motorized valve (EV2) (RXYQ8~)	0 pls	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF	OFF
Accumulator oil return valve (SVO)	OFF	OFF	OFF
Injection (SVT) (RXYQ5P model)	OFF	OFF	OFF
Ending conditions	A lapse of one minute	A lapse of 10 sec.	• A lapse of 130 sec. • Pc>2.70MPa • Pc-Pe>0.39MPa

Special Control Si34-601A

3.2 Large capacity start up control (Heating)

For startup, oil return operation, or setup after defrosting, start up multiple compressors at a high speed according to the conditions of indoor units with thermostat ON, thus maximizing the equipment capacity.



Start up STD compressors at intervals of 15 seconds.

Si34-601A Special Control

3.3 Oil Return Operation

In order to prevent the compressor from running out of oil, the oil return operation is conducted to recover oil flown out from the compressor to the system side.

3.3.1 Oil Return Operation in Cooling Operation

[Start conditions]

Referring to the set conditions for the following items, start the oil return operation in cooling.

- · Cumulative oil feed rate
- Timer setting (Make this setting so as to start the oil return operation when the initial cumulative operating time reaches two hours after power supply is turned ON and then every eight hours.)

Furthermore, the cumulative oil feed rate is computed from Tc, Te, and compressor loads.

Outdoor unit actuator	Oil return preparation operation	Oil return operation	Post-oil-return operation
Compressor	Take the current step as the upper limit.	5 HP: 52 Hz (→ Low pressure constant control) Other model: 52 Hz + ON + ON (→ Low pressure constant control) Maintain number of compressors in oil return preparation operation ON	Same as the "oil return operation" mode.
Outdoor unit fan	Fan control (Normal cooling)	Fan control (Normal cooling)	Fan control (Normal cooling)
Four way valve	OFF	OFF	OFF
Main motorized valve (EV1)	480 pls	480 pls	480 pls
Subcooling motorized valve (EV2)	SH control	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF	OFF
Accumulator oil return valve (SVO)	ON	ON	ON
Ending conditions	20 sec.	or • 3 min. • Ts - Te<5°C	• 3 min. • Pe<0.6MPa • HTdi>110°C

^{*} In the case of multi-outdoor-unit system,

Master unit: Performs the operations listed in the table above.

Slave units: Operating units perform the operations listed in the table above.

Non-operating units perform the operations listed in the table above from the oil return operation.

(Non-operating unit stops during "oil return preparation operation".)

^{*} Actuators are based on RXYQ14~18P.

Indoor unit actuator		Cooling oil return operation
	Thermostat ON unit	Remote controller setting
Fan	Stopping unit	OFF
	Thermostat OFF unit	Remote controller setting
	Thermostat ON unit	Normal opening
Electronic expansion valve	Stopping unit	224 pls
	Thermostat OFF unit	Normal opening with forced thermostat ON

Special Control Si34-601A

3.3.2 Oil Return Operation in Heating Operation

Outdoor Unit Actuator	Oil return preparation operation	Oil return operation	Post-oil-return operation
Compressor	Upper limit control	176 Hz + ON + ON	124 Hz + OFF + OFF 2-steps increase/20sec. till Pc - Pe>0.4 MPa
Outdoor unit fan	STEP7 or STEP8	OFF	STEP8
Four way valve	ON	OFF	ON
Main motorized valve (EV1)	SH control → 480 pls	480 pls	55 pls
Subcooling motorized valve (EV2)	SH control	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF	OFF
Accumulator oil return valve (SVO)	ON	ON	ON
Injection (SVT) (RXYQ5P model only)	OFF	OFF	OFF
Ending conditions	170 sec.	or • 4 min. • Ts - Te<5°C	or • 10 sec. • Pc - Pe>0.4MPa

^{*} In the case of multi-outdoor-unit system,

Master unit: Performs the operations listed in the table above.

Slave units: Operating units perform the operations listed in the table above.

Non-operating units perform the operations listed in the table above from the oil return operation.

(Non-operating unit stops during "oil return preparation operation".)

^{*} Actuators are based on RXYQ14~18P.

Indoor unit actuator		Heating oil return operation
	Thermostat ON unit	OFF
Fan	Stopping unit	OFF
	Thermostat OFF unit	OFF
	Thermostat ON unit	Oil return EV opening degree
Electronic expansion valve	Stopping unit	256 pls
	Thermostat OFF unit	Oil return EV opening degree

Si34-601A Special Control

3.4 Defrosting Operation

To defrost the outdoor unit heat exchanger while in Evaporator, the defrost operation is conducted to recover the heating capacity.

[Start conditions]

Referring to the set conditions for the following items, start the defrosting operation.

- Heat transfer coefficient of the outdoor unit heat exchanger
- Heat exchange temperature (Tb)
- Timer (Set to two hours at minimum.)

Furthermore, the heat transfer coefficient of the outdoor unit Evaporator is computed from Tc, Te, and compressor loads.

Outdoor unit actuator	Defrost preparation operation	Defrost operation	Post Defrost operation
Compressor	Upper limit control	176 Hz + ON + ON	124 Hz + OFF + OFF 2-steps increase/20sec. till Pc - Pe>0.4 MPa
Outdoor unit fan	STEP7 or STEP8	OFF	STEP8
Four way valve	ON	OFF	ON
Main motorized valve (EV1)	SH control → 480 pls	480 pls	55 pls
Subcooling motorized valve (EV2)	0 pls	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF	OFF
Accumulator oil return valve (SVO)	ON	ON	ON
Injection (SVT) (RXYQ5P model only)	OFF	OFF	OFF
Ending conditions	170 sec.	or • 10 min. • Tb>11°C	or • 10 sec. • Pc - Pe>0.4MPa

^{*} In the case of multi-outdoor-unit system,

Master unit: Performs the operations listed in the table above.

Slave units: Operating units perform the operations listed in the table above.

Non-operating units perform the operations listed in the table above from the Defrost operation.

(Non-operating unit stops during "Defrost preparation operation".)

^{*} Actuators are based on RXYQ14~18P.

Indoor unit actuator		During defrost
Thermostat ON unit		OFF
Fan	Stopping unit	OFF
Thermostat OFF unit		OFF
	Thermostat ON unit	Defrost EV opening degree
Electronic expansion valve	Stopping unit	256 pls
	Thermostat OFF unit	Defrost EV opening degree

Special Control Si34-601A

3.5 Pump-down Residual Operation

3.5.1 Pump-down Residual Operation in Cooling Operation

If the liquid refrigerant stays in the Evaporator at the startup of a compressor, this liquid refrigerant enters the compressor, thus resulting in diluted oil in the compressor and then degraded lubrication performance. Consequently, in order to recover the refrigerant in the Evaporator while the compressor stops, the pump-down residual operation is conducted.

Actuator	Master unit operation	Slave unit operation
Compressor	124 Hz + OFF + OFF	OFF
Outdoor unit fan	Fan control	OFF
Four way valve	OFF	OFF
Main motorized valve (EV1)	480 pls	0 pls
Subcooling motorized valve (EV2)	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF
Accumulator oil return valve (SVO)	ON	ON
Ending conditions	or • 5 min. • Master Unit Pe<0.49 MPa • Master Unit Td>110°C • Master Unit Pc>2.94 MPa	

^{*} Actuators are based on RXYQ14~18P.

3.5.2 Pump-down Residual Operation in Heating Operation

Actuator	Master unit operation	Slave unit operation
Compressor	124 Hz + OFF + OFF	OFF
Outdoor unit fan	STEP7	STEP4
Four way valve	ON	ON
Main motorized valve (EV1)	0 pls	0 pls
Subcooling motorized valve (EV2)	0 pls	0 pls
Hot gas bypass valve (SVP)	OFF	OFF
Accumulator oil return valve (SVO)	ON	ON
Ending conditions	or • 3 min. • Master Unit Pe<0.25 MPa • Master Unit Td>110°C • Master Unit Pc>2.94 MPa	

^{*} Actuators are based on RXYQ14~18P.

Si34-601A Special Control

3.6 Standby

3.6.1 Restart Standby


Used to forcedly stop the compressor for a period of 3 minutes, in order to prevent the frequent ON/OFF of the compressor and equalize the pressure within the refrigerant system.

Actuator	Operation
Compressor	OFF
Outdoor unit fan	Ta>30°C: STEP4 Ta≤30°C: OFF
Four way valve	Holds
Main motorized valve (EV1)	0 pls
Subcooling motorized (EV2)	0 pls
Hot gas bypass valve (SVP)	OFF
Accumulator oil return valve (SVO)	OFF
Injection (SVT) (RXYQ5P model)	OFF
Ending conditions	3 min.

^{*} Actuators are based on RXYQ14~18P.

3.6.2 Crankcase Heater Control

In order to prevent the refrigerant from melting in the compressor oil in the stopped mode, this mode is used to control the crankcase heater.



Special Control Si34-601A

3.7 Stopping Operation

3.7.1 When System is in Stop Mode (Normal operation stop)

This mode is used to define actuator operations when the system stops.

Actuator	Operation
Compressor	OFF
Outdoor unit fan	OFF
Four way valve	Holds
Main motorized valve (EV1)	0 pls
Subcooling motorized valve (EV2)	0 pls
Hot gas bypass valve (SVP)	OFF
Accumulator oil return valve (SVO)	OFF
Injection (SVT) (RXYQ5P model only)	OFF
Ending conditions	Indoor unit thermostat is turned ON.

^{*} Actuators are based on RXYQ14~18P.

3.7.2 Stop due to Malfunction

In order to protect compressors, if any of the following items has an abnormal value, the system will make "stop with thermostat OFF" and the malfunction will be determined according to the number of retry times.

Item	Judgment Criteria	Malfunction Code
1. Abnormal low pressure level	0.07MPa	E4
2. Abnormal high pressure level	4.0MPa	E3
3. Abnormal discharge pipe temperature level	135°C	F3
4. Abnormal power supply voltage	Reverse-phase power supply	U1
5. Abnormal inverter current level	16.1A: 260 sec.	L8
6. Abnormal radiator fin temperature level	93°C	L4

Si34-601A Special Control

3.7.3 Stopping Operation of Slave Units During Master Unit is in Operation with Multi-Outdoor-Unit System

While the master unit is in operation, this mode is used to set the refrigerant flow rate to a required level using a slave unit in the stopped mode.

In cooling operation: Same as that of normal operation stop.

In heating operation: The system operates with following mode.

Actuator	Operation
Compressor	OFF
Outdoor unit fan	OFF
Four way valve	ON
Main motorized valve (EV1)	0 pls
Subcooling motorized valve (EV2)	0 pls
Hot gas bypass valve (SVP)	OFF
Accumulator oil return valve (SVO)	OFF
Injection valve (SVT 5HP only)	OFF
Ending conditions	Slave units are required to operate.

Protection Control Si34-601A


4. Protection Control

4.1 High Pressure Protection Control

This high pressure protection control is used to prevent the activation of protection devices due to abnormal increase of high pressure and to protect compressors against the transient increase of high pressure.


[In cooling operation]

In the case of multi-outdoor-unit system, each outdoor unit performs this control individually in the following sequence.



[In heating operation]

★ In the case of multi-outdoor-unit system, the entire system performs this control in the following sequence.




Si34-601A Protection Control

4.2 Low Pressure Protection Control

This low pressure protection control is used to protect compressors against the transient decrease of low pressure.


[In cooling operation]

★ In the case of multi-outdoor-unit system, the entire system performs this control in the following sequence.



[In heating operation]

★ In the case of multi-outdoor-unit system, each outdoor unit performs this control individually in the following sequence.




Protection Control Si34-601A

4.3 Discharge Pipe Protection Control

This discharge pipe protection control is used to protect the compressor internal temperature against a malfunction or transient increase of discharge pipe temperature.

★ Each compressor performs the discharge pipe temperature protection control individually in the following sequence.


[INV compressor]



[STD compressor]

HTds: Value of STD compressor discharge pipe temperature (Tds) compensated with outdoor air temperature

Tp: Value of compressor port temperature calculated by Tc and Te, and suction superheated degree.




Si34-601A Protection Control

4.4 Inverter Protection Control


Inverter current protection control and inverter fin temperature control are performed to prevent tripping due to a malfunction, or transient inverter overcurrent, and fin temperature increase.

★ In the case of multi-outdoor-unit system, each INV compressor performs these controls in the following sequence.

[Inverter overcurrent protection control]




[Inverter fin temperature control]



Protection Control Si34-601A


4.5 STD Compressor Overload Protection

This control is used to prevent abnormal heating due to overcurrent to the compressor resulting from failures of STD compressor such as locking.



4.6 Injection Control (only for RXYQ5P)

For transitional rise in discharge pipe temperature, have the liquid refrigerant flow into the suction side to reduce the discharge pipe temperature for the compressor protection.



HTdi: Correction value of the discharge pipe temperature on the INV compressor.

Si34-601A Other Control

5. Other Control

5.1 Outdoor Unit Rotation

In the case of multi-outdoor-unit system, this outdoor unit rotation is used to prevent the compressor from burning out due to unbalanced oil level between outdoor units.

[Details of outdoor unit rotation]

In the case of multi-outdoor-unit system, each outdoor unit is given an operating priority for the control.

Outdoor unit rotation makes it possible to change the operating priority of outdoor units.

Thus, the system becomes free of compressors that stop over an extended period of time at the time of partial loading, preventing unbalanced oil level.


[Timing of outdoor unit rotation]

- After oil return operation
- After defrosting operation
- At the beginning of the starting control

When any of outdoor unit stops for a period of 20 minutes or more (in heating)


- There are outdoor units that stop operation (in cooling).
- Low pressure of all outdoor units in operation is less than 0.25 MPa (in cooling).


Example) The following diagram shows outdoor unit rotation in combination of 3 outdoor units. (in heating) (in cooling)



Other Control Si34-601A







* "Master unit", "slave unit 1" and "slave unit 2" in this section are the names for installation. They are determined in installation work, and not changed thereafter. (These names are different from "master unit" and "slave unit" for control.)

The outdoor unit connected the control wires (F1 and F2) for the indoor unit should be designated as main unit.

Consequently, The LED display on the main PC board for "master unit", "slave unit 1" and "slave unit 2" do not change. (Refer to the page 127.)

5.2 **Emergency Operation**

If the compressor cannot operate, this control inhibits any applicable compressor or outdoor unit from operating to perform emergency operation only with the operative compressor or outdoor unit.



Caution

In order to disable the compressor operation due to a failure or else, be sure to do so in emergency operation mode.

NEVER attempt to disconnect power supply wires from magnetic contactors or else. (Doing so will operate compressors in combination that disables oil equalization between the compressors, thus resulting in malfunctions of other normal compressors.)

5.2.1 Restrictions for Emergency Operation

- In the case of system with 1 outdoor unit installed, only when thermostats of indoor units having a capacity of 50% or more of the outdoor unit capacity turn ON, the emergency operation is functional. (If the total capacity of indoor units with thermostat ON is small, the outdoor unit cannot operate.)
- If the emergency operation is set while the outdoor unit is in operation, the outdoor unit stops once after pump-down residual operation (a maximum of 5 minutes elapsed).

Si34-601A Other Control

5.2.2 In the Case of 1-Outdoor-Unit System (RXYQ8P to 18P)

[Set the system to operation prohibition mode by compressor]

 In order to set an INV compressor to operation prohibition mode, set No. 42 of Setting mode 2 to "EMERGENCY OPERATION".

(Procedure)

- (1) Press and hold the MODE button (BS1) for a period of 5 seconds or more.
- (2) Press the SET button (BS2) 42 times.
- (3) Press the RETURN button (BS3) once.
- (4) Press the SET button (BS2) once.
- (5) Press the RETURN button (BS3) twice.
- (6) Press the MODE button (BS1) once.
- In order to set STD1 and STD2 compressors to operation prohibition mode, set No. 19 of Setting mode 2 to "STD1, 2 OPERATION PROHIBITION". (RXYQ10P to 18P)

(Procedure)

- (1) Press and hold the MODE button (BS1) for a period of 5 seconds or more.
- (2) Press the SET button (BS2) 19 times.
- (3) Press the RETURN button (BS3) once.
- (4) Press the SET button (BS2) once.
- (5) Press the RETURN button (BS3) twice.
- (6) Press the MODE button (BS1) once.
- In order to set the STD 2 compressor to operation prohibition mode, set No. 19 of Setting mode 2 to "STD2 OPERATION PROHIBITION". (RXYQ14P, 16P, 18P)

(Procedure)

- (1) Press and hold the MODE button (BS1) for a period of 5 seconds or more.
- (2) Press the SET button (BS2) 19 times.
- (3) Press the RETURN button (BS3) once.
- (4) Press the SET button (BS2) twice.
- (5) Press the RETURN button (BS3) twice.
- (6) Press the MODE button (BS1) once.
- For RXYQ14P, 16P and 18P, if the INV
- compressor is set to operation prohibition mode, only a single STD compressor will operate for the convenience of oil equalization.
- For RXYQ14P, 16P and 18P, only the STD1 compressor cannot be put into operation prohibition mode for the convenience of oil equalization.
- For the system with a single outdoor unit (RXYQ8P to 18P), automatic backup operation is not functional.

5.2.3 In The Case of Multi-Outdoor-Unit System (RXYQ20P to 54P)

[Automatic backup operation]


With multi-outdoor-unit system, if a certain outdoor unit system malfunctions (i.e., the system stops and indoor unit remote controller displays the malfunction), by resetting the system with the indoor unit remote controller, the applicable outdoor unit is inhibited from operating for 8 hours, thus making it possible to perform emergency operation automatically.

However, in the event any of the following malfunctions occurs, automatic backup operation can be performed.


Malfunctions under which automatic backup operation can be performed:

- E3. E4. E5. E7
- F3
- H7, H9
- J2, J3, J5, J6, J7, J9, JA, JC
- L3, L4, L5, L8, L9, LC
- U2, UJ


LED display (\bigcirc :ON \bullet :OFF \bullet :Blink) H1P----H7P



LED display (○:ON ●:OFF ●:Blink) H1P----H7P



LED display (○:ON •:OFF •:Blink) H1P---H7P



Other Control Si34-601A



In order to forcedly clear the automatic backup operation, reset the power supply with the outdoor unit in the stopped state.


Si34-601A Other Control

[Emergency operation with settings in service mode]

* "Inhibition of operation" is set with each outdoor unit.

Make the following settings with the master unit. (Setting with the slave unit becomes disabled.)

* Discriminate the operating status of the master unit / slave units through the following LED display.



 In order to set the master unit to operation prohibition mode, set No. 38 of Setting mode 2 to "MASTER OPERATION PROHIBITION".

(Procedure)


- (1) Press and hold the MODE button (BS1) for a period of 5 seconds or more.
- (2) Press the SET button (BS2) 38 times.
- (3) Press the RETURN button (BS3) once.
- (4) Press the SET button (BS2) once.
- (5) Press the RETURN button (BS3) twice.
- (6) Press the MODE button (BS1) once.
- In order to set the slave unit 1 to operation prohibition mode, set No. 39 of Setting mode 2 to "SLAVE 1 OPERATION PROHIBITION".

(Procedure)


- (1) Press and hold the MODE button (BS1) for a period of 5 seconds or more.
- (2) Press the SET button (BS2) 39 times.
- (3) Press the RETURN button (BS3) once.
- (4) Press the SET button (BS2) once.
- (5) Press the RETURN button (BS3) twice.
- (6) Press the MODE button (BS1) once.
- •In order to set the slave unit 2 to operation prohibition mode, set No. 40 of Setting mode 2 to "SLAVE 2 OPERATION PROHIBITION".

(Procedure)


- (1) Press and hold the MODE button (BS1) for a period of 5 seconds or more.
- (2) Press the SET button (BS2) 40 times.
- (3) Press the RETURN button (BS3) once.
- (4) Press the SET button (BS2) once.
- (5) Press the RETURN button (BS3) twice.
- (6) Press the MODE button (BS1) once.











- In the case of multi-outdoor-unit system, "Inhibition of operation" is not set with each compressor individually.
- In the case of multi-outdoor-unit system, when the above "Inhibition of operation" is set, outdoor unit rotation is not functional.



Note: Reset the power supply during the outdoor unit is stopping to cancel the automatic backup operation forcibly.

Other Control Si34-601A

5.3 Demand Operation

In order to save the power consumption, the capacity of outdoor unit is saved with control forcibly by using "Demand 1 Setting" or "Demand 2 Setting".

To operate the unit with this mode, additional setting of "Continuous Demand Setting" or external input by external control adapter is required.

Set item	Condition	Content
Demand 1	Mode 1	The compressor operates at approx. 60% or less of rating.
	Mode 2	The compressor operates at approx. 70% or less of rating.
	Mode 3	The compressor operates at approx. 80% or less of rating.
Demand 2	_	The compressor operates at approx. 40% or less of rating.

5.4 Heating Operation Prohibition


Heating operation is prohibited above 24°C ambient temperature.

6. Outline of Control (Indoor Unit)

6.1 Drain Pump Control


1. The drain pump is controlled by the ON/OFF buttons (4 button (1) - (4) given in the figure below).

6.1.1 When the Float Switch is Tripped While the Cooling Thermostat is ON:




* 1. The objective of residual operation is to completely drain any moisture adhering to the fin of the indoor unit heat exchanger when the thermostat goes off during cooling operation.

6.1.2 When the Float Switch is Tripped while the Cooling Thermostat is OFF:




6.1.3 When the Float Switch is Tripped During Heating Operation:



During heating operation, if the float switch is not reset even after the 5 minutes operation, 5 seconds stop, 5 minutes operation cycle ends, operation continues until the switch is reset.

6.1.4 When the Float Switch is Tripped and "AF" is Displayed on the Remote Controller:




Note:

If the float switch is tripped five times in succession, a drain malfunction is determined to have occurred. "AF" is then displayed as operation continues.

6.2 Louver Control for Preventing Ceiling Dirt

We have added a control feature that allows you to select the range of in which air direction can be adjusted in order to prevent the ceiling surrounding the air discharge outlet of ceiling mounted cassette type units from being soiled. (This feature is available on double flow, multiflow and corner types.)



The factory set position is standard position.


(VL012)

6.3 Thermostat Sensor in Remote Controller

Temperature is controlled by both the thermostat sensor in remote controller and air suction thermostat in the indoor unit. (This is however limited to when the field setting for the thermostat sensor in remote controller is set to "Use.")

Cooling

If there is a significant difference in the preset temperature and the suction temperature, fine adjustment control is carried out using a body thermostat sensor, or using the sensor in the remote controller near the position of the user when the suction temperature is near the preset temperature.



■ Ex: When cooling

Assuming the preset temperature in the figure above is 24°C, and the suction temperature has changed from 18°C to 30°C (A \rightarrow F):

(This example also assumes there are several other air conditioners, the VRV system is off, and that temperature changes even when the thermostat sensor is off.)

Body thermostat sensor is used for temperatures from 18°C to 23°C (A \rightarrow C).

Remote controller thermostat sensor is used for temperatures from 23°C to 27°C (C \rightarrow E).

Body thermostat sensor is used for temperatures from 27°C to 30°C (E \rightarrow F).

And, assuming suction temperature has changed from 30°C to 18°C (F \rightarrow A):


Body thermostat sensor is used for temperatures from 30°C to 25°C (F \rightarrow D).

Remote controller thermostat sensor is used for temperatures from 25°C to 21°C (D \rightarrow B).

Body thermostat sensor is used for temperatures from 21°C to 18°C (B \rightarrow A).

Heating

When heating, the hot air rises to the top of the room, resulting in the temperature being lower near the floor where the occupants are. When controlling by body thermostat sensor only, the unit may therefore be turned off by the thermostat before the lower part of the room reaches the preset temperature. The temperature can be controlled so the lower part of the room where the occupants are doesn't become cold by widening the range in which thermostat sensor in remote controller can be used so that suction temperature is higher than the preset temperature.



Ex: When heating Assuming the preset temperature in the figure above is 24°C, and the suction temperature has changed from 18°C to 28°C (A \rightarrow D):


(This example also assumes there are several other air conditioners, the VRV system is off, and that temperature changes even when the thermostat sensor is off.) Body thermostat sensor is used for temperatures from 18°C to 25°C (A \rightarrow C). Remote controller thermostat sensor is used for temperatures from 25°C to 28°C (C \rightarrow D).

And, assuming suction temperature has changed from 28°C to 18°C (D \rightarrow A): Remote controller thermostat sensor is used for temperatures from 28°C to 23°C (D \rightarrow B).

Body thermostat sensor is used for temperatures from 23°C to 18°C (B \rightarrow A).

6.4 Thermostat Control While in Normal Operation

VRV multi systems are set at factory to thermostat control mode using the remote controller. While in normal thermostat differential control mode (i.e., factory set mode), the thermostat turns OFF when the system reaches a temperature of -1°C from the set temperature while in cooling operation or of +1°C from that while in heating operation.




While in a single remote controller group control, the body thermostat is only used fro this control.

Furthermore, while in heating operation, cassette-mounted indoor units conduct the thermostat control by a value compensated by -2°C for the value detected with the body thermostat. (Through field settings, the thermostat differential setting can be changed from 1°C to 0.5°C. For details on the changing procedure, refer to information on page onward.)

6.5 Thermostat Control in Dry Operation

While in dry operation, the thermostat control is conducted according to a suction temperature at the time of starting the dry operation.

Assuming that the suction air temperature at the time of starting the dry operation is Tro and the suction air temperature in operation is Tr.



Furthermore, while in dry operation mode, fans operate at L flow rate, stops for a period of six minutes while the thermostat is OFF, and then return to operation at L flow rate. (This control is used to prevent a rise in indoor temperature while in thermostat OFF mode.)

6.6 Electronic Expansion Valve Control

• Electronic expansion Valve Control

In cooling, to maximize the capacity of indoor unit heat exchanger (evaporator), operate the electronic expansion valve under PI control so that the evaporator outlet superheated degree (SH) will become constant.

In heating, to maximize the capacity of indoor unit heat exchanger (condenser), operate the electronic expansion valve under PI control so that the evaporator outlet superheated degree (Condenser outlet subcooled degree) will become constant.

Cooling SH=TH₂-TH₁ SH: Evaporator outlet superheated degree

(Heating SC=TC-TH₁) TH₁: Temperature (°C) detected with the liquid thermistor

TH₂: Temperature (°C) detected with the gas thermistor

SC : Condenser outlet subcooled degree

TC: High pressure equivalent saturated temperature


Furthermore, the default value of the optimal evaporator outlet superheated degree (condenser outlet subcooled degree) is 5 deg. However, this default value varies with the operating performance.

6.7 Hot Start Control (In Heating Operation Only)

At startup with thermostat ON or after the completion of defrosting in heating operation, the indoor unit fan is controlled to prevent cold air from blasting out and ensure startup capacity.

[Detail of operation]

When either the **start condition 1** or the **start condition 2** is established, the operations shown below will be conducted.



TH $_2$: Temperature (°C) detected with the gas thermistor

TC: High pressure equivalent saturated temperature


6.8 Freeze Prevention

Freeze Prevention by Off Cycle (Indoor Unit) When the temperature detected by liquid pipe temperature thermistor (R2T) of the indoor unit heat exchanger drops too low, the unit enters freeze prevention operation in accordance with the following conditions, and is also set in accordance with the conditions given below.

Conditions for starting freeze prevention: Temperature is -1°C or less for total of 40 min., or temperature is -5°C or less for total of 10 min.

Conditions for stopping freeze prevention: Temperature is +7°C or more for 10 min. continuously

Ex: Case where temperature is -5°C or less for total of 10 min.



6.9 Heater Control

The heater control is conducted in the following manner.


[Normal control]


While in heating operation, the heater control (ON/OFF) is conducted as shown on the right.

[Overload control]


When the system is overloaded in heating operation, the heater will be turned OFF in the following two manners.

 The heater control (ON/OFF) is conducted through the liquid pipe temperature (R2T) of the indoor unit.





(2) The heater control (ON/OFF) is conducted by converting the heater temperature into the condensing pressure equivalent saturated temperature (Tc) according to the temperature detection



through the high pressure sensor (SINPH) of the outdoor unit.

[Fan residual operation]

While the heater turns OFF, in order to prevent the activation of the thermal protector, the fan conducts residual operation for a given period of time after the heater turns OFF. (This operation is conducted regardless of with or without heater equipped.)

Residual operation time = 100 seconds on ceiling suspended type or 60 seconds on other types

6.10 List of Swing Flap Operations

Swing flaps operate as shown in table below.

				Flap			
			Fan	FXFQ	FXCQ FXHQ FXKQ	FXAQ	
	Hot start from defrosting	Swing	OFF	Horizontal	Horizontal	Horizontal	
	operation	Wind direction set	OFF	Horizontal	Horizontal	Horizontal	
	Defrosting operation	Swing	OFF	Horizontal	Horizontal	Horizontal	
	Denosting operation	Wind direction set	OFF	Horizontal	Horizontal	Horizontal	
Heating	Thermostat OFF	Swing	LL	Horizontal	Horizontal	Horizontal	
пеашу	memosiai OFF	Wind direction set	LL	Horizontal	Horizontal	Horizontal	
	Hot start from thermostat OFF mode (for prevention	Swing	LL	Horizontal	Horizontal	Horizontal	
	of cold air)	Wind direction set	LL	Horizontal	Horizontal	Horizontal	
	0:	Swing	OFF	Horizontal	Horizontal	Totally closed	
	Stop	Wind direction set	OFF	Horizontal	Horizontal	Totally closed	
	Thermostat ON in dry	Swing	L* ¹	Swing	Swing	Swing	
	operation using micro computer	Wind direction set	L* ¹	Set	Set	Set	
	Thermostat OFF in dry operation using micro	Swing	OFF or L	Swing	Swing	Swing	
	computer	Wind direction set	OFFOIL	Set	Set	Set	
Cooling	Thermostat OFF in	Swing	Set	Swing	Swing	Swing	
Cooling	cooling	Wind direction set	Set	Set	Set	Set	
	Stop	Swing	OFF	Horizontal	Horizontal	Totally closed	
	Stop	Wind direction set	OFF	Set	Horizontal	Totally closed	
	Micro computer control	Swing	L	Swing	Swing	Swing	
	(including cooling operation)	Wind direction set	L	Set	Set	Set	

*1. L or LL only on FXFQ models

6.11 Control of Outdoor Air Processing Unit (Unique Control for Outdoor Air Processing Unit)


6.11.1 Selection of Operation Mode (by suction air thermostat)

Objective

To select cooling, heating, or fan operation mode according to the suction air (outdoor air) temperature.

Details


[Outdoor air processing unit]




6.11.2 Discharge Air Temperature Control

Used to control the EV (electronic expansion valve) opening and thermostat ON/OFF so as to keep the discharge air temperature at the set temperature.


(1) Cooling operations



- T1: Temperature detected by suction air thermistor Th1
- T2: Temperature detected by liquid pipe temp. thermistor Th2
- T3: Temperature detected by gas pipe temp. thermistor Th3
- T4: Temperature detected by discharge air thermistor Th4
- EV: Electronic expansion valve opening



(2) Heating operations



T1: Temperature detected by suction air thermistor Th1


T2: Temperature detected by liquid pipe temp. thermistor Th2

T3: Temperature detected by gas pipe temp. thermistor Th3

T4: Temperature detected by discharge air thermistor Th4

Tc: Outdoor unit condensing temperature

EV: Electronic expansion valve opening



(3) Thermostat OFF by discharge air temperature

<Cooling>

```
Target discharge air temp. Ts – Discharge air temp. T4

>5 degree continue for 5 minutes.

→Thermostat stops for 1 minute. →Thermostat ON
```

<Heating>

```
& Discharge air temp. T4 – Target discharge air temp. Ts >5 degree continue for 5 EV opening is low limit
```

→Thermostat stops for 1 minute. →Thermostat ON

6.11.3 Low Outdoor Air Temperature Protection Control

Objective

In cooling (or fan operation) or heating, if outdoor air is low in temperature, stop the fan forcibly.

Details

[Cooling and fan operation]

Turn OFF the fan for a period of 60 minutes at a suction temperature of 5°C or lower. In order to monitor the outdoor air temperature, however, turn ON the fan for a period of one minute and turn OFF the fan again at a temperature of 5°C or lower after the said timer completes the operative period.

Reset the 60-minute timer when the fan stops running.

[Heating]

Turn OFF the fan for a period of 60 minutes at a suction temperature of -5° C or lower. In order to monitor the outdoor air temperature, however, turn ON the fan for a period of one minute and turn OFF the fan again at a temperature of -5° C or lower after the said timer completes the operative period.

Reset the 60-minute timer when the fan stops running.

- * The thermostat will not turn ON in one minute due to the temperature while the fan stops.
- This control shall be disabled at test run both in cooling and heating. (The test run shall be conducted first.)


Part 5 Test Operation

1.	Lest	Operation	144
		Installation Process	
	1.2	Procedure and Outline	145
	1.3	Operation When Power is Turned On	159
2.	Outo	door Unit PC Board Layout	160
3.	Field	d Setting	161
		Field Setting from Remote Controller	
	3.2	Field Setting from Outdoor Unit	174

1. Test Operation

1.1 Installation Process

Below Fiure shows the installation process. Install in the order of the steps shown.



Si34-601A **Test Operation**

1.2 **Procedure and Outline**

Follow the following procedure to conduct the initial test operation after installation.

Check work prior to turn power supply on

Check the below items.

- Power wiring
- · Control transmission wiring between units
- · Earth wire



Check on refrigerant piping /

insulation materials



Check airtight test and vacuum drying.



Check on amount of refrigerant charge




O Is the wiring performed as specified?

- O Is the designated wire used?
- O Is the wiring screw of wiring not loose?
- O Is the grounding work completed?
- O Is the insulation of the main power supply circuit deteriorated? Use a 500V megger tester to measure the insulation. (*1)
 - · Do not use a megger tester for other circuits than 200V (or 240V) circuit.

*1:Measure to be taken against decreased insulation resistance in the compressor

If the compressor is left to stand for an extended period of time after the refrigerant charge with the stop valve open and the power supply OFF, the refrigerant may be mixed in the compressor, thus decreasing the insulation resistance.

Heat the compressor as shown on the right and then recheck the insulation.



O Is the pipe size proper?

- O Is the pipe insulation material installed securely? Liquid and gas pipes need to be insulated. (Otherwise causes water leak.)
- O Have the airtight test and the vacuum drying been conducted according to the procedure in the Installation Manual?
- O Is a proper quantity of refrigerant refilled? The following two methods are available for refilling of the refrigerant.
 - (1) Use the automatic refrigerant refilling function.
 - (2) Calculate a refrigerant refilling quantity.

Check the stop valves for conditions.

O Check to be sure the stop valves are under the following conditions.

Liquid-side stop valve	Gas-side stop valve
Open	Open

1.2.2 Turn power on

Turn outdoor unit and indoor unit power on.



Check the LED display of the outdoor unit PC board.



Make field settings with outdoor



Conduct check operations.

unit PC board.



Check for normal operation.

O Be sure to turn the power on 6 hours before starting operation to protect compressors. (to power on clankcase heater)

 Check to be sure the transmission is normal.
 The transmission is normal if the LEDs display conditions as shown in table below.

					LE	D displa	y O	N • O	FF • E	Blinking
		Micro-			COOL	/ HEAT	select	Low		
LED display (Default status before delivery)		computer operation monitor	MODE	TEST	IND	MASTER	SLAVE	Low noise	Demand	Multi
			H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H8P
One outdoor unit	installed	•	•	•	0	•	•	•	•	•
When multiple	Master	•	•	•	0	•	•	•	•	0
outdoor unit installed (*)	Slave 1	•	•	•	•	•	•	•	•	•
	Slave 2	•	•	•	•	•	•	•	•	•

(*) The master unit is the outdoor unit to which the transmission wiring for the indoor units is conncted.

The other outdoor units are slave units.

O Make field settings if needed.

(For the setting procedure, refer to information in "3.2. Field Setting from Outdoor Unit" on page 174 onward.)

For the outdoor-multi system, make field settings with the master unit. (Field settings made with the slave unit will be all invalid.)

The check operations shown below will be automatically initiated.

- Check for erroneous wirings
- Check for failure to open stop valves
- Check for excessive refrigerant refilling
- Automatic judgment of piping length
- O Before starting the normal operation after the completion of check operations, make sure indoor and outdoor units normally operate.

Si34-601A Test Operation

1.2.3 Air Tight Test and Vacuum Drying

Note:

- Always use nitrogen gas for the airtightness test.
- Absolutely do not open the shutoff valve until the main power ciruit insulation measurement has been completed. (measuring after the shutoff valve is opened will cause the insulation value to drop.)

1.2.3.1 Preparations

<Needed tools>

Gauge manifold Charge hose valve	To prevent entry of any impurities and insure sufficient pressure resistance, always use the special tools dedicated for R-410A. Use charge hose that have pushing stick for connecting to service port of shutoff valves or refrigerant charge port.
Vacuum pump	The vacuum pump for vacuum drying should be able to lower the pressure to -100.7kPa (5 Torr -755mm Hg). Take care the pump oil never flow backward into the refrigerant pipe during the pump stops.

<The system for air tight test and vacuum drying>

- Referring to figure 28, connect an nitrogen tank, refrigerant tank, and a vacuum pump to the outdoor unit.
- The shutoff valve and valve A~C in figure 28 should be open or closed as shown in the table below.




fig. 28

of valve A, B and C and shutoff valves		Valve		shutoff valve		
		В	С	Liquid side	Gas side	
Air tight test, Vacuum drying (Close valve A and shutoff valves certainly. Otherwise the refrigerant in the unit are released.)	Close	Open	Open	Close	Close	

Note:

- The airtightness test and vacuum drying should be done using the liquid side and gas side shutoff valve service ports.
 - See the [R-410A] Label attached to the front plate of the outdoor unit for details on the location of the service port (see figure at right).
- See [Shutoff valve operation procedure] for details on handling the shutoff valve. (Refer page 149)
- The refrigerant charge port is connected to unit pipe.
 When shipped, the unit contains refrigerant, so use caution when attaching the charge hose.



[Caution] Label

1.2.3.2 Air Tight Test and Vacuum Drying Method

After finished piping work, carry out air tight test and vacuum drying.

<Air tight test>

Pressurize the liquid and gas pipes to 4.0MPa (40bar) (do not pressurize more than 4.0MPa (40bar)). If the pressure does not drop within 24 hours, the system passes the test.

If there is a pressure drop, check for leaks, make repairs, and perform the airtight test again.

<Vacuum drying>

work, etc.)

Evacuate the system from the liquid and gas pipes by using a vacuum pump for more than 2 hours and bring the system to –100.7kPa or less. After keeping the system under that condition for more than 1 hour, check if the vacuum gauge rises or not. If it rises, the system may either contain moisture inside or have leaks.

Note:

- If moisture might enter the piping, follow belows.
 (I.e., if doing work during the rainy season, if the actual work takes long enough that condensation may form on the inside of the pipes, if rain might enter the pipes during
- 1. After performing the vacuum drying for two hours, pressurize to 0.05 MPa (i.e., vacuum breakdown) with nitrogen gas, then depressurize down to –100.7 kPa for an hour using the vacuum pump (vacuum drying).
- 2. If the pressure does not reach –100.7 kPa even after depressurizing for at least two hours, repeat the vacuum breakdown vacuum drying process.

After vacuum drying, maintain the vacuum for an hour and make sure the pressure does not rise by monitoring with a vacuum gauge.

1.2.4 Additional Refrigerant Charge and Check Operation

The outdoor unit is charged with refrigerant when shipped from the factory, but depending on the size and length of the piping when installed, it may require additional charging. For charging the additional refrigerant, follow the procedure in this chapter. And then carry out the check operation.

Note: Total amount of refrigerant should be 100 kg or less

1.2.4.1 Before Working

[About the refrigerant cylinder]

Check whether the cylinder has a siphon pipe before charging and place the cylinder so that the refrigerant is charged in liquid form. (See the figure below.)

. 3	, · · · · · · · · · · · · · · · · · · ·	
With siphon pipe		
	Stand the cylinder upright and charge. (The siphon pipe goes all the way inside, so the cylinder does not need be put upside-down charge in liquid form.)	
Other tanks		
	Stand the cylinder upside-down and charge.	



- Always use the proper refrigerant (R-410A). If charged with the refrigerant containing an improper material, it may cause an explosion or accident.
- R-410A is a mixed refrigerant, so charging it as a gas will cause the refrigerant composition to change, which may prevent normal operation.

Si34-601A Test Operation

[Shutoff Valve Operation Procedure]

When operating the shutoff valve, follow the procedure instructed below.

Note:

- Do not open the shutoff valve until "1.2.1 Check work prior to turn power supply on" in page 145 are completed. If the shutoff valve is left open without turning on the power, it may cause refrigerant to buildup in the compressor, leading insulation degradation.
- Be sure to use the correct tools.
- The shutoff valve is not a back-seat type. If forced it to open, it might break the valve body.
- When using a service port, use the charge hose.
- After tightening the cap, make sure no refrigerant gas is leaking.

[Tightening torque]

The sizes of the shutoff valves on each model and the tightening torque for each size are listed in the table below.

<Size of Shutoff Valve>

	5HP type	8HP type	10HP type	12HP type	14HP type	16HP type	18HP type		
	The 12HP ty onsite piping	pe correspo			φ 12.7 The 18HP type corresponds to the 15.9-diameter onsite piping using the accessory pipe.				
Gas side shutoff valve	ф 15.9	φ 19.1		er onsite pip HP type cori	ing using the responds to t				

<Tightening torque>

	Tightening torque N⋅m (Turn clockwise to close)								
Shutoff valve size	Shaft (va	lve body)	Cap (valve lid)	Service port					
φ 9.5	5.4 - 6.6	Hexagonal wrench	13.5 - 16.5						
φ 12.7	8.1 - 9.9	4 mm	18.0 - 22.0						
ф 15.9	13.5 - 16.5	Hexagonal wrench 6 mm		11.5 - 13.9					
ф 19.1	27.0 - 33.0	Hexagonal wrench	22.5 - 27.5						
ф 25.4	φ 25.4 27.0 - 33.0								




fig 34

[To open]

- 1. Remove the cap and turn the shaft counterclockwise with the hexagon wrench (JISB4648).
- 2. Turn it until the shaft stops.
- Make sure to tighten the cap securely.
 (For the tightening torque, refer to the item <Tightening Torque>.)

[To close]

- 1. Remove the cap and turn the shaft clockwise with the hexagon wrench (JISB4648).
- 2. Securely tighten the valve until the shaft contacts the main body seal.
- Make sure to tighten the cap securely.(For the tightening torque, refer to the item <Tightening Torque>.)

[How to Check How Many Units are Connected]

It is possible to find out how many indoor or outdoor unit in the system are turned on by operating the push button on the PC-board (A1P) of outdoor unit (In case of multi system master unit).

Follow the procedure below to check how many indoor or outdoor units are turned on.

			Į	_ED	dis	play	y		
	(LED display: ●OFF ۞ON ۞Blin	H ₁ P	H 2 P	H 3 P	H 4 P	H 5 P	H 6 P	H 7 P	
1.	 Press the MODE button (BS1) once, and set the MONITOR MODE (H1P: Blinking). 						•	•	•
2.	Press the SET button (BS2) the number of number of outdoor units: eight times					≎	•	•	•
	times until the LED display matches that at right. For checking the number of indoor units: five times				•	•	≎	•	¢
3.	3. Press the RETURN button (BS3) and read the number of units from the display of H2P through H7P. [Reading Method] The display of H2P through H7P should be read as a binary number, with → standing for "1" and ● standing for "0".						*	*	*
	Ex: For the LED display at right, this would be "0 1 0 1 1 0", which would mean 22 units are connected. $32 \times 0 + 16 \times 1 + 8 \times 0 + 4 \times 1 + 2 \times 1 + 1 \times 0 = 22 \text{ units}$ Note: "000000" indicates 64 units.					•	Φ	Φ	•
4.	Press the MODE button (BS1) once. This retu (default).	rns to Setting Mode 1	•	•	≎	•	•	•	•

Note:

Press the "MODE button" (BS1) if you get confused while operating. This returns to **Setting Mode 1** (default).

Si34-601A Test Operation

1.2.4.2 Procedure of Adding Refrigerant Charging and Check Operation



Warning

4 Electric Shock Warning

■ Make sure to close the EL. COMPO. BOX lid before turning on the power when performing the refrigerant charging operation.

- Perform the setting on the PC-board (A1P) of the outdoor unit and check the LED display after the power is on via the inspection door which is in the EL. COMPO. BOX lid.
- Use an insulated rod to operate the push buttons via the EL. COMPO. BOX's inspection door.

There is a risk of electric shock if you touch any live parts, since this operation must be performed with the power on.



- Make sure to use the protect tool (protective groves and goggles) when charging the refrigerant.
- Due to a danger of liquid hammer, the refrigerant must not be charged over the allowable maximum amount when charging the refrigerant.
- Do not perform the refrigerant charging operation under working for the indoor unit.
- When opening the front panel, make sure to take caution to the fan rotation during the working.

After the outdoor unit stops operating, the fan may keep rotation for a while.

Note:

- If operation is performed within 12 minutes after the indoor and outdoor units are turned on, H2P will be lit on and the compressor will not operate.
- In order to ensure uniform refrigerant distribution, it may take up to around 10 minutes for the compressor to start up after the unit starting operating. This is not a malfunction.

<About refrigerant charging>

- The refrigerant charge port is connected to the piping inside the unit.

 When the unit is shipped from the factory, the unit's internal piping is already charged with refrigerant, so be careful when connecting the charge hose.
- After adding the refrigerant, make sure to close the lid of the refrigerant charging port. The tightening torque for the lid is 11.5 to 13.9 Nm.
- See [Shutoff valve operation procedure] in 1.2.4.1 for details on how to handle shutoff valves.
- When done or when pausing the refrigerant charging operation, close the valve of the refrigerant tank immediately. If the tank is left with the valve open, the amount of refrigerant which is properly charged may be off the point. More refrigerant may be charged by any remaining pressure after the machine is stopped.

<About check operation>

- Make sure to perform the check operation after installation. Otherwise, the malfunction code "U3" will be displayed and normal operation cannot be performed.
 - And the failure of "Check of miswiring" may also cause abnormal operation. Performance may drop due to the failure of "Judgment of piping length".
- Check operation must be performed for each refrigerant piping system.
 - Checking is impossible if plural systems are being done at once.
- The individual problems of indoor units can not be checked.

 About these problems check by test run after the check operation is completed. (See page 158)
- The check operation cannot be performed in recovery or other service modes.
- 1. Make sure the following works are complete in accordance with the installation manual.
 - ■Piping work
 - ■Wiring work
 - ■Air tight test
 - ■Vacuum drying
 - ■Installation work for indoor unit
- 2. Calculate the "additional charging amount" using "How to calculate the additional refrigerant to be charged" in "6 Example of connection" on Part7. Appendix in page 363.

3. Open the valve C (See the figure 31. The valve A, B and the liquid and gas side shutout valve must be left closed), and charge the refrigerant of the "additional charging amount" from the liquid side shutout valve service port.

If the "additional charging amount" was charged fully, close the valve C and go to step 5. If the "additional charging amount" was not charged fully, go to step 4.




fig 31


4. Perform the refrigerant charging operation following [Refrigerant charging operation procedure] as shown in page 153, and charge the remaining refrigerant of the "additional charging amount". For performing the refrigerant charging operation the push button on the PC-board (A1P) of outdoor unit (Incase of multi system master unit) are use. (See the figure 32) In addition, the refrigerant are charged from the refrigerant charge port via the valve A. (See the figure 33)

For operating the push button and opening and closing the valve, follow the work procedure.

Note:

The refrigerant will be charged about 22kg in one hour at outdoor temp. 30°C DB (6kg at 0°C DB).

If you need to speedup in case of multi system, connect the refrigerant cylinders to each outdoor unit as shown in the figure 33.






fig 33

Si34-601A Test Operation

[Refrigerant Charging Operation Procedure]

STEP1 Open the liquid and gas side shutoff valves (The valve A~C must be closed. The valve A~C means the valves in the figure 33.)

[Display of normal system]

in the state of th										
LED display (Default status of shipped)		SERV.		TEST/		SELEC	_		DEMA-	
		MONI- TOR	MODE	HWL	IND	MASTE R	SLAVE	L.N.O.P	ND	MULTI
		HAP	H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H8P
Single	system	•	•	•	Ф	•	•	•	•	•
Multi	Master unit	❖	•	•	¢	•	•	•	•	≎
system	Sub unit 1	﴾	•	•	•	•	•	•	•	Φ
(*)	Sub unit 2	•	•	•	•	•	•	•	•	•

LED display: ●...OFF, ♦...ON, ♦...Blinking

(*)How to distinguish the master unit, sub unit 1, and sub unit 2 in the multi system.

Method 1: By the H8P (MULTI) LED display

⊕ (ON): Master unit ⊕ (Blinking): Sub unit 1 ⊕ (OFF): Sub unit 2	☼ (ON): Master unit	(Blinking): Sub unit 1	● (OFF): Sub unit 2
--	---------------------	------------------------	---------------------

Method 2: By the transmission wiring to indoor unit

Transmission wiring is connected: Master unit

Transmission wiring is not connected: Sub unit 1 or Sub unit 2

STEP2 If necessary, set the field setting by using the dip switch on the outdoor unit PC-board(A1P).

(For how to set, see "1.2.5.1 Onsite Settings With the Power Off")

- **STEP3** Close the EL. COMPO. BOX lid and all front panel except on the side of the EL. COMPO. BOX (*1) and turn the power to the outdoor unit and all connected indoor units. (*2)
 - After H2P stop blinking (about 12 minutes after turning on the power), check LED displays as shown in the table [Display of normal system] and the system is normal state.

If H2P is blinking, check the malfunction code in the remote controller, and correct the malfunction in accordance with [Remote controller display malfunction code] in page 155.

- (*1) Lead the refrigerant charge hose etc from the pipe intake. All front panels must be closed at the procedure (9).
- (*2) If you perform the refrigerant charging operation within the refrigerant system that have

the power off unit, the operation cannot finish properly.

For confirming the number of the outdoor and indoor units with the power on, see [How to check how many units are connected] in chapter 1.2.4.1. In case of a multi system,

turn on the power to all outdoor units in the refrigerant system.

- To energize the crankcase heater, make sure to turn on for 6 hours before starting operation.
- **STEP4** Start the additional refrigerant charge operation.

(About the system settings for additional refrigerant charge operation, refer to the [Service Precaution] label attached on the EL. COMPO. BOX lid in the outdoor unit.) Open valve A immediately after starting the compressor.

STEP5 Close the valve A if the "additional charging amount" of refrigerant was charged, and push the RETURN button (BS3) once.

STEP6 Record the charging amount on the accessory "REQUEST FOR THE INDICATION" label and attach it to the back side of the front panel.

5. After completing the additional refrigerant charging perform the check operation following below

NOTE:

- For check operation, the following work will be performed.
 - Check of shutoff valve opening
 - Check of miswiring
 - Judgment of piping length
 - Check of refrigerant overcharge
- It takes about 40 minutes to complete the check operation.

[Check Operation Procedure]

- **STEP1** Make the onsite setting as needed using the dip switches on the outdoor unit PC-board (A1P) with the power off (See "1.2.5.1 Onsite Settings With the Power Off")
- **STEP2** Close the EL. COMPO. BOX lid and all front panels except as the side of the EL. COMPO. BOX and turn on the power to the outdoor unit and all connected indoor units. (Be sure to turn the power on at least 6 hours before operation in order to have power running to the crank case heater.)
- **STEP3** Check the LED display on the outdoor unit PC-board (A1P) is as shown in the table below and transmission is normal.

LED display (Default status of shipped)		SERV.				SELEC	-		DEMA	
		MONI- TOR		TEST/ HWL	IND	MASTE R	SLAVE	L.N.O.P	ND	MULTI
		HAP	H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H8P
Single	Single system		•	•	¢	•	•	•	•	•
Multi	Master unit	﴾	•	•	≎	•	•	•	•	¢
system (*)	Sub unit 1	﴾	•	•	•	•	•	•	•	Φ
	Sub unit 2	•	•	•	•	•	•	•	•	•

LED display: ●...OFF, ♦...ON, ♦...Blinking

(*)How to distinguish the master unit, sub unit 1, and sub unit 2 in the multi system.

Method 1: By the H8P (MULTI) LED display

☼ (ON): Master unit ♠ (Blinking): Sub unit 1	• (OFF): Sub unit 2
--	---------------------

Method 2: By the transmission wiring to indoor unit

Transmission wiring is connected: Master unit

Transmission wiring is not connected: Sub unit 1 or Sub unit 2

- **STEP4** Make the onsite settings as needed using the push button (BS1-BS5) on the outdoor unit PC-board (A1P) with the power on. (See "1.2.5.2 Onsite Settings With the Power On")
- **STEP5** Perform the check operation following the Check Operation Method of the [Service Precautions] label on the EL. COMPO. BOX lid. The system operation for about 40 minutes and automatically stops the check operation.

If the malfunction code is not displayed in the remote controller after the system stop, check operation is completed. Normal operation will be possible after 5 minutes. If the malfunction code is displayed in the remote controller, correct the malfunction following [Remote controller displays malfunction code] and perform the check operation again.

Si34-601A Test Operation

[Remote controller displays malfunction code]

Malfunction code	Installation error	Remedial action
E3, E4 F3, F6 UF	The shutoff valve of the outdoor unit is left closed.	Open the shutoff valve.
U1	The phases of the power to the outdoor unit is reversed.	Exchange two of the three phases (L1, L2, L3) to make a proper connection.
U1 U4 LC	No power is supplied to an outdoor or indoor unit (including phase interruption).	Make sure the power source wire is properly connected to the outdoor unit and revise if necessary.
UF	There is conflict on the connection of transmission wiring in the system.	Check if the refrigerant piping line and the transmission wiring are consistent with each other.
E3 F6 UF	Refrigerant overcharge.	Recalculate the additional amount refrigerant from the piping length and correct the refrigerant charge level by recovering any excessive refrigerant with a refrigerant recovery machine.
E4 F3	Insufficient refrigerant.	 Check if the additional refrigerant charge has been finished correctly. Recalculate the additional amount refrigerant from the piping length and add the adequate amount.
U7, U4 UF, UH	If the outdoor unit terminal is connected when there is one outdoor unit installed.	Remove the line from the outdoor multi terminals (Q1 and Q2).

If any malfunction codes other than the above are displayed, check the service manual for how to respond.

1.2.5 Onsite Settings


NOTE:

In the case of a multi system, all onsite settings should be made on the master unit. Settings made on sub units are invalid.

The outdoor unit to which the indoor unit transmission wire are connected is the master unit, and all other units are sub units.

1.2.5.1 Onsite Settings with the Power Off

If the COOL/HEAT selector was connected to the outdoor unit, set the dip switch (DS1) on the outdoor unit PC-board (A1P) to "ON" (it is set to "OFF" when shipped from the factory). For the position of the dip switch (DS1), see the "Service Precautions" label (see at right) which is attached to the EL. COMPO. BOX lid.





Warning



Electric Shock Warning

Never perform with the power on.

There is a serious risk of electric shock if any live part is touched.

1.2.5.2 Onsite Settings with the Power On

Use the push button switches (BS1 through BS5) on the outdoor unit PC-board (A1P) to make the necessary onsite settings.

See the "Service Precautions" label on the EL. CONPO. BOX lid for details on the positions and operating method of the push button switches and on the onsite setting.

Make sure to record the setting on the accessory "REQUEST FOR THE INDICATION" label.



Warning



Electric Shock Warning

Use an insulated rod to operate the push buttons via the inspection door of EL. COMPO. BOX lid.

There is a risk of electric shock if you touch any live parts, since this operation must be performed with the power on.

Si34-601A Test Operation

1.2.6 Test Run

1.2.6.1 Before Test Run

- Make sure the following works are completed in accordance with the installation manual.
 - ■Piping work
 - ■Wiring work
 - ■Air tight test
 - ■Vacuum drying
 - ■Additional refrigerant charge
- Check that all work for the indoor unit are finished and there are no danger to operate.

1.2.6.2 Test Run

After check operation is completed, operate the unit normally and check the following.

- (1) Make sure the indoor and outdoor units are operating normally.
- (2) Operate each indoor unit one by one and make sure the corresponding outdoor unit is also operating.
- (3) Check to see if cold (or hot) air is coming out from the indoor unit.
- (4) Push the fan direction and strength buttons on the remote controller to see if they operate properly.

NOTE:

- Heating is not possible if the outdoor temperature is 24°C or higher. Refer to the Operation manual.
- If a knocking sound can be heard in the liquid compression of the compressor, stop the unit immediately and then energize the crank case heater for a sufficient length of time before restarting the operation.
- Once stopping, the compressor will not restart in about 5 minutes even if the On/Off button of the remote controller is pushed.
- When the system operation is stopped by the remote controller, the outdoor units may continue operating for further 5 minutes at maximum.
- The outdoor unit fan may rotate at low speeds if the Night-time low noise setting or the External low noise level setting is made, but this is not a malfunction.

1.2.6.3 Checks after Test Run

Perform the following checks after the test run is complete.

- · Record the contents of field setting.
 - →Record them on the accessory "REQUEST FOR THE INDICATION" label. And attach the label on the back side of the front panel.
- Record the installation date.
 - \rightarrow Record the installation date on the accessory "REQUEST FOR THE INDICATION" label in accordance with the IEC60335-2-40.
 - And attach the label on the back side of the front panel.

NOTE:

After the test run, when handing the unit over to the customer, make sure the EL.COMPO.BOX lid, the inspection door, and the unit casing are all attached.

Si34-601A Test Operation

Operation When Power is Turned On 1.3

1.3.1 When Turning On Power First Time

The unit cannot be run for up to 12 minutes to automatically set the master power and address (indoor-outdoor address, etc.).

Status

Outdoor unit

Test lamp H2P Blinks

Can also be set during operation described above.

Indoor unit

If ON button is pushed during operation described above, the "UH"

malfunction indicator blinks. (Returns to normal when automatic setting is complete.)

1.3.2 When Turning On Power The Second Time and Subsequent

Tap the RESET button on the outdoor unit PC board. Operation becomes possible for about 2 minutes. If you do not push the RESET button, the unit cannot be run for up to 10 minutes to automatically set master power.

Status

Outdoor unit

Test lamp H2P Blinks

Can also be set during operation described above.

Indoor unit

If ON button is pushed during operation described above, the operation lamp lights but the compressor does not operate. (Returns to normal when automatic setting is complete.)

1.3.3 When an Indoor Unit or Outdoor unit Has Been Added, or Indoor or **Outdoor Unit PC Board Has Been Changed**

Be sure to push and hold the RESET button for 5 seconds. If not, the addition cannot be recognized. In this case, the unit cannot be run for up to 12 minutes to automatically set the address (indoor-outdoor address, etc.)

Status


Outdoor unit

Test lamp H2P ON

Can also be set during operation described above.

Indoor unit

If ON button is pushed during operation described above, the "UH" or "U4" malfunction indicator blinks. (Returns to normal when automatic setting is complete.)




Caution When the 400 volt power supply is applyed to "N" phase by mistake, replace Inverter P.C.B (A2P) and control transformer (T1R, T2R) in switch box together.

(V0847)

2. Outdoor Unit PC Board Layout

Outdoor unit PC board



(V3054)

- (1) Microcomputer normal monitor

 This monitor blinks while in normal operation, and turns on or off when a malfunction occurs.
- (2) Set mode display (LED) LEDs display mode according to the setting.
- (3) Mode setting switch Used to change mode.
- (4) Local setting switch Used to make field settings.

Si34-601A Field Setting

3. Field Setting


Field Setting from Remote Controller 3.1

Individual function of indoor unit can be changed from the remote controller. At the time of installation or after service inspection / repair, make the local setting in accordance with the following description.

Wrong setting may cause malfunction.

(When optional accessory is mounted on the indoor unit, setting for the indoor unit may be required to change. Refer to information in the option handbook.)

3.1.1 Wired Remote Controller <BRC1C61, 62>



- 1. When in the normal mode, press the " with the normal mode, press the normal mode, press the normal mode, press the " with the normal mode, press the normal FIELD SET MODE is entered.
- 2. Select the desired MODE NO. with the " 🐧 " button (2).
- 3. During group control, when setting by each indoor unit (mode No. 20, 22 and 23 have been selected), push the " $\frac{0}{0}$ " button (3) and select the INDOOR UNIT NO to be set. (This operation is unnecessary when setting by group.)
- 4. Push the " and select FIRST CODE NO.
- 6. Push the " button (6) once and the present settings are SET.
 7. Push the " button (7) to return to the NORMAL MODE.


(Example)

If during group setting and the time to clean air filter is set to FILTER CONTAMINATION, HEAVY, SET MODE NO. to "10" FIRST CODE NO. to "0", and SECOND CODE NO. to "02".

Field Setting Si34-601A

3.1.2 Wireless Remote Controller - Indoor Unit

BRC7C type **BRC7E** type **BRC4C** type



1. When in the normal mode, push the " button for 4 seconds or more, and operation then enters the "field set mode."

- 2. Select the desired "mode No." with the " button.
- 3. Pushing the " \bigcirc " button, select the first $\overline{\text{code}}$ No.
- 4. Pushing the " button, select the second code No.
 5. Push the timer " button and check the settings.
- 6. Push the " button to return to the normal mode.


(Example)

When setting the filter sign time to "Filter Dirtiness-High" in all group unit setting, set the Mode No. to "10", Mode setting No. to "0" and setting position No. to "02".

Si34-601A Field Setting

3.1.3 Simplified Remote Controller

BRC2A51 BRC2C51



- 1. Remove the upper part of remote controller.
- 2. When in the normal mode, press the [BS6] BUTTON (2) (field set), and the FIELD SET MODE is entered.
- 3. Select the desired MODE No. with the [BS2] BUTTON (③) (temperature setting ▲) and the [BS3] BUTTON (③) (temperature setting ▼).
- 4. During group control, when setting by each indoor unit (mode No. 20, 22, and 23 have been selected), push the [BS8] (4) BUTTON (unit No.) and select the INDOOR UNIT NO. to be set. (This operation is unnecessary when setting by group.)
- 5. Push the [BS9] BUTTON (5) (set A) and select FIRST CODE NO.
- 6. Push the [BS10] BUTTON (6) (set B) and select SECOND CODE NO.
- 7. Push the [BS7] BUTTON (7) (set/cancel) once and the present settings are SET.
- 8. Push the [BS6] BUTTON (8) (field set) to return to the NORMAL MODE.
- 9. (Example) If during group setting and the time to clean air filter is set to FILTER CONTAMINATION HEAVY, SET MODE NO. to "10", FIRST CODE NO. to "0", and SECOND CODE NO. to "02".

Field Setting Si34-601A

3.1.4 Setting Contents and Code No. – VRV Indoor unit

VRV	Mode	Setting	Setting Contents				Sec	cond Code	e No.(Not	e 3)								
system	No. Note 2	Switch No.			C	1	0)2	C)3	()4						
unit settings	tings 10(20) 0 Filte ligh time		Filter contamination heavy/ light (Setting for display time to clean air filter) (Sets display time to clean	Super long life filter	Light	Approx. 10,000 hrs.	Heavy	Approx. 5,000 hrs.	_	_	-	_						
			àir filter to half when there is heavy filter contamination.)	Long life filter		Approx. 2,500 hrs.		Approx. 1,250 hrs.										
				Standard filter		Approx. 200 hrs.		Approx. 100 hrs.										
		1	Long life filter type		Long li	fe filter		long life ter	-	_	-	_						
		2	Thermostat sensor in remote	controller	U	se	No	use	_	_								
		3	Display time to clean air filter calculation (Set when filter si to be displayed.)	gn is not	Dis	play	No di	isplay	_	_								
	12(22)	0	Optional accessories output (field selection of output for a wiring)		turned	or unit ON by nostat			Operation	onoutput		inction tput						
		1	ON/OFF input from outside (ON/OFF is to be controlled froutside.)	rom	Force	d OFF	ON/OF	= control	External protection device input		protection device		protection device		protection device		-	
		2	Thermostat differential chang (Set when remote sensor is tused.)	geover o be	1'	°C	0.5°C		_									
		3	OFF by thermostat fan speed	b	L	L	Set fan speed		<u> </u>		-							
		4	Automatic mode differential (temperature differential settir system heat recovery series	g for VRV	01:0	02:1	03:2	04:3	05:4	06:5	07:6	08:7						
		5	Power failure automatic rese	t	Not eq	uipped	Equipped		_	_	-							
	13(23)	0	High air outlet velocity (Set when installed in place whigher than 2.7 m.)	vith ceiling	1	7	Н		,	S	-	_						
		1	Selection of air flow direction (Set when a blocking pad kit installed.)		F (4 dir	ections)	T (3 directions)		W (2 directions)		-	_						
		3	Air flow direction adjustment installation of decoration pan		Equi	pped	Not eq	uipped			_							
		4	Field set air flow position set	ting	Draft pr	evention	Stan	ndard	Ceiling Soiling prevention		_							
		5	Field set fan speed selection (fan speed control by air discharge outlet for phase control)		Star	dard	Optional accessory 1		Optional accessory 2		-	_						
	15(25)	1	Thermostat OFF excess humidity		Not eq	uipped	Equi	pped	_	_	-	_						
		2	Direct duct connection (when the indoor unit and he ventilation unit are connected directly.) *Note 6	d by duct	Not eq	uipped	Equi	pped	_	_	-	_						
		3	Drain pump humidifier interloselection	ck	Not eq	uipped	Equi	pped	-	_	-	_						
		5	Field set selection for individuentilation setting by remote	controller		uipped	Equi	pped	_	_	-	_						
		6	Field set selection for individuentilation setting by remote	ual controller	Not eq	uipped	Equi	pped	_	_	-	_						



- Settings are made simultaneously for the entire group, however, if you select the mode No.
 inside parentheses, you can also set by each individual unit. Setting changes however
 cannot be checked except in the individual mode for those in parentheses.
- 2. The mode numbers inside parentheses cannot be used by wireless remote controllers, so they cannot be set individually. Setting changes also cannot be checked.
- 3. Marked are factory set.
- 4. Do not make settings other than those described above. Nothing is displayed for functions the indoor unit is not equipped with.
- 5. "88" may be displayed to indicate the remote controller is resetting when returning to the normal mode.
- 6. If the setting mode to "Equipped", heat reclaim ventilation fan conducts the fan residual operation by linking to indoor unit.

Si34-601A Field Setting

3.1.5 Applicable range of Field setting

	Ceiling n	nounted o	cassette t	уре	Slim	Ceiling	Ceiling	Ceiling	Wall	Floor	Concealed		Outdoor
			Double flow	e Corner mounted		mounted built-in type	mounted duct type	suspended type	mounted type	standing type	Floor standing type	Ceiling suspende d cassette type	air processing unit
	FXFQ	FXZQ	FXCQ	FXKQ	FXDQ	FXSQ	FXMQ	FXHQ	FXAQ	FXLQ	FXNQ	FXUQ	FXMQ- MF
Filter sign	0	0	0	0	0	0	0	0	0	0	0	0	0
Ultra long life filter sign	0	0	0	_	_	_	_	_	_	_	_	_	_
Remote controller thermostat sensor	0	0	0	0	0	0	0	0	0	0	0	0	_
Set fan speed when thermostat OFF	0	0	0	0	0	0	0	0	0	0	0	0	_
Air flow adjustment Ceiling height	0	_	_	_	_	_	_	0	_	_	_	0	_
Air flow direction	0	0	_	_	_	_	_	_	_	_	_	0	_
Air flow direction adjustment (Down flow operation)	_		_	0	_	_	_	_	_		_	_	_
Air flow direction adjustment range	0	0	0	0	_	_	_	_	_	_	_	_	_
Field set fan speed selection	0	_	_	_	O*1	_	_	0	_	_	_	_	_
Discharge air temp. (Cooling)	_	_	_	_	_	_	_	_	_	_	_	_	0
Discharge air temp. (Heating)	_	_		_	_	_	_	_	_		_	_	0

^{*1} Static pressure selection

Field Setting Si34-601A

3.1.6 Detailed Explanation of Setting Modes

Filter Sign Setting

If switching the filter sign ON time, set as given in the table below.

Set Time

Filter Specs. Setting	Standard	Long Life	Ultra Long Life Filter
Contamination Light	200 hrs.	2,500 hrs.	10,000 hrs.
Contamination Heavy	100 hrs.	1,250 hrs.	5,000 hrs.

Ultra-Long-Life Filter Sign Setting


When a Ultra-long-life filter is installed, the filter sign timer setting must be changed.

Setting Table

Mode No.	Setting Switch No.	Setting Position No.	Setting
		01	Long-Life Filter
10 (20)	1	02	Ultra-Long-Life Filter (1)
		03	_

External ON/OFF input

This input is used for "ON / OFF operation" and "Protection device input" from the outside. The input is performed from the T1-T1 terminal of the operation terminal block (X1A) in the electric component box.



Setting Table

Mode No.	Setting Switch No.	Setting Position No.	Operation by input of the signal A
		01	ON: Forced stop (prohibition of using the remote controller) OFF: Permission of using the remote controller
12 (22)	1	02	
		03	ON: Operation OFF: The system stops, then the applicable unit indicates "A0". The other indoor units indicate "U9".

Fan Speed Changeover When Thermostat is OFF

By setting to "Set Fan Speed," you can switch the fan speed to the set fan speed when the heating thermostat is OFF.

* Since there is concern about draft if using "fan speed up when thermostat is OFF," you should take the setup location into consideration.

Setting Table

Mode No.	First Code No.	Second Code No.	Setting
12(22)	2	01	LL Fan Speed
12(22)	3	02	Set Fan Speed

Si34-601A Field Setting

Auto Restart after Power Failure Reset

For the air conditioners with no setting for the function (same as factory setting), the units will be left in the stop condition when the power supply is reset automatically after power failure reset or the main power supply is turned on again after once turned off. However, for the air conditioners with the setting, the units may start automatically after power failure reset or the main power supply turned on again (return to the same operation condition as that of before power failure).

For the above reasons, when the unit is set enabling to utilize "Auto restart function after power failure reset", utmost care should be paid for the occurrence of the following situation.



- / Caution 1. The air conditioner starts operation suddenly after power failure reset or the main power supply turned on again. Consequently, the user might be surprised (with question for the reason why).
 - 2. In the service work, for example, turning off the main power switch during the unit is in operation, and turning on the switch again after the work is completed start the unit operation (the fan rotates).

Air Flow Adjustment - Ceiling height

Make the following setting according to the ceiling height. The setting position No. is set to "01" at the factory.

■ In the Case of FXAQ, FXHQ

Mode No.	Setting Switch No.	Setting Position No.	Setting
		01	Wall-mounted type: Standard
13(23)	0	02	Wall-mounted type: Slight increase
		03	Wall-mounted type: Normal increase

■ In the Case of FXFQ25~80

Mode	First	Second			Ceiling height	
No.	code No.	code No.	Setting	4-way Outlets	3-way Outlets	2-way Outlets
		01	Standard (N)	Lower than 2.7 m	Lower than 3.0 m	Lower than 3.5 m
13 (23)	0	02	High Ceiling (H)	Lower than 3.0 m	Lower than 3.3 m	Lower than 3.8 m
		03	Higher Ceiling (S)	Lower than 3.5 m	Lower than 3.5 m	_

■ In the Case of FXFQ100~125

Mode	First Second		o		Ceiling height	
No.	code No.	code No.	Setting	4-way Outlets	3-way Outlets	2-way Outlets
		01	Standard (N)	Lower than 3.2 m	Lower than 3.6 m	Lower than 4.2 m
13 (23)	0	02	High Ceiling (H)	Lower than 3.6 m	Lower than 4.0 m	Lower than 4.2 m
		03	Higher Ceiling (S)	Lower than 4.2 m	Lower than 4.2 m	_

■ In the Case of FXUQ71~125

Mode No.	First	Second code No.		Ceiling height							
	code No.		Setting	4-way Outlets	3-way Outlets	2-way Outlets					
13 (23)	0	01	Standard (N)	Lower than 2.7 m	Lower than 3.0 m	Lower than 3.5 m					
		02	High Ceiling (H)	Lower than 3.0 m	Lower than 3.5 m	Lower than 3.8 m					
		03	Higher Ceiling (S)	Lower than 3.5 m	Lower than 3.8 m						

Field Setting Si34-601A

Air Flow Direction Setting

Set the air flow direction of indoor units as given in the table below. (Set when optional air outlet blocking pad has been installed.) The second code No. is factory set to "01."

Setting Table

Mode No. First Code No.		Second Code No.	Setting				
		01	F: 4-direction air flow				
13 (23)	1	02	T: 3-direction air flow				
		03	W: 2-direction air flow				

Setting of Air Flow Direction Adjustment

Only the model FXKQ has the function.


When only the front-flow is used, sets yes/no of the swing flap operation of down-flow.

Setting Table

Setting	Mode No.	First Code No.	Second Code No.			
Down-flow operation: Yes	13 (23)	2	01			
Down-flow operation: No	13 (23)	3	02			

Setting of Air Flow Direction Adjustment Range

Make the following air flow direction setting according to the respective purpose.



Setting Table

Mode No.	First Code No.	Second Code No.	Setting		
		01	Upward (Draft prevention)		
13 (23)	4	02	Standard		
		03	Downward (Ceiling soiling prevention)		

Air flow rate switching at discharge grille for field air flow rate switching

When the optional parts (high performance filter, etc.) is installed, sets to change fan speed for securing air flow rate.

Follow the instruction manual for the optional parts to enter the setting numbers.

Setting of the static pressure selection (for FXDQ model)

Model No.	First Code No.	Second Code No.	External static pressure
13 (23)	5	01	Standard (15Pa)
13 (23)	5	02	High static pressure (44Pa)

Si34-601A Field Setting

3.1.7 Outdoor Air Processing Unit-Field Setting (Remote Controller)

Mode	Setting	Setting	Setting position No.														
No.	SW No.		01	02	03	04	05	06	07	80	09	10	11	12	13	14	15
10 (20)	0	Stain of filter	2500hr	1250hr	_	_	_	_	_	_	_	_	_	_	_	_	_
	3	Filtering time cumulation	Display	No display	_	_	_	_	_	_	_	_	_	_	_	_	_
12 (22)	1	External ON/OFF input	Forced stop	ON-OFF control	_	_	_	_	_	_	_	_	_	_	_	_	_
	5	Power failure automatic reset	Not equipped	Equipped	_	_	_	_	_	_	_	_	_	_	_	_	_
14 (24)	3	Discharge temperature (cooling)	13°C	14	15	16	17	18	19	20	21	22	23	24	25	25	25
	4	Discharge temperature (heating)	18°C	19	20	21	22	23	24	25	26	27	28	29	30	30	30

Note) Bold face in indicates the default setting.


3.1.8 Centralized Control Group No. Setting

BRC1A Type

In order to conduct the central remote control using the central remote controller and the unified ON/OFF controller, Group No. settings should be made by group using the operating remote controller.

Make Group No. settings for central remote control using the operating remote controller.

- 1. While in normal mode, press and hold the with more to set the system to "Field Setting Mode"." switch for a period of four seconds or more to set the system to "Field Setting Mode"."
- 3. Use the " just button to select the group No. for each group. (Group numbers increase in the order of 1-00, 1-01, ... 1-15, 2-00, ... 4-15.)
- 4. Press " $\stackrel{\square}{\underline{\hspace{1.5cm}}}$ " to set the selected group No.
- 5. Press " $\frac{1}{|\mathbf{x}|}$ " to return to the NORMAL MODE.



Note:


- For wireless remote controller, see the following.
- For setting group No. of HRV and wiring adaptor for other air conditioners, etc., refer to the instruction manual attached.

NOTICE


Enter the group No. and installation place of the indoor unit into the attached installation table. Be sure to keep the installation table with the operation manual for maintenance.

BRC7C Type BRC7E Type BRC4C Type

- Group No. setting by wireless remote controller for centralized control
- 1. When in the normal mode, push " button for 4 seconds or more, and operation then enters the "field set mode."
- 2. Set mode No. "00" with " $\stackrel{\text{\tiny MODE}}{\longleftarrow}$ " button.
- 3. Set the group No. for each group with " $\stackrel{\frown}{Q}$ " " $\stackrel{\frown}{\mathbb{Q}}$ " button (advance/backward).
- 4. Enter the selected group numbers by pushing " $\stackrel{\text{\tiny RESENVE}}{\bigcirc}$ " button.
- 5. Push " button and return to the normal mode.



Group No. Setting Example



Caution

When turning the power supply on, the unit may often not accept any operation while "88" is displaying after all indications were displayed once for about 1 minute on the liquid crystal display. This is not an operative fault.

3.1.9 Setting of Operation Control Mode from Remote Controller (Local Setting)

The operation control mode is compatible with a variety of controls and operations by limiting the functions of the operation remote controller. Furthermore, operations such as remote controller ON/OFF can be limited in accordance with the combination conditions. (Refer to information in the next page.)

Central remote controller is normally available for operations. (Except when centralized monitor is connected)


3.1.10 Contents of Control Modes

Twenty modes consisting of combinations of the following five operation modes with temperature and operation mode setting by remote controller can be set and displayed by operation modes 0 through 19.

- ◆ ON/OFF control impossible by remote controller Used when you want to turn on/off by central remote controller only. (Cannot be turned on/off by remote controller.)
- OFF control only possible by remote controller
 Used when you want to turn on by central remote controller only, and off by remote controller only.
- Centralized
 Used when you want to turn on by central remote controller only, and turn on/off freely by remote controller during set time.
- ◆ Individual Used when you want to turn on/off by both central remote controller and remote controller.
- ◆ Timer operation possible by remote controller Used when you want to turn on/off by remote controller during set time and you do not want to start operation by central remote controller when time of system start is programmed.

How to Select Operation Mode


Whether operation by remote controller will be possible or not for turning on/off, controlling temperature or setting operation mode is selected and decided by the operation mode given on the right edge of the table below.



		Control by ren	note controller			
	Ope	ration				
Control mode	Unified operation, individual operation by central remote controller, or operation controlled by timer	Unified OFF, individual stop by central remote controller, or timer stop	OFF	Temperature control	Operation mode setting	Control mode
				Dejection	Acceptance	0
ON/OFF control			Daiastian	Rejection	Rejection	10
impossible by remote controller			Rejection (Example)	Acceptance (Example)	Acceptance (Example)	1(Example)
	Rejection (Example)			(⊏xample)	Rejection	11
				Dojoction	Acceptance	2
OFF control only possible by		Rejection (Example)		Rejection	Rejection	12
remote controller				Accontance	Acceptance	3
				Acceptance	Rejection	13
				Dojoction	Acceptance	4
Centralized				Rejection	Rejection	14
Centralized				Acceptones	Acceptance	5
	Aggertance		Acceptones	Acceptance	Rejection	15
	Acceptance		Acceptance	Dejection	Acceptance	6
Individual		Aggartance		Rejection	Rejection	16
individual		Acceptance		Acceptones	Acceptance	7 *1
				Acceptance	Rejection	17
				Poinction	Acceptance	8
Timer operation	Acceptance	Acceptance		Rejection	Rejection	18
possible by remote controller	(During timer at ON position only)	(During timer at ON position only)		Acceptones	Acceptance	9
				Acceptance	Rejection	19

Do not select "timer operation possible by remote controller" if not using a remote controller. Operation by timer is impossible in this case.

*1. Factory setting



3.2 Field Setting from Outdoor Unit

3.2.1 Field Setting from Outdoor Unit

■ List of Field Setting Items

This following section indicates the list of field setting items. For the lists of dip switch contents, Setting mode 1, and Setting mode 2, refer to information in tables shown on the following page onward.

For setting items of (*1), refer to detailed information provided on page 161 onward.

	Se	etting item	Content and objective of setting	Overview of setting procedure
	1	Setting of COOL/ HEAT selection (*1)	■ COOL/HEAT selection methods are possible to select from the following (1) Control by each outdoor unit using the indoor unit remote controller (2) Control by each outdoor unit using the COOL/HEAT selection remote controller (3) Batch control by outdoor unit group using the indoor unit remote controller (4) Batch control by outdoor unit group using the COOL/HEAT selection remote controller	 In order to use the COOL/HEAT selection remote controller, set the DS1-1 on the outdoor unit PC board to OUT. For outdoor unit group control, set the system to "BATCH MASTER" or "SLAVE" while in "Setting mode 1". Then, make setting of COOL/HEAT batch address.
	2	Setting of low noise operation (*1)	A. Use external input to step down the upper limit of the fan (factory set to Step 8), providing low noise level. (1) Mode 1: Step 6 or lower (2) Mode 2: Step 5 or lower (3) Mode 3: Step 4 or lower	■ Use the "External control adaptor for outdoor unit". Set to "External control adaptor for outdoor unit" with No. 12 of "Setting mode 2" and select the mode with No. 25. If necessary, set the "Capacity priority setting" to ON with No. 29.
Function setting			B. The low noise operation aforementioned is enabled in nighttime automatic low noise operation mode. Start time: Possible to select in the range of 20:00 to 24:00 hours. End time: Possible to select in the range of 06:00 to 08:00 hours. (Use the said time as a guide since the start time and the end time are estimated according to outdoor temperatures.)	■ Make this setting while in "Setting mode 2". Select a mode with No. 22 of "Setting mode 2". Select the start time with No. 26 and the end time with No. 27. If necessary, set the "Capacity priority setting" to ON with No. 29.
	3	Setting of demand operation (*1)	■ Used to place limits on the compressor operating frequency to control the upper limit of power consumption. (1) Mode 1 of Demand 1: 60% or less of rating (2) Mode 2 of Demand 1: 70% or less of rating (3) Mode 3 of Demand 1: 80% or less of rating (4) Demand 2: 40% or less of rating	 For setting with the use of "external control adapter": Set the system to "External control adaptor for outdoor unit" with No. 12 of Setting mode 2" and select the mode with No. 30. For setting only in "Setting mode 2": Set the system to Normal demand mode with No. 32 of "Setting mode 2" and select the mode with No. 30.
	4	Setting of AirNet address	■ Used to make address setting with AirNet connected.	■ Set the AirNet to an intended address using binary numbers with No. 13 of "Setting mode 2".
	5	Setting of hot water heater	Make this setting to conduct heating operation using the hot water heater.	■ Set No. 16 of "Setting mode 2" to ON.
	6	Setting of high static pressure	 Make this setting to operate a system with diffuser duct while in high static pressure mode. (Use this setting mode when shields are installed on upper floors or balconies.) In order to mount the diffuser duct, remove the cover from the outdoor unit fan. 	■ Set No. 18 of "Setting mode 2" to ON.

Se	etting item	Content and objective of setting	Overview of setting procedure
1	Indoor unit fan forced H operation	Used to operate the indoor unit in the stopped state in forced H operation mode.	Set No. 5 of "Setting mode 2" to indoor unit forced fan H.
2	Indoor unit forced operation	Used to operate the indoor unit in forced operation mode.	■ Set No. 6 of "Setting mode 2" to indoor unit forced operation mode.
3	Change of targeted evaporating temperature (in cooling)	In cooling operation, used to change the targeted evaporating temperature for compressor capacity control.	■ Select high side or low side with No. 8 of "Setting mode 2".
4	Change of targeted condensing temperature (in heating)	In heating operation, used to change the targeted condensing temperature for compressor capacity control.	■ Select high side or low side with No. 9 of "Setting mode 2".
5	Setting of defrost selection	Used to change a temperature at which the defrost operation is initiated, thus making the initiation easy or hard.	Select fast side or slow side with No. 10 of "Setting mode 2".
6	Setting of sequential startup	Used to start units not in sequence but simultaneously.	■ Set No. 11 of "Setting mode 2" to NONE.
7	Emergency operation (*1)	■ If the compressor has a failure, used to prohibit the operation of compressor(s) concerned or outdoor unit(s) concerned and to conduct emergency operation of the system only with operable compressor(s) or outdoor unit(s).	■ Make this setting while in "Setting mode 2". For system with a single outdoor unit: Set with No. 19 or 42. For system with multiple outdoor units: Set with No. 38, 39, or 40.
8	Additional refrigerant charging (*1)	If a necessary amount of refrigerant cannot be charged due to the stop of outdoor unit, operate the outdoor unit and then refill refrigerant.	Set No. 20 of "Setting mode 2" to ON and then charge refrigerant.
9	Refrigerant recovery mode (*1)	■ Used to recover refrigerant on site. With operations of indoor and outdoor units prohibited, fully open the expansion valve of the indoor and outdoor units.	■ Set No. 21 of "Setting mode 2" to ON.
10	Vacuuming mode (*1)	■ Used to conduct vacuuming on site. Fully open the expansion valves of the indoor and outdoor units, and energize part of solenoid valves. Use a vacuum pump to conduct vacuuming.	■ Set No. 21 of "Setting mode 2" to ON.
11	ENECUT test operation	Used to forcedly turn ON the ENECUT. (Be noted this mode is not functional with the indoor unit remote controller turned ON.)	■ Set No. 24 of "Setting mode 2" to ON.
12	Power transistor check mode	Used for the troubleshooting of DC compressors. Inverter waveform output makes it possible to judge whether a malfunction results from the compressor or the PC board.	■ Set No. 28 of "Setting mode 2" to ON.
13	Setting of model with spare PC board	■ In order to replace the PC board by a spare one, be sure to make model setting.	■ For this setting, set the DS2-2, -3, and-4 switches on the PC board to the model concerned.
	1 2 3 4 5 6 7 8 9 10 11 12	1 forced H operation 2 Indoor unit forced operation Change of targeted evaporating temperature (in cooling) Change of targeted condensing temperature (in heating) 5 Setting of defrost selection 6 Setting of sequential startup 7 Emergency operation (*1) 8 Additional refrigerant charging (*1) 9 Refrigerant recovery mode (*1) 10 Vacuuming mode (*1) 11 ENECUT test operation 12 Power transistor check mode 13 Setting of model with spare PC	Indoor unit fan forced H operation Indoor unit forced with operation between the stopped state in forced H operation mode. Indoor unit forced operation with operation mode. Indoor unit forced operation mode. Indoor unit forced operation mode. In cooling operation, used to change the targeted evaporating temperature (in cooling) Change of targeted condensing temperature for compressor capacity control. In heating operation, used to change the targeted evaporating temperature for compressor capacity control. In heating operation, used to change the targeted condensing temperature for compressor capacity control. In heating operation, used to change the targeted condensing temperature for compressor capacity control. In heating operation is initiated, thus making the initiation easy or hard. If the compressor has a failure, used to prohibit the operation of compressor(s) concerned or outdoor unit(s) concerned and to conduct emergency operation of the system only with operable compressor(s) or outdoor unit(s). Additional refrigerant cannot be charged due to the stop of outdoor unit, operate the outdoor unit and then refill refrigerant. If a necessary amount of refrigerant cannot be charged due to the stop of outdoor unit, operate the outdoor unit and then refill refrigerant. Used to recover refrigerant on site. With operations of indoor and outdoor units. Used to conduct vacuuming on site. Fully open the expansion valves of the indoor and outdoor units, and energize part of solenoid valves. Use a vacuum pump to conduct vacuuming. Used to forcedly turn ON the ENECUT. (Be noted this mode is not functional with the indoor unit remote controller turned ON.) Used for the troubleshooting of DC compressors. Inverter waveform output makes it possible to judge whether a malfunction results from the complex service of the PC board. In order to replace the PC board by a spare on the part of the product o

For setting items of (*1), refer to detailed information provided on page 174 onward.

■ Setting by dip switches

Using dip switches on the PC board enables field setting shown below. However, make no changes of factory settings except for DS1-1.

	Dipswitch	Setting item	Description						
No.	Setting	Setting item	Description						
DC1 1	ON	Cool / Hook colook	Used to set cool / heat select by Cool/Heat select						
DS1-1	OFF (Factory set)	Cool / Heat select	equipped with outdoor unit.						
DS1-2	ON	Neturnal	Do not also no the feeton, actions						
~DS1-4	OFF (Factory set)	Not used	Do not change the factory settings.						
DS2-1	ON	Notuced	Do not change the factory cottings						
~4	OFF (Factory set)	Not used	Do not change the factory settings.						



Setting at replacement by spare PC board

DIP switch Setting after changing the main P.C.Board(A1P) to spare parts P.C.B.

After the replacement by the spare PC board, be sure to make settings shown below. When you change the main P.C.Board(A1P) to spare parts P.C.B., please carry out the following setting.

Initial conditions of dip switches





DIP Switch Detail

DS No.	Item				С	onte	nts			
DS1-1	Cool/Heat change over setting	ON	C	COOL/HEA Cool/Heat	AT s sele	ettin ctor	g is mad mounted	le with the	ne use of outdoor (fa unit.
		OFF (Factory setting of spare PC board)	C	COOL/HEA Cool/Heat	AT s sele	ettin ctor	g is not i mounted	made wi d to the d	th the us outdoor (e of a unit.
DS1-2	Power supply	ON	2	00V class	(22	(V0				
	specification	OFF (Factory setting of spare PC board)	4	400V class (380V)						
DS1-3	Cooling only/Heat-	ON	С	cooling on	ly se	etting	9			
	pump setting	OFF (Factory setting of spare PC board)	Heat pump setting							
DS1-4	Unit allocation setting	ON		Make the fo nit. (All m						cation of
DS2-1			-			Domestic Japan		Oversea Genera	~ I F	urope
502 .		OFF (Factory		DS1-4		C)FF	OFF		ON
		setting of spare PC board)		DS2-1		OFF		ON		OFF
DS2-2	Model setting	Make the follo (All models a	ow re	ring settin set to OF	gs a	acco t fac	rding to tory.)	models	of outdo	or units.
DS2-3		RXY				Q10P	RXYQ12P	RXYQ14P	RXYQ16P	RXYQ18P
		DS2-2 OF		OFF ON	_	N N	OFF OFF	ON OFF	OFF ON	ON ON
DS2-4		DS2-4 OF		OFF	_	FF	OFF	OFF	ON	ON
	01.1.1.1.000.0.0		- 1					I - «I I A		

^{*} If the DS1-1~1-4, DS2-2~2-4 setting has not been carried out, error code "UA" are displayed and unit can not be operated.



Refer "DS1-1~4, DS2-1~4 setting detail" on next page.

"Detail of DS1-1~4, DS2-1~4 setting" (for Overseas general)

Unit	Setting method (■ repr	resents the position of switches)
HEAT PUMP(5HP) RXYQ5PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1 to ON.
HEAT PUMP(8HP) RXYQ8PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1 and DS2-3 to ON.
HEAT PUMP(10HP) RXYQ10PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1, DS2-2 and DS2-3 to ON.
HEAT PUMP(12HP) RXYQ12PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1 and DS2-4 to ON.
HEAT PUMP(14HP) RXYQ14PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1, DS2-2 and DS2-4 to ON.
HEAT PUMP(16HP) RXYQ16PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1, DS2-3 and DS2-4 to ON.
HEAT PUMP(18HP) RXYQ18PY1	ON OFF 1 2 3 4 1 2 3 4	Set DS2-1, DS2-2, DS2-3, and DS2-4 to ON.

Setting by pushbutton switches

The following settings are made by pushbutton switches on PC board.


In case of multi-outdoor unit system, various items should be set with the master unit. (Setting with the slave unit is disabled.)

The master unit and slave unit can be discriminated with the LED display as shown below.

LED display

		MODE	TEST	CO	OL/HEAT se	Low	Demand	Multi;	
		H1P	H2P	IND H3P	MASTER H4P	SLAVE H5P	noise H6P	H7P	H8P
Single-outdoor-unit system		•	•	0	•	•	•	•	•
Outdoor-	Master	•	•	0	•	•	•	•	0
multi	Slave 1	•	•	•	•	•	•	•	•
system	Slave 2	•	•	•	•	•	•	•	•

(Factory setting)



There are the following three setting modes.

① Setting mode 1 (HTP off)

Initial status (when normal): Used to select the cool/heat setting. Also indicates during "abnormal", "low noise control" and "demand control".


2 Setting mode 2 (H1P on)

Used to modify the operating status and to set program addresses, etc. Usually used in servicing the system.


3 Monitor mode (H1P blinks)

Used to check the program made in Setting mode 2.

■ Mode changing procedure 1



■ Mode changing procedure 2




a. "Setting mode 1"


This mode is used to set and check the following items.

- 1. Set items In order to make COOL/HEAT selection in a batch of outdoor unit group, change the setting.
 - COOL/HEAT selection (IND)Used to select COOL or HEAT by individual outdoor unit (factory set).
 - COOL/HEAT selection (MASTER)Used to select COOL or HEAT by outdoor unit group with the master unit.
 - COOL/HEAT selection (SLAVE)......Used to select COOL or HEAT by outdoor unit group with the slave unit.
- 2. Check items The following items can be checked.
 - (1) Current operating conditions (Normal / Abnormal / In check operation)
 - (2) Setting conditions of COOL/HEAT selection (Individual / Batch master / Batch slave)
 - (3) Low noise operating conditions (In normal operation / In low noise operation)
 - (4) Demand operating conditions (In normal operation / In demand operation)

Procedure for changing COOL/HEAT selection setting



Procedure for checking check items



b. "Setting mode 2"

Push and hold the MODE (BS1) button for 5 seconds and set to "Setting mode 2".

<Selection of setting items>

Push the SET (BS2) button and set the LED display to a setting item shown in the table on the right.

Push the RETURN (BS3) button and decide the item. (The present setting condition is blinked.)

<Selection of setting conditions>

Push the SET (BS2) button and set to the setting condition you want.

Push the RETURN (BS3) button and decide the condition.

Push the RETURN (BS3) button and set to the initial status of "Setting mode 2".

* If you become unsure of how to proceed, push the MODE (BS1) button and return to setting mode 1.

(V2764)

No.	Setting item	Description
110.	, and the second	Used to make setting of contents to display on the digital
0	Degital pressure gauge kit display	pressure gauges (e.g. pressure sensors and temperature sensors)
1	Cool/heat unified address	Sets address for cool/heat unified operation.
2	Low noise/demand address	Address for low noise/demand operation
3	Test operation settings	Used to conduct test operation without making changes to the PCB and replacing the refrigerant, after the completion of maintenance.
5	Indoor unit forced fan H	Allows forced operation of indoor unit fan while unit is stopped. (H tap)
6	Indoor unit forced operation	Allows forced operation of indoor unit.
8	Te setting	Target evaporation temperature for cooling
9	Tc setting	Target condensation temperature for heating
10	Defrost changeover setting	Changes the temperature condition for defrost and sets to quick defrost or slow defrost.
11	Sequential operation setting	Sets sequential operation (Factory set to ON)
12	External low noise setting / Demand setting	Reception of external low noise or demand signal
13	AIRNET address	Set address for AIRNET.
16	Setting of hot water	Make this setting to conduct heating operation with hot water heater.
18	High static pressure setting	Make this setting in the case of operating in high static pressure mode with diffuser duct mounted. (In order to mount the diffuser duct, remove the cover from the outdoor unit fan.)
19	Emergency operation (STD compressor operation prohibited)	Used to operate system only with inverter compressor when STD compressor malfunctions. This is a temporary operation extremely impairing comfortable environment. Therefore, prompt replacement of the compressor is required. (This operation, however, is not set with RXYQ5, 8P.)
20	Additional refrigerant charge operation setting	Carries out additional refrigerant charge operation.
21	Refrigerant recovery/ vacuuming mode setting	Sets to refrigerant recovery or vacuuming mode.
22	Night-time low noise setting	Sets automatic nighttime low noise operation in a simple way. The operating time is based on "Starting set" and "Ending set".
24	ENECUT test operation	Used to forcedly turn ON the ENECUT. (Be noted that the ENECUT is only functional with outdoor unit in the stopped state - Japanese domestic model only.)
25	Setting of external low noise level	Sets low noise level when the low noise signal is input from outside.
26	Night-time low noise operation start setting	Sets starting time of nighttime low noise operation. (Night-time low noise setting is also required.)
27	Night-time low noise operation end setting	Sets ending time of nighttime low noise operation. (Night-time low noise setting is also required.)
28	Power transistor check mode *Check after disconnection of compressor wires	Used for trouble diagnosis of DC compressor. Since the waveform of inverter is output without wiring to the compressor, it is convenient to probe whether the trouble comes from the compressor or PC board.
29	Capacity precedence setting	If the capacity control is required, the low noise control is automatically released by this setting during carrying out low noise operation and nighttime low noise operation.
30	Demand setting 1	Changes target value of power consumption when demand control 1 is input.
32	Normal demand setting	Normally enables demand control 1 without external input. (Effective to prevent a problem that circuit breaker of small capacity is shut down due to large load.)

No.	Setting item	Description
35	Setting of difference in elevation for the outdoor unit	Make the setting when the outdoor unit is installed 40 m or more below the indoor unit.
38	Emergency operation (Setting for the master unit operation prohibition in multi- outdoor-unit system)	
39	Emergency operation (Setting for the slave unit 1 operation prohibition in multi- outdoor-unit system)	Used to temporarily prohibit the applicable outdoor unit from operating should there be any faulty part in multi-outdoor-unit system. Since the comfortable environment is extremely impaired, prompt replacement of the part is required.
40	Emergency operation (Setting for the slave unit 2 operation prohibition in multi- outdoor-unit system)	
42	Emergency operation (prohibition of INV compressor operation)	If the INV compressor has a failure, used to run the system only with STD compressor(s). This is a temporary running of the system until the compressor is replaced, thus making comfort extremely worse. Therefore, it is recommended to replace the compressor as soon as possible. (Be noted this setting is not available on model RXYQ5, 8PY1.)

		Setting item display												
No.	Setting item	MODE	TEST		/H selection		Low noise	Demand	Setting con	nditic	on displa	ay		
	Setting item	H1P	H2P	IND H3P	Master H4P	Slave H5P	H6P	H7P					* F	actory set
									Address 0		\circ	• •	• (•
0	Degital pressure	0							Binary number 1		\circ	• •	• (
U	gauge kit display								(4 digits)		~			
									1!	5	\circ	\bullet \circ	0	0 0
									Address 0		0	• •	• (* •
1	Cool / Heat	0						0	Binary number 1		\circ	• •	•	
	Unified address								(6 digits)	-	~			
									3	1	\bigcirc $lacktriangle$	00	0 () ()
									Address 0		\circ	• •	•	• *
2	Low noise/demand address	0	•	•	•	•	0	•	Binary number 1		\circ	• •	•	
	address								(6 digits)		~			
									3:	1	0 •	00	0 (00
3	Test operation (Refer to the description	0	•	•	•	•	0	0	Test operation: ON		0	• •		
	on page 180)								Test operation: OFF		0 •	••	• () • *
5	Indoor forced fan H	0	•	•	•	0	•	0	Normal operation		0	• •		0 *
									Indoor forced fan H		0 •	••	• () •
6	Indoor forced operation	0	•	•	•	0	0	•	Normal operation		0	• •		* 0
	operane.								Indoor forced operation		<u> </u>	••	0 (<u>) • </u>
	T								High		\circ	• •	0	
8	Te setting	0	•	•	0	•	•	_	Normal (factory setting)		0	• •		* • (
									Low	—	0 •	••		
	T								High		\circ	• •	0	
9	Tc setting	0	•	•	0	•	•	0	Normal (factory setting)		\circ	• •		* • (
									Low	—	$\frac{\bigcirc \bullet}{\bigcirc \bullet}$	••		
10	Defrost changeover	0							Quick defrost		\circ	• •	0	
10	setting		•	•	0		0	_	Normal (factory setting)			• •		* • (
									Slow defrost OFF		$\bigcirc \bullet$	••		
11	Sequential operation setting	0	•	•	0	•	0	0	ON		0			
									External low noise/demand:			••) • * • • ·
12	External low noise/	0	•	•	0	0			NO		\circ	••		* 0
	demand setting								External low noise/demand: YES		\circ	• •	• (O
									Address 0		$\cap \bullet$	• •	•	* •
40	A								Binary number 1		0	• •		
13	Airnet address	0	•	•	0	0	•	0	(6 digits)		~	-		
									63	3	00	00	0 (0 0
16	Setting of hot water	0		0					OFF		\circ	• •	• (* 0
10	heater	O		O					ON		\circ	• •	• () •
	Lligh static procesure								High static pressure setting: OFF		\circ	• •	•	* 0
18	High static pressure setting	0	•	0	•	•	0	•	High static pressure setting:		\cap	•) •
									ON					
	Emergency operation								OFF		0	• •		* •
19	(STD compressor is inhibited to operate.)	0	•	0	•	•	0	0	STD 1, 2 operation: Inhibited		0	• •		
									STD 2 operation: Inhibited		0 •	••) •
20	Additional refrigerant charging operation	0	•	0	•	0	•	•	Refrigerant charging: OFF		\circ			* 0
	setting							-	Refrigerant charging: ON		0 •	<u> </u>		
21	Refrigerant recovery/vacuuming	0	•	0	•	0	•	0	Refrigerant recovery / vacuuming: OFF					* 0
	mode setting								Refrigerant recovery / vacuuming: ON OFF					<u> </u>
														*
22	Night-time low noise setting	0	•	0	•	0	0	•	Level 1 (outdoor fan with 6 step or lower) Level 2 (outdoor fan with 5 step or lower)					
									Level 2 (outdoor fan with 5 step of lower) Level 3 (outdoor fan with 4 step or lower)				•) •
					1				Level 3 (outdoor fall with 4 step of lower)		\bigcirc $lacktriangle$		• () U

			Settin	g item dis	play							
No.	0.111.00.110.00	MODE	TEST		C/H selection		Low	Demand	Setting cond	dition display		
	Setting item	H1P	H2P	IND H3P	Master H4P	Slave H5P	noise H6P	H7P			* Fa	ctory set
0.4	ENECUT test								ENECUT output OFF	$\circ \bullet \bullet \bullet$	• •	* ()
24	operation (Domestic Japan only)	0		0	0	•	•		ENECUT output forced ON	$\circ \bullet \bullet \bullet$	• 0	
									Level 1 (outdoor fan with 6 step or lower)	$\circ \bullet \bullet \bullet$	• •	0
25	Low noise setting	0	•	0	0	•	•	0	Level 2 (outdoor fan with 5 step or lower)	$\circ \bullet \bullet \bullet$	• 0	*
									Level 3 (outdoor fan with 4 step or lower)	$\circ \bullet \bullet \bullet$	0	
	Night-time low noise								About 20:00	$\circ \bullet \bullet \bullet$	•	0
26	operation start setting	0	•	0	0	•	0	•	About 22:00 (factory setting)	$\circ \bullet \bullet \bullet$	• 0	• *
	Setting								About 24:00	$\circ \bullet \bullet \bullet$		
	Night-time low noise								About 6:00	$\circ \bullet \bullet \bullet$	•	0
27	operation end setting	0	•	0	0	•	0	0	About 7:00	$\circ \bullet \bullet \bullet$	• 0	•
	Setting								About 8:00 (factory setting)	$\circ \bullet \bullet \bullet$	0	• *
28	Power transistor	0		0	0	0			OFF	$\circ \bullet \bullet \bullet$	• •	* 0
20	check mode	O		O	O	O			ON	$\circ \bullet \bullet \bullet$	• 0	•
29	Capacity	0		0	0	0		0	OFF	$\circ \bullet \bullet \bullet$	• •	* 0
23	precedence setting	O		O	O			O	ON	$\circ \bullet \bullet \bullet$	• 0	•
									60 % demand	$\circ \bullet \bullet \bullet$	• •	0
30	Demand setting 1	0	•	0	0	0	0	•	70 % demand	$\circ \bullet \bullet \bullet$	• 0	* •
									80 % demand	$\circ \bullet \bullet \bullet$	0	
32	Normal demand	0	0						OFF	$\circ \bullet \bullet \bullet$	• •	* 0
32	setting	O	O						ON	$\circ \bullet \bullet \bullet$	• 0	•
	Setting of difference								Normal	$\circ \bullet \bullet \bullet$	•	
35	in elevation for the outdoor unit	0	0	•	•	•	0	0	65 m or less	$\circ \bullet \bullet \bullet$	00	•
	outdoor unit								90 m or less	$\circ \bullet \bullet \bullet$	00	0
	Emergency operation								OFF	\circ		* ()
38	(Master unit with multi-outdoor-unit	0	0	•	•	0	0	•				
	system is inhibited to operate.)								Master unit operation: Inhibited	$\circ \bullet \bullet \bullet$	• 0	
	Emergency											
	operation (Slave unit 1 with			_	_		_		OFF	$\circ \bullet \bullet \bullet$	•	* ()
39	multi-outdoor-unit system is inhibited to	0	0	•	•	0	0	0			. •	
	operate.)								Slave unit 1 operation: Inhibited			
	Emergency operation								OFF	\circ		* ()
40	(Ślave unit 2 with	0	0	•	0	•	•	•				
	multi-outdoor-unit system is inhibited to								Slave unit 2 operation: Inhibited		• 0	
	operate.)											
	Emergency operation								Normal operation	$\circ \bullet \bullet \bullet$	• •	* 0
42	(prohibition of INV compressor	0	0	•	0	•	0	•	Emergency operation	0 0 0 0		
	operation)								(prohibition of INV compressor operation)	$\cup \bullet \bullet \bullet$		

c. Monitor mode

To enter the monitor mode, push the MODE (BS1) button when in "Setting mode 1".

<Selection of setting item>

Push the SET (BS2) button and set the LED display to a setting item.

<Confirmation on setting contents>

Push the RETURN (BS3) button to display different data of set items.

Push the RETURN (BS3) button and switches to the initial status of "Monitor mode".

^{*} Push the MODE (BS1) button and returns to "Setting mode 1".

Na	Catting items			LE	D disp	lay			Data diameter	
No.	Setting item	H1P	H2P	НЗР	H4P	H5P	H6P	H7P	Data display	
0	Various settings	•	•	•	•	•	•	•	Lower 4 digits	
1	C/H unified address	•	•	•	•	•	•	0		
2	Low noise/demand address	•	•	•	•	•	0	•		
3	Not used	•	•	•	•	•	0	0		
4	Airnet address	•	•	•	•	0	•	•		
5	Number of connected indoor units	•	•	•	•	0	•	0	Lower 6 digits	
6	Number of connected BS units	•	•	•	•	0	0	•		
7	Number of connected zone units (excluding outdoor and BS unit)	•	•	•	•	0	0	0		
8	Number of outdoor units	•	•	•	0	•	•	•		
9	Number of connected BS units	•	•	•	0	•	•	0	Lower 4 digits: upper	
10	Number of connected BS units	•	•	•	0	•	0	•	Lower 4 digits: lower	
11	Number of zone units (excluding outdoor and BS unit)	•	•	•	0	•	0	0	Lower 6 digits	
12	Number of terminal blocks	•	•	•	0	0	•	•	Lower 4 digits: upper	
13	Number of terminal blocks	•	•	•	0	0	•	0	Lower 4 digits: lower	
14	Contents of malfunction (the latest)	•	•	•	0	0	0	•	Malfunction code table	
15	Contents of malfunction (1 cycle before)	•	•	•	0	0	0	0	Refer page 216.	
16	Contents of malfunction (2 cycle before)	•	•	0	•	•	•	•		
20	Contents of retry (the latest)	•	•	0	•	0	•	•		
21	Contents of retry (1 cycle before)	•	•	0	•	0	•	0		
22	Contents of retry (2 cycle before)	•	•	0	•	0	0	•		
25	Number of multi connection outdoor units	•	•	0	0	•	•	0	Lower 6 digit	

The numbers in the "No." column represent the number of times to press the SET (BS2) button.


Setting item 0 Display contents of "Number of units for various settings"

octung item o bispia	y content	.3 01	Hui		Oi ui	1113 1	Oi V	ii ioas
EMG operation / backup operation	ON	0	•	•	0	•	•	•
setting	OFF	•	•	•	•	•	•	•
Defrost select setting	Short	•	•	•	•	0	•	•
	Medium	•	•	•	•	•	•	•
	Long	•	•	•	•	•	•	•
Te setting	Н	•	•	•	•	•	0	•
	М	•	•	•	•	•	•	•
	L	•	•	•	•	•	•	•
Tc setting	Н	•	•	•	•	•	•	0
	М	•	•	•	•	•	•	•
	L	0	•	•	•	•	•	•

(V2765)


Push the SET button and match with the LEDs No. 1 - 15, push the RETURN button, and confirm the data for each setting.

★ Data such as addresses and number of units is expressed as binary numbers; the two ways of expressing are as follows:



The No. 1 cool/heat unified address is expressed as a binary number consisting of the lower 6 digits. (0 - 63)

In \odot the address is 010110 (binary number), which translates to 16+4+2=22 (base 10 number). In other words, the address is 22.



The number of terminal blocks for No. 12 and 13 is expressed as an 8-digit binary number, which is the combination of four upper, and four lower digits for No. 12 and 13 respectively. (0 - 128) In ② the address for No. 12 is 0101, the address for No. 13 is 0110, and the combination of the two is 01010110 (binary number), which translates to 64 + 16 + 4 + 2 = 86 (base 10 number). In other words, the number of terminal block is 86.

★ See the preceding page for a list of data, etc. for No. 0 - 25.


3.2.2 Cool / Heat Mode Switching

There are the following 4 cool/heat switching modes.

- ① Set cool/heat separately for each outdoor unit system by indoor unit remote controller.
- ② Set cool/heat separately for each outdoor unit system by cool/heat selector.
- 3 Set cool/heat for more than one outdoor unit system simultaneously in accordance with unified master outdoor unit by indoor unit remote controller.
- Set cool/heat for more than one outdoor unit system simultaneously in accordance with
 unified master outdoor unit by cool/heat switching remote controller.

① Set Cool / Heat Separately for Each Outdoor Unit System by Indoor Unit Remote Controller

- It does not matter whether or not there is outdoor outdoor unit wiring.
- Set outdoor unit PC board DS1-1 to <u>IN</u> (factory set).
- Set cool/heat switching to <u>IND</u> (individual) for "Setting mode 1" (factory set).
- Set the master unit (= indoor unit having the right to select the cooling/heating operation mode).



<Set the master unit (= indoor unit having the right to select the cooling/heating operation mode).> In the case of wired remote controllers

- After the check operation, "CHANGEOVER UNDER CONTROL" is flashing in all connected remote controllers.
- Select an indoor unit to be used as the master unit in accordance with the request from the customer. (It is recommended to select an indoor unit which will be used most often as the master unit.)
- Press the operation mode selector button in the remote controller of the indoor unit selected as the master unit.
- In that remote controller, "CHANGEOVER UNDER CONTROL" disappears. That remote controller will control changeover of the cooling/heating operation mode.
 In other remote controllers, "CHANGEOVER UNDER
- In other remote controllers, "CHANGEOVER UNDER CONTROL" lights.


For the details, refer to the installation manual supplied together with the indoor unit.

In the case of wireless remote controllers

- After the check operation, the timer lamp is flashing in all connected indoor units.
- Select an indoor unit to be used as the master unit in accordance with the request from the customer.
 (It is recommended to select an indoor unit which will be used most often as the master unit.)
- Press the operation selector mode button in the remote controller of the indoor unit selected as the master unit. A "peep" sound is emitted, and the timer lamp turns off in all indoor units.
- That indoor unit will control changeover of the cooling/ heating operation mode.


② Set Cool / Heat Separately for Each Outdoor Unit System by Cool / Heat Selector

- ◆ It does not matter whether or not there is outdoor outdoor unit wiring.
- ◆ Set outdoor unit PC board DS1-1 to <u>OUT</u> (factory set).
- ◆ Set cool/heat switching to IND (individual) for "Setting mode 1" (factory set).



③ Set Cool / Heat for More Than One Outdoor Unit System Simultaneously in Accordance with Unified Master Outdoor Unit by Indoor Unit Remote Controller


- Install the external control adapter for outdoor unit on either the outdoor-outdoor, indoor-outdoor transmission line.
- ◆ Set outdoor unit PC board DS1-1 to IN (factory set).
- ◆ In setting mode 1, set the outdoor unit you want to give cool/heat selection permission to as the group master, and set the other outdoor units as group slave units.
- ◆ Set the outdoor unit external control adapter SS1 to BOTH (factory set) or C/H, and SS2 to OFF (factory set).



Multi outdoor units connection

Set Cool / Heat for More Than One Outdoor Unit System Simultaneously in Accordance with Unified Master Outdoor Unit by Cool / Heat Selector


- Install the external control adapter for outdoor unit on either the outdoor-outdoor, indoor-outdoor transmission line.
- ◆ Mount the COOL/HEAT selector to the master outdoor unit for the unified control.
- ◆ Set the DS1-1 on the PC board of master outdoor unit to <u>OUT</u>.
- ◆ In setting mode 1, set the outdoor unit you want to give cool/heat selection permission to as the group master, and set the other outdoor units as group slave units.
- ◆ Set the outdoor unit external control adapter SS1 to BOTH (factory set) or C/H, and SS2 to OFF (factory set).



Multi outdoor units connection

Supplementation on 3 and 4.

When switching cool/heat for each adapter PC board with the use of more than one adapter PC board, set the address of the external control adaptor for outdoor unit PC board <u>DS1 and DS2</u> so that it matches the unified cool/heat address of outdoor unit main PC board.



(V2723)

Address setting for ③ and ④ (Set lower 5 digits with binary number.) [No.0 to No.31]

Address	Outdoor unit PC board LED	External control adaptor for out	
No.	Set with setting mode 2	DS2 DS1	
No 0	$\circ \bullet \bullet \bullet \bullet \bullet \circ \circ$		0
No 1	○ ● ● ● ○ 1		1
No 2	$\circ \bullet \bullet \bullet \circ \bullet$		2
No 3			3
No 4			4
1	}	₹	
No 30	○ ● ○ ○ ○ ○ ● 30		30
No 31	○ ● ○ ○ ○ ○ ○ ○ ○ 31		31
	○ ON ● OFF Upper p	osition (ON) lower position (OFF) (The shaded part	shows kno

(V2724)

3.2.3 Setting of Low Noise Operation and Demand Operation

Setting of Low Noise Operation

By connecting the external contact input to the low noise input of the outdoor unit external control adapter (optional), you can lower operating noise by 2-3 dB.

Setting	Content
Mode 1	Set the outdoor unit fan to Step 6 or lower.
Mode 2	Set the outdoor unit fan to Step 5 or lower.
Mode 3	Set the outdoor unit fan to Step 4 or lower.

A. When the low noise operation is carried out by external instructions (with the use of the external control adapter for outdoor unit)

- 1. While in "Setting mode 2", set the setting condition for set item No. 12 (Setting of external low noise/demand operation) to "YES".
- 2. If necessary, while in "Setting mode 2", select the setting condition (i.e., "Mode 1", "Mode 2", or "Mode 3") for set item No. 25 (Setting of external low noise level).
- If necessary, while in "Setting mode 2", set the setting condition for the set item No. 29
 (Setting of capacity precedence) to "ON".
 (If the condition is set to "ON", when the air-conditioning load reaches a high level, the low noise operation command will be ignored to put the system into normal operation mode.)

B. When the low noise operation is carried out automatically at night (The external control adapter for outdoor unit is not required)

- 1. While in "Setting mode 2", select the setting condition (i.e., "Mode 1", "Mode 2", or "Mode 3") for set item No. 22 (Setting of nighttime low noise level).
- If necessary, while in "Setting mode 2", select the setting condition (i.e., "20:00", "22:00", or "24:00") for set item No. 26 (Setting of start time of nighttime low noise operation).
 (Use the start time as a guide since it is estimated according to outdoor temperatures.)
- If necessary, while in "Setting mode 2", select the setting condition (i.e., "06:00", "07:00", or "08:00") for set item No. 27 (Setting of end time of nighttime low noise operation).
 (Use the end time as a guide since it is estimated according to outdoor temperatures.)
- 4. If necessary, while in "Setting mode 2", set the setting condition for set item No. 29 (Setting of capacity precedence) to "ON". (If the condition is set to "ON", when the air-conditioning load reaches a high level, the system will be put into normal operation mode even during nighttime.)

Image of operation in the case of A




Image of operation in the case of B





Image of operation in the case of A and B



Setting of Demand Operation

By connecting the external contact input to the demand input of the outdoor unit external control adapter (optional), the power consumption of unit operation can be saved suppressing the compressor operating condition.

Set item	Condition	Content
Demand 1	Mode 1	The compressor operates at approx. 60% or less of rating.
	Mode 2	The compressor operates at approx. 70% or less of rating.
	Mode 3	The compressor operates at approx. 80% or less of rating.
Demand 2	_	The compressor operates at approx. 40% or less of rating.

A. When the demand operation is carried out by external instructions (with the use of the external control adapter for outdoor unit).

- 1. While in "Setting mode 2", set the setting condition for set item No. 12 (Setting of external low noise/demand operation) to "YES".
- 2. If necessary, while in "Setting mode 2", select the set item No. 30 (Setting of Demand 1 level) and then set the setting condition to targeted mode.

B. When the normal demand operation is carried out. (Use of the external control adapter for outdoor unit is not required.)

- 1. While in "Setting mode 2", make setting of the set item No. 32 (Setting of constant demand) to "ON".
- 2. While in "Setting mode 2", select the set item No. 30 (Setting of Demand 1 level) and then set the setting condition to targeted mode.

Image of operation in the case of A




Image of operation in the case of B





Image of operation in the case of A and B



Detailed Setting Procedure of Low Noise Operation and Demand Control

1. Setting mode 1 (H1P off)

 \odot In setting mode 2, push the BS1 (MODE button) one time. \rightarrow Setting mode 2 is entered and H1P lights.

During the setting mode 1 is displayed, "In low noise operation" and "In demand control" are displayed.

2. Setting mode 2 (H1P on)

- \odot In setting 1, push and hold the BS1 (MODE button) for more than 5 seconds. \rightarrow Setting mode 2 is entered and H1P lights.
- ② Push the BS2 (SET button) several times and match the LED display with the Setting No. you want.
- ③ Push the BS3 (RETURN button) one time, and the present setting content is displayed. → Push the BS2 (SET button) several times and match the LED display with the setting content (as shown below) you want.
- 9 Push the BS3 (RETURN button) two times. \rightarrow Returns to 0.
- $\ \ \$ Push the BS1 (MODE button) one time. $\ \ \rightarrow$ Returns to the setting mode 1 and turns H1P off.

O: ON ●: OFF ④: Blink

		①							2								3																								
Setting No. Setting No.			No. in	dicatio	on			S	etting	No. in	dicatio			Setting contents	Setting contents indication (Initial setting)																										
		H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H1P	H2P	НЗР	H4P	H5P	H6P	H7P		H1P	H2P	НЗР	H4P	H5P	H6P	H7P																		
12	External low noise / Demand setting	0	•	•	•	•	•	•	0	•	•	0	0	•	•	NO (Factory setting)	0	•	•	•	•	•	•																		
	Setting															YES	0	•	•	•	•	•	•																		
22	Night-time low noise setting								0	•	0	•	0	0	•	OFF (Factory setting)	0	•	•	•	•	•	•																		
																Mode 1	0	•	•	•	•	•	•																		
																Mode 2	0	•	•	•	•	•	•																		
																Mode 3	0	•	•	•	•	•	•																		
25	External								0	•	0	0	•	•	0	Mode 1	0	•	•	•	•	•	•																		
	low noise setting															Mode 2 (Factory setting)	0	•	•	•	•	•	•																		
																Mode 3	0	•	•	•	•	•	•																		
26	Night-time								0	•	0	0	•	0	•	PM 8:00	0	•	•	•	•	•	•																		
	low noise start setting																																	PM 10:00 (Factory setting)	0	•	•	•	•	•	•
																PM 0:00	0	•	•	•	•	•	•																		
27	Night-time								0	•	0	0	•	0	0	AM 6:00	0	•	•	•	•	•	•																		
	low noise end setting									n .									AM 7:00	0	•	•	•	•	•	•															
	ond soming															AM 8:00 (Factory setting)	0	•	•	•	•	•	•																		
29	Capacity precedence setting								0	•	0	0	0	•	0	Low noise precedence (Factory setting)	0	•	•	•	•	•	•																		
																Capacity precedence	0	•	•	•	•	•	•																		
30	Demand setting 1								0	•	0	0	0	0	•	60 % of rated power consumption	0	•	•	•	•	•	•																		
																70 % of rated power consumption (Factory setting)	0	•	•	•	•	•	•																		
																80 % of rated power consumption	0	•	•	•	•	•	•																		
32	Normal demand setting								0	•	•	•	•	•	•	OFF (Factory setting)	0	•	•	•	•	•	•																		
																ON	0	•	•	•	•	•	•																		
			Settin	g mod	e indi	cation	sectio	n		Settin	g No.	indica	tion se	ction				Set co	ontent	s indic	ation s	ection																			

3.2.4 Setting of Refrigerant Recovery Mode

When carrying out the refrigerant collection on site, fully open the respective expansion valve of indoor and outdoor units.

All indoor and outdoor unit's operation are prohibited.

[Operation procedure]

- ① In setting mode 2 with units in stop mode, set "Refrigerant Recovery / Vacuuming mode" to ON. The respective expansion valve of indoor and outdoor units are fully opened. (H2P turns to display "TEST OPERATION" (blinks), "TEST OPERATION" and "UNDER CENTRALIZED CONTROL" are displayed on the remote controller, and the all indoor / outdoor unit operation is prohibited.
 - After setting, do not cancel "Setting Mode 2" until completion of refrigerant recovery operation.
- ② Collect the refrigerant using a refrigerant recovery unit. (See the instruction attached to the refrigerant recovery unit for more detal.)
- ③ Press Mode button "BS1" once and reset "Setting Mode 2".

3.2.5 Setting of Vacuuming Mode

In order to perform vacuuming operation at site, fully open the expansion valves of indoor and outdoor units and turn on some solenoid valves.


[Operating procedure]

- With Setting Mode 2 while the unit stops, set "Refrigerant recovery / Vacuuming mode" to ON. The expansion valves of indoor and outdoor units fully open and some of solenoid valves open.
 - (H2P blinks to indicate the test operation, and the remote controller displays "Test Operation" and "Under centralized control", thus prohibiting operation.)
 - After setting, do not cancel "Setting Mode 2" until completion of Vacuuming operation.
- ② Use the vacuum pump to perform vacuuming operation.
- ③ Press Mode button "BS1" once and reset "Setting Mode 2".

3.2.6 Check Operation Detail

CHECK OPERATION FUNCTION

(Press the MODE button BS1 once and set to SETTING MODE 1 (H1P: OFF))



Part 6 Troubleshooting

1.	Sym	ptom-based Troubleshooting	201
2.	Trou	bleshooting by Remote Controller	204
	2.1	The INSPECTION / TEST Button	
	2.2	Self-diagnosis by Wired Remote Controller	205
	2.3	Self-diagnosis by Wireless Remote Controller	
	2.4	Operation of The Remote Controller's Inspection /	
		Test Operation Button	209
	2.5	Remote Controller Service Mode	210
	2.6	Remote Controller Self-Diagnosis Function	212
3.	Trou	bleshooting by Indication on the Remote Controller	220
	3.1	"RD" Indoor Unit: Error of External Protection Device	
	3.2	"Ri" Indoor Unit: PC Board Defect	221
	3.3	"R3" Indoor Unit: Malfunction of Drain Level Control System (S1L)	222
	3.4	"R6" Indoor Unit: Fan Motor (M1F) Lock, Overload	224
	3.5	"R7" Indoor Unit: Malfunction of Swing Flap Motor (M1S)	225
	3.6	"RS" Indoor Unit: Malfunction of Moving Part of	
		Electronic Expansion Valve (Y1E)	227
	3.7	"RF" Indoor Unit: Drain Level above Limit	229
	3.8	"RJ" Indoor Unit: Malfunction of Capacity Determination Device	230
	3.9	"ยฯ" Indoor Unit: Malfunction of Thermistor (R2T) for	
		Heat Exchanger	
		"E5" Indoor Unit: Malfunction of Thermistor (R3T) for Gas Pipes	
		"L9" Indoor Unit: Malfunction of Thermistor (R1T) for Suction Air	233
	3.12	"ເປ" Indoor Unit: Malfunction of Thermostat Sensor in	
		Remote Controller	
		"E?" Outdoor Unit: PC Board Defect	
		"E3" Outdoor Unit: Actuation of High Pressure Switch	
		"E4" Outdoor Unit: Actuation of Low Pressure Sensor	
		"E5" Outdoor Unit: Inverter Compressor Motor Lock	
		"EE" Outdoor Unit: STD Compressor Motor Overcurrent/Lock	
		"E7" Outdoor Unit: Malfunction of Outdoor Unit Fan Motor	243
	3.19	"E9" Outdoor Unit: Malfunction of Moving Part of	
		Electronic Expansion Valve (Y1E, Y2E)	
		"F3" Outdoor Unit: Abnormal Discharge Pipe Temperature	
		"F6" Outdoor Unit: Refrigerant Overcharged	
		"หา" Outdoor Unit: Abnormal Outdoor Fan Motor Signal	
		"หรู" Outdoor Unit: Malfunction of Thermistor (R1T) for Outdoor Air	
		"ป๋่ว" Outdoor Unit: Current Sensor Malfunction	252
	3.25	"ปร" Outdoor Unit: Malfunction of Discharge Pipe Thermistor	050
	0.00	(R3, R31~33T)	253
	3.26	"J5" Outdoor Unit: Malfunction of Thermistor (R2T), (R7T) for	05.4
	0.07	Suction Pipe	254
	3.27	"ปริ" Outdoor Unit: Malfunction of Thermistor (R4T) for	055
	0.00	Outdoor Unit Heat Exchanger	
	3.28	"ป่า" Outdoor Unit: Malfunction of Liquid Pipe Thermistor (R6T)	256

3.29	"്വദ്" Outdoor Unit: Malfunction of Subcooling Heat Exchanger	
	Gas Pipe Thermistor (R5T)	257
3.30	"JR" Outdoor Unit: Malfunction of High Pressure Sensor	258
3.31	"JC" Outdoor Unit: Malfunction of Low Pressure Sensor	259
3.32	"LY" Outdoor Unit: Malfunction of	
	Inverter Radiating Fin Temperature Rise	260
3.33	"L5" Outdoor Unit: Inverter Compressor Abnormal	262
	"L8" Outdoor Unit: Inverter Current Abnormal	
	"L9" Outdoor Unit: Inverter Start up Error	266
3.36	"LC" Outdoor Unit: Malfunction of Transmission Between Inverter	
	and Control PC Board	
	"Pi" Outdoor Unit: Inverter Over-Ripple Protection	271
3.38	"Pฯ" Outdoor Unit: Malfunction of Inverter Radiating Fin	
	Temperature Rise Sensor	
3.39	"PJ" Outdoor Unit: Faulty Field Setting after Replacing Main PC Boar	
	or Faulty Combination of PC Board	274
3.40	"UD" Outdoor Unit: Low Pressure Drop Due to Refrigerant Shortage	
	or Electronic Expansion Valve Failure	
	"U" Reverse Phase, Open Phase	2/6
3.42	"U2" Outdoor Unit: Power Supply Insufficient or	077
0.40	Instantaneous Failure	
	"U3" Outdoor Unit: Check Operation not Executed	
	"U4" Malfunction of Transmission Between Indoor Units	281
3.45	"U5" Indoor Unit: Malfunction of Transmission Between	000
2 46	Remote Controller and Indoor Unit "IJ" Indoor Unit: Malfunction of Transmission Between	∠oა
3.40	Outdoor Units	284
2 17	"U8" Indoor Unit: Malfunction of Transmission Between Main and	204
J. 4 7	Sub Remote Controllers	286
3 48	"U9" Indoor Unit: Malfunction of Transmission Between Indoor and	200
J. 7 U	Outdoor Units in the Same System	287
3 49	"UR" Improper Combination of Indoor and Outdoor Units,	207
0. 10	Indoor Units and Remote Controller	288
3.50	"UE" Address Duplication of Centralized Controller	
	"UE" Malfunction of Transmission Between Centralized Controller	00
	and Indoor Unit	291
3.52	"UF" System is not Set yet	
	"UH" Malfunction of System, Refrigerant System Address Undefined	
	bleshooting (OP: Central Remote Controller)	
4.1	"fil" PC Board Defect	
4.2	"fi8" Malfunction of Transmission Between Optional Controllers	0.
	for Centralized Control	298
4.3	"PR" Improper Combination of Optional Controllers for	
	Centralized Control	.300
4.4	"TE" Address Duplication, Improper Setting	
Trou	bleshooting (OP: Unified ON/OFF Controller)	
5.1	Operation Lamp Blinks	
5.2	Display "Under Centralized Control" Blinks (Repeats Single Blink)	
5.3	Display "Under Centralized Control" Blinks (Repeats Double Blink)	

200 Troubleshooting

4.

5.

1. Symptom-based Troubleshooting

	Symptom	Supposed Cause	Countermeasure	
1 The system does	s not start operation at all.	Blowout of fuse(s)	Turn Off the power supply and then replace the fuse(s).	
		Cutout of breaker(s)	 If the knob of any breaker is in its OFF position, turn ON the power supply. If the knob of any circuit breaker is in its tripped position, do not turn ON the power supply. 	
			ON Knob Tripped OFF	
		Power failure	After the power failure is reset, restart the system.	
2 The system start immediate stop.	s operation but makes an	Blocked air inlet or outlet of indoor or outdoor unit	Remove obstacle(s).	
		Clogged air filter(s)	Clean the air filter(s).	
3 The system does	s not cool or heat air well.	Blocked air inlet or outlet of indoor or outdoor unit	Remove obstacle(s).	
		Clogged air filter(s)	Clean the air filter(s).	
		Enclosed outdoor unit(s)	Remove the enclosure.	
		Improper set temperature	Set the temperature to a proper degree.	
		Airflow rate set to "LOW"	Set it to a proper airflow rate.	
		Improper direction of air diffusion	et it to a proper direction.	
		Open window(s) or door(s)	Shut it tightly.	
	[In cooling]	Direct sunlight received	Hang curtains or shades on windows.	
	[In cooling]	Too many persons staying in a room		
	[In cooling]	equipment) located in a room		
4 The system does not operate.	immediately restarts operation.	If the OPERATION lamp on the remote controller turns ON, the system will be normal. These	Normal operation. The system will automatically start operation after	
	Pressing the TEMP ADJUST button immediately resets the system.	system will be normal. These symptoms indicate that the system is controlled so as not to put unreasonable loads on the system.	a lapse of five minutes.	
	The remote controller displays "UNDER CENTRALIZED CONTROL", which blinks for a period of several seconds when the OPERATION button is depressed.	The system is controlled with centralized controller. Blinking display indicates that the system cannot be operated using the remote controller.	Operate the system using the COOL/HEAT centralized remote controller.	
	The system stops immediately after turning ON the power supply.	The system is in preparation mode of micro computer operation.	Wait for a period of approximately one minute.	
The system makes intermittent stops.	The remote controller displays malfunction codes "U4" and "U5", and the system stops but restarts after a lapse of several minutes.	The system stops due to an interruption in communication between units caused by electrical noises coming from equipment other than air conditioners.	Remove causes of electrical noises. If these causes are removed, the system will automatically restart operation.	
6 COOL-HEAT selection is disabled.	The remote controller displays "UNDER CENTRALIZED CONTROL".	This remote controller has no option to select cooling operation.	Use a remote controller with option to select cooling operation.	
	The remote controller displays "UNDER CENTRALIZED CONTROL", and the COOLHEAT selection remote controller is provided.	COOL-HEAT selection is made using the COOL-HEAT selection remote controller.	Use the COOL-HEAT selection remote controller to select cool or heat.	


		Symptom	Supposed Cause	Countermeasure
7	The system conducts fan operation but not cooling or heating operation.	This symptom occurs immediately after turning ON the power supply.	The system is in preparation mode of operation.	Wait for a period of approximately 10 minutes.
α	The airflow rate is not reproduced according to the setting.	Even pressing the AIRFLOW RATE SET button makes no changes in the airflow rate.	In heating operation, when the room temperature reaches the set degree, the outdoor unit will stop while the indoor unit is brought to fan LL operation so that no one gets cold air. Furthermore, if fan operation mode is selected when other indoor unit is in heating operation, the system will be brought to fan LL operation. (The fan LL operation is also enabled while in oil return mode in cooling operation.)	Normal operation.
9	The airflow direction is not reproduced according to the setting.	The airflow direction is not corresponding to that displayed on the remote controller. The flap does not swing.	Automatic control	Normal operation.
10	A white mist comes out from the system.	<pre><indoor unit=""> In cooling operation, the ambient humidity is high. (This indoor unit is installed in a place with much oil or dust.)</indoor></pre>	Uneven temperature distribution due to heavy stain of the inside of the indoor unit	Clean the inside of the indoor unit.
		<indoor unit=""> Immediately after cooling operation stopping, the ambient temperature and humidity are low.</indoor>	Hot gas (refrigerant) flown in the indoor unit results to be vapor from the unit.	Normal operation.
		<indoor and="" outdoor="" units=""> After the completion of defrosting operation, the system is switched to heating operation.</indoor>	Defrosted moisture turns to be vapor and comes out from the units.	Normal operation.
11	The system produces sounds.	<indoor unit=""> Immediately after turning ON the power supply, indoor unit produces "ringing" sounds.</indoor>	These are operating sounds of the electronic expansion valve of the indoor unit.	Normal operation. This sound becomes low after a lapse of approximately one minute.
		<indoor and="" outdoor="" units=""> "Hissing" sounds are continuously produced while in cooling or defrosting operation.</indoor>	These sounds are produced from gas (refrigerant) flowing respectively through the indoor and outdoor units.	Normal operation.
		<indoor and="" outdoor="" units=""> "Hissing" sounds are produced immediately after the startup or stop of the system, or the startup or stop of defrosting operation.</indoor>	These sounds are produced when the gas (refrigerant) stops or changes flowing.	Normal operation.
		<indoor unit=""> Faint sounds are continuously produced while in cooling operation or after stopping the operation.</indoor>	These sounds are produced from the drain discharge device in operation.	Normal operation.
		<pre><indoor unit=""> "Creaking" sounds are produced while in heating operation or after stopping the operation.</indoor></pre>	These sounds are produced from resin parts expanding and contracting with temperature changes.	Normal operation.
		<indoor unit=""> Sounds like "trickling" or the like are produced from indoor units in the stopped state.</indoor>	On VRV systems, these sounds are produced when other indoor units in operation. The reason is that the system runs in order to prevent oil or refrigerant from dwelling.	Normal operation.
		<outdoor unit=""> Pitch of operating sounds changes.</outdoor>	The reason is that the compressor changes the operating frequency.	Normal operation.

		Symptom	Supposed Cause	Countermeasure
12	Dust comes out from the system.	Dust comes out from the system when it restarts after the stop for an extended period of time.	Dust, which has deposited on the inside of indoor unit, is blown out from the system.	Normal operation.
13	Odors come out from the system.	In operation	Odors of room, cigarettes or else adsorbed to the inside of indoor unit are blown out.	The inside of the indoor unit should be cleaned.
14	Outdoor unit fan does not rotate.	In operation	The reason is that fan revolutions are controlled to put the operation to the optimum state.	Normal operation.
15	LCD display "88" appears on the remote controller.	Immediately after turning ON the power supply	The reason is that the system is checking to be sure the remote controller is normal.	Normal operation. This code is displayed for a period of approximately one minute at maximum.
16	The outdoor unit compressor or the outdoor unit fan does not stop.	After stopping operation	It stops in order to prevent oil or refrigerant from dwelling.	Normal operation. It stops after a lapse of approximately 5 to 10 minutes.
17	The outdoor gets hot.	While stopping operation	The reason is that the compressor is warmed up to provide smooth startup of the system.	Normal operation.
18	Hot air comes out from the system even though it stops.	Hot air is felt while the system stops.	On VRV systems, small quantity of refrigerant is fed to indoor units in the stopped state when other indoor units are in operation.	Normal operation.
19	The system does not cool air well.	The system is in dry operation.	The reason is that the dry operation serves not to reduce the room temperature where possible.	Change the system to cooling operation.

2. Troubleshooting by Remote Controller

2.1 The INSPECTION / TEST Button


The following modes can be selected by using the [Inspection/Test Operation] button on the remote control.



2.2 Self-diagnosis by Wired Remote Controller

Explanation

If operation stops due to malfunction, the remote controller's operation LED blinks, and malfunction code is displayed. (Even if stop operation is carried out, malfunction contents are displayed when the inspection mode is entered.) The malfunction code enables you to tell what kind of malfunction caused operation to stop. See page 213 for malfunction code and malfunction contents.



Note:

- 1. Pressing the INSPECTION/TEST button will blink the check indication.
- 2. While in check mode, pressing and holding the ON/OFF button for a period of five seconds or more will clear the failure history indication shown above. In this case, on the codes display, the malfunction code will blink twice and then change to "00" (=Normal), the Unit No. will change to "0", and the operation mode will automatically switch from check mode to normal mode (displaying the set temperature).

2.3 Self-diagnosis by Wireless Remote Controller

In the Case of BRC7C Type BRC7E Type BRC4C Type If equipment stops due to a malfunction, the operation indicating LED on the light reception section flashes.

The malfunction code can be determined by following the procedure described below. (The malfunction code is displayed when an operation error has occurred. In normal condition, the malfunction code of the last problem is displayed.)

- Press the INSPECTION/TEST button to select "Inspection."
 The equipment enters the inspection mode. The "Unit" indication lights and the Unit No. display shows flashing "0" indication.
- 2. Set the Unit No.

Press the UP or DOWN button and change the Unit No. display until the buzzer (*1) is generated from the indoor unit.

*1 Number of beeps

3 short beeps: Conduct all of the following operations.

1 short beep: Conduct steps 3 and 4.

Continue the operation in step 4 until a buzzer remains ON. The continuous buzzer indicates that the malfunction code is confirmed.

Continuous beep: No abnormality.

3. Press the MODE selector button.

The left "0" (upper digit) indication of the malfunction code flashes.

4. Malfunction code upper digit diagnosis

Press the UP or DOWN button and change the malfunction code upper digit until the malfunction code matching buzzer (*2) is generated.

■ The upper digit of the code changes as shown below when the UP and DOWN buttons are pressed.



*2 Number of beeps

Continuous beep: Both upper and lower digits matched. (Malfunction code confirmed)

2 short beeps : Upper digit matched.

1 short beep: Lower digit matched.


5. Press the MODE selector button.

The right "0" (lower digit) indication of the malfunction code flashes.

6. Malfunction code lower digit diagnosis

Press the UP or DOWN button and change the malfunction code lower digit until the continuous malfunction code matching buzzer (*2) is generated.

■ The lower digit of the code changes as shown below when the UP and DOWN buttons are pressed.




Normal status

(SF008)

Enters inspection mode from normal status when the INSPECTION/ TEST button is pressed. 27.0 CODE 1 Press INSPECTION/TEST button. ą, If no button is pressed for 1 minute, equipment returns to normal status. * 3 Press MODE selector button. When MODE selector button is pressed or no button is pressed for 1 minute, equipment returns to normal status. If no button is pressed for 1 minute, equipment returns to normal status. CODE CODE 5 Press MODE selector button.


2.4 Operation of The Remote Controller's Inspection / Test Operation Button



(V2775)

2.5 Remote Controller Service Mode

How to Enter the Service Mode



Service Mode Operation Method

1. Select the mode No.

Set the desired mode No. with the button. (For wireless remote controller, Mode 43 only can be set.)

2. Select the unit No. (For group control only)

Select the indoor unit No. to be set with the time mode \bullet : (For wireless remote controller, \bullet) button.)

3. Make the settings required for each mode. (Modes 41, 44, 45)

In case of Mode 44, 45, push button to be able to change setting before setting work. (LCD "code" blinks.)

For details, refer to the table in next page.

4. Define the setting contents. (Modes 44, 45)

Define by pushing the timer $\begin{tabular}{l} \blacksquare \\ \hline \end{tabular}$ button.

After defining, LCD "code" changes blinking to ON.

5. Return to the normal operation mode.


Push the button one time.

Mode No	Function	Contents and operation method	Remote controller display example
40	Malfunction hysteresis display	Display malfunction hysteresis. The history No. can be changed with the button.	Unit 1 Malfunction code 2-U4 Malfunction code Hystory No: 1 - 9 1: Latest
41	Display of sensor and address data	Display various types of data. Select the data to be displayed with the button. Sensor data 0: Thermostat sensor in remote controller. 1: Suction 2: Liquid pipe 3: Gas pipe Address data 4: Indoor unit address 5: Outdoor unit address 6: BS unit address 7: Zone control address 8: Cool/heat group address 9: Demand / low noise address	Sensor data display Unit No. Sensor type 1 1 1 47 27 Temperature °C Address display Unit No. Address type 1 8 47 1 (VE008) Address
43	Forced fan ON	Manually turn the fan ON by each unit. (When you want to search for the unit No.) By selecting the unit No. with the button, you can turn the fan of each indoor unit on (forced ON) individually.	Unit 1 <i>ЧЗ</i>
44	Individual setting	Set the fan speed and air flow direction by each unit Select the unit No. with the time mode button. Set the fan speed with the button. Set the air flow direction with the button.	Unit 1 Code 44 Fan speed 1: Low 3: High (VE010)
45	Unit No. transfer	Transfer unit No. Select the unit No. with the total button. Set the unit No. after transfer with the button.	Present unit No. Unit 1
45 47	This function is not	used by VRV II R-410A Heat Pump 50Hz.	

2.6 Remote Controller Self-Diagnosis Function

The remote controller switches are equipped with a self diagnosis function so that more appropriate maintenance can be carried out. If a malfunction occurs during operation, the operation lamp, malfunction code and display of malfunctioning unit No. let you know the contents and location of the malfunction.

When there is a stop due to malfunction, the contents of the malfunction given below can be diagnosed by a combination of operation lamp, INSPECTION display of the liquid crystal display and display of malfunction code. It also lets you know the unit No. during group control.



(VL050)

○: ON •: OFF •: Blink

					O:UN •:UFF	T: Blink
	Malfunction code	Operation lamp	Inspection display	Unit No.	Malfunction contents	Page Referred
Indoor Unit	A0	•	•	•	Error of external protection device	220
	A1	•	•	•	PC board defect, E ² PROM defect	221
	А3	•	•	•	Malfunction of drain level control system (S1L)	222
	A6	•	•	•	Fan motor (M1F) lock, overload	224
	A7	0	•	•	Malfunction of swing flap motor (MA)	225
	A9	•	•	•	Malfunction of moving part of electronic expansion valve (20E)	227
	AF	0	•	•	Drain level about limit	229
	AH	0	•	•	Malfunction of air filter maintenance	_
	AJ	•	•	•	Malfunction of capacity setting	230
	C4	•	•	•	Malfunction of thermistor (R2T) for heat exchange (loose connection, disconnection, short circuit, failure)	231
	C5	•	•	•	Malfunction of thermistor (R3T) for gas pipes (loose connection, disconnection, short circuit, failure)	232
	C9	•	•	•	Malfunction of thermistor (R1T) for air inlet (loose connection, disconnection, short circuit, failure)	233
	CJ	0	0	0	Malfunction of thermostat sensor in remote controller	234
Outdoor Unit	E1	•	•	•	PC board defect	235
	E3	•	•	•	Actuation of high pressure switch	236
	E4	•	•	•	Actuation of low pressure sensor	238
	E5	•	•	•	Compressor motor lock	240
	E6	•	•	•	Standard compressor lock or over current	242
	E7	•	•	•	Malfunction of outdoor unit fan motor	243
	E9	•	•	•	Malfunction of moving part of electronic expansion valve (Y1E, Y2E)	246
	F3	•	•	•	Abnormal discharge pipe temperature	248
	F6	•	•	•	Refrigerant overcharged	249
	H7	•	•	•	Abnormal outdoor fan motor signal	250
	H9	•	•	•	Malfunction of thermistor (R1T) for outdoor air (loose connection, disconnection, short circuit, failure)	251
	J2	•	•	•	Current sensor malfunction	252
	J3	•	•	•	Malfunction of discharge pipe thermistor (R31~33T) (loose connection, disconnection, short circuit, failure)	253
	J5	•	•	•	Malfunction of thermistor (R2T) for suction pipe (loose connection, disconnection, short circuit, failure)	254
	J6	•	•	•	Malfunction of thermistor (R4T) for heat exchanger (loose connection, disconnection, short circuit, failure)	255
	J7	•	•	•	Malfunction of receiver outlet liquid pipe thermistor (R6T)	256
	J9	•	•	•	Malfunction of subcooling heat exchanger gas pipe thermistor (R5T)	257
	JA	•	•	•	Malfunction of discharge pipe pressure sensor	258
	JC	•	•	•	Malfunction of suction pipe pressure sensor	259
	L0	•	•	•	Inverter system error	_
	L4	•	•	•	Malfunction of inverter radiating fin temperature rise	260
	L5	•	•	•	DC output overcurrent of inverter compressor	262
	L8	•	•	•	Inverter current abnormal	264
-	L9	•	•	•	Inverter start up error	266

Outdoor Unit						O.ON V.OFF	J. Dillik
LC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0					Unit No.	Malfunction contents	Page Referred
P1	Outdoor Unit	LA	•	0	•	Malfunction of power unit	_
P4		LC	•	•	•		268
System PJ		P1	•	0	•	Inverter over-ripple protection	271
System		P4	•	0	•		272
electronic expansion valve failure U1		PJ	•	0	•	Faulty field setting after replacing main PC board or faulty combination of PC board	274
U2	System	U0	0	•	•	Low pressure drop due to refrigerant shortage or electronic expansion valve failure	275
U3 0 0 0 Check operation is not completed. U4 0 0 0 0 Malfunction of transmission between indoor and outdoor units U5 0 0 0 Malfunction of transmission between remote controller and indoor unit 0 0 Malfunction of transmission between remote controller and indoor unit 0 0 0 Malfunction of transmission between outdoor units 0 0 0 Malfunction of transmission between outdoor units 0 0 0 Malfunction of transmission between outdoor units 0 0 0 0 0 Malfunction of transmission between outdoor units 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		U1	•	0	•	Reverse phase / open phase	276
U4		U2	•	•	•	Power supply insufficient or instantaneous failure	277
U5		U3	•	0	•	Check operation is not completed.	280
U5		U4	•	0	•		281
U7 0 0 Malfunction of transmission between main and subremote controller U8 U9 0 0 Malfunction of transmission between main and subremote controller (malfunction of subremote controller) U9 0 0 Malfunction of transmission between main and subremote controller (malfunction of subremote controller) U9 0 0 Malfunction of transmission between indoor unit and outdoor unit in the same system UA UA 0 0 Malfunction of indoor and outdoor units, indoor units and remote controller UE 0 0 Malfunction of central remote controller UE 0 0 Malfunction of transmission between central remote controller and indoor unit UF 0 0 Malfunction of transmission between central remote controller and indoor unit VIII VI		U5	•	0	•		283
U8		U5	•	0	•	Failure of remote controller PC board or setting during control by remote controller	283
Leat Reclaim Ventilation Mark M		U7	•	0	•	Malfunction of transmission between outdoor units	284
Outdoor unit in the same system UA UA UB UC Address duplication of central remote controller UE UB UB UB UB UB UB UB UB UB		U8	•	•	•		286
Indoor units and remote controller UC		U9	•	0	•		287
UE		UA	•	•	•	Improper combination of indoor and outdoor units, indoor units and remote controller	288
Central Remote Controller and Schedule Timer Heat Reclaim Ventilation Heat Reclaim Ventilation Augusta Augu		UC	0	0	0	Address duplication of central remote controller	290
Description		UE	•	0	•		291
Central Remote Remote Controller and Schedule Timer M8 ○ or ● ○ ○ Malfunction of transmission between optional controllers for centralized control 29 MA ○ or ● ○ ○ Malfunction of transmission between optional controllers for centralized control 29 MA ○ or ● ○ ○ Improper combination of optional controllers for centralized control 30 MC ○ or ● ○ ○ Address duplication, improper setting 30 Heat Reclaim Ventilation 64 ○ ● ○ Indoor unit's air thermistor error - 6A ○ ● ○ Damper system alarm - 6A ○ ● ○ Damper system + thermistor error - 6F ○ ● Malfunction of simple remote controller - 6H ○ ● Malfunction of door switch or connector -		UF	•	0	•	Refrigerant system not set, incompatible wiring / piping	294
Remote Controller and Schedule Timer M8 Or Or Malfunction of transmission between optional controllers for centralized control MA Or Malfunction of transmission between optional controllers for centralized control MC Or Malfunction of optional controllers for centralized control MC Or Malfunction, improper setting Malfunction of optional controllers for centralized control MC Or Malfunction of optional controllers for centralized control MC Or Malfunction of optional controllers for centralized control MC Or Malfunction of optional controllers for centralized control MC Or Malfunction of simple remote controller MB Or Malfunction of door switch or connector MAlfunction of door switch or connector		UH	•	0	•	Malfunction of system, refrigerant system address undefined	295
And Schedule Timer MA Or Improper combination of optional controllers for centralized control MC Or Improper combination of optional controllers for centralized control MC Address duplication, improper setting Indoor unit's air thermistor error Indoor unit's air thermistor error Outside air thermistor error Address duplication, improper setting Outside air thermistor error Damper system alarm And And And And And And And And Andress duplication, improper setting MA MB MA Or MC Or MC Or MC Or Or Or Or Or Or Or Or Or O	Remote	M1	○ or •	•	•	Central remote controller PC board defect Schedule timer PC board defect	297
Timer MA Or Improper combination of optional controllers for centralized control MC Or MC Address duplication, improper setting Address duplication, improper setting Indoor unit's air thermistor error Outside air thermistor error Outside air thermistor error Address duplication, improper setting Outside air thermistor error Damper system alarm Address duplication, improper setting MA Malfunction of simple remote controller Malfunction of door switch or connector Malfunction of door switch or connector	and	M8	○ or •	•	•		298
Heat Reclaim Ventilation Heat Reclaim Venti		MA	○ or •	0	•	Improper combination of optional controllers for centralized control	300
Reclaim Ventilation 65 6A 6A 6A 6B 6B 6B 6B 6B 6B 6B		MC	o or ●	0	•	Address duplication, improper setting	302
Ventilation 6A		64	0	•	•	Indoor unit's air thermistor error	_
6A		65	0	•	•	Outside air thermistor error	_
6F	Vontation	6A	0	•	•	Damper system alarm	_
6H O Malfunction of door switch or connector –		6A	•	•	•	Damper system + thermistor error	_
		6F	0	•	•	Malfunction of simple remote controller	_
04 a Internal transmission error		6H	0	•	•	Malfunction of door switch or connector	_
		94	•	0	•	Internal transmission error	_

The system operates for malfunction codes indicated in black squares, however, be sure to check and repair.

Malfunction code indication by outdoor unit PC board

<Monitor mode>

To enter the monitor mode, push the MODE (BS1)]button when in "Setting mode 1".

* Refer to P.184 for Monitor mode.

<Selection of setting item>

Push the SET (BS2) button and set the LED display to a setting item.

* Refer to P.184 for Monitor mode.

<Confirmation of malfunction 1>

Push the RETURN (BS3) button once to display "First digit" of malfunction code.

<Confirmation of malfunction 2>

Push the SET (BS2) button once to display "Second digit" of malfunction code.

Detail

on next page.

description

<Confirmation of malfunction 3>

Push the SET (BS2) button once to display "malfunction location".

<Confirmation of malfunction 4>

Push the <u>SET (BS2)</u> button once to display "master or slave 1 or slave 2" and "malfunction location".

Push the RETURN (BS3) button and switches to the initial status of "Monitor mode".

* Push the MODE (BS1) button and returns to "Setting mode 1".

Contents of	f malfunction	Malfunction code
Abnormal discharge pressure	HPS activated	E3
Abnormal suction pressure	Abnormal Pe	E4
Compressor lock	Detection of INV compressor lock	E5
Activation of OC	Detection of STD1 compressor lock	E6
	Detection of STD2 compressor lock	
Over load, over current,	Instantaneous over current of DC fan 1 motor	E7
abnormal lock of outdoor unit fan motor	Detection of DC fan 1 motor lock	
	Instantaneous over current of DC fan 2 motor	
	Detection of DC fan 2 motor lock	
Malfunction of electronic expansion	EV1	E9
valve	EV2	
	EV3	
Abnormal position signal of outdoor	Abnormal position signal of DC fan 1 motor	H7
unit fan motor	Abnormal position signal of DC fan 2 motor	
Faulty sensor of outdoor air	Faulty Ta sensor (short)	H9
temperature	Faulty Ta sensor (open)	
Abnormal discharge pipe temperature	Abnormal Td	F3
Abnormal heat exchanger temperature	Refrigerant over charge	F6
Faulty current sensor	Faulty CT1 sensor	J2
	Faulty CT2 sensor	
Faulty sensor of discharge pipe	Faulty Tdi sensor (short)	J3
temperature	Faulty Tds1 sensor (short)	
	Faulty Tds2 sensor (short)	
	Faulty Tdi sensor (open)	
	Faulty Tds1 sensor (open)	
	Faulty Tds2 sensor (open)	
Faulty sensor of suction pipe	Faulty Ts1 sensor (short)	J5
temperature	Faulty Ts1 sensor (open)	
	Faulty Ts2 sensor (short)	
	Faulty Ts2 sensor (open)	
Faulty sensor of heat exchanger	Faulty Tb sensor (short)	J6
temperature	Faulty Tb sensor (open)	
Malfunction of the liquid pipe temperature sensor	Faulty TI sensor (short)	J7
temperature sensor	Faulty TI sensor (open)	
Faulty sensor of subcool heat exchanger temperature	Faulty Tsh sensor (short)	J9
exonanger temperature	Faulty Tsh sensor (open)	
Faulty sensor of discharge pressure	Faulty Pc sensor (short)	JA
	Faulty Pc sensor (open)	
Faulty sensor of suction pressure	Faulty Pe sensor (short)	JC
	Faulty Pe sensor (open)	
Instantaneous power failure	*NO display on remote controller (Judge during compressor operation)	(L2)
Inverter radiation fin temperature rising	Over heating of inverter radiation fin temperature	L4
DC output over current	Inverter instantaneous over current	L5
	IGBT malfunction	L5
Electronic thermal	Electronic thermal switch 1	L8
	Electronic thermal switch 2	
	Out-of-step	
	Speed down after startup	
	Lightening detection	
Stall prevention (Limit time)	Stall prevention (Current increasing)	L9
	Stall prevention (Faulty start up)	
	Abnormal wave form in startup	
	Out-of-step	
Transmission error between inverter and outdoor unit	Inverter transmission error	LC

 \bigcirc : ON \bullet : OFF \bullet :Blink

Mathematical Continuation of mathematical			Confin	motion	of m	olfun	otion	1		Confir	motion	a of n	aalfun	otion	2		Confir	motio	n of m	olfur	otion	2	_	O:			OFF	① :Blink
S	Malfunction code		_			_		_							_		_			_	,						_	
E6 E7 E8			1121	TIOF						1121	ПОГ						1125	ПОГ						1121	ПОГ			TIOF TITE
E9 E9 F7 F8		•					•						-								+ -			1			-	
E9 E9 B9 B9 B9 B9 B9 B9 B9 B9												_			_				_		1		_			_	_	
E7												_				_					+						_	
E7 E9 10 10 10 10 10 10 10 10 10 1													•	•	•						+						_	
E9	E7												-	_	_						+	-						
E9	⊏/												•	•	•						+							*1
E9																					+		-				•	
F3																					+					_	•	
H7 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	En											_			_				_				_			•	•	
H7 9 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E9											•	•	•	•						+		-			•	•	
H9																			_	_	+ -		-			_		
He had be left at the second of the left at the left a	117	_			_	_			_						_				_	_	+ -	1	_				_	
F3	П/	•			•	•	•	•				•	•	•	•						+							
F3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	LIO								_			•		_	_						1						_	*1
F3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	пэ											•	•	•	•						+					<u> </u>		
F6	Ε0.	_				_		_	_			_		_	_	_							_			_	_	4
J2		•			•	•	•	0					-								+ -	1					_	
JS		_				_	_	_						_	_					_	1						_	0 0
JS	J2	0			•	•	0	•				•	•	0	•			 			1		-				_	
J5 J6 J7 J7 J7 JA J8 J8 J8 J8 J8 J8 J8 J8 J8	10								_			_	_	_	_						+							
J5 J6 J7 J7 J9 J0 J0 J0 J0 J0 J0 J0 J0 J0	J3								•			•	•	•	•					_			_					
J5 J6 J7 J7 J9 J9 J0 J0 J0 J0 J0 J0 J0 J0																					1							
J5 J6 J7 J7 J9 J9 JA JC JC JC JC JC JC JC JC JC																					1		-				_	
J5 J6 J7 J7 J9 J9 J9 J0																		-	_			1				•		
J5 J6 J7 J7 J9 J0 J0 J0 J0 J0 J0 J0 J0 J0																			•	•	•						•	
J6																					+	1					•	
Color Colo	J5								•			•	•	•	•					•	1					•	•	
J6 J7 J9 J9 JA JC																			•	•	+					•	_	
J7 J9 JA JC O O O O O O O O O O O O O																			•	•	•	-	_			•		*1
J7 J9 JA JC (L2) JC L4 L5 L5 L8 L9 L9 L9 L9 L9 L9 L9 L9 L9																_			•	•	+	•	_			•	•	
J7 J9 JA JA L2 L3 L4 L5 L5 L8 L9	J6								•			•	•	•	•				•	•	•	•				•	•	
J9																			•	•	1	•				•	•	
J9 JA JC (L2) J J J J J J J J J J J J J J J J J J J	J7								•			•	•	•	•	•			•	•	•	•	•			•	•	
JA JC UL2) JO JO JO JO JO JO JO JO JO J																•			•	•	•	•				•	•	
JA JC L2 JC JC JC JC JC JC JC JC JC J	J9								•			•	•	•	•	•			•	•	•	•	•			•	•	
C																			•	•	•	•				•	•	
C	JA								•			•	•	•	•				•	•	•		_			•	•	
(L2)																			•	•	•	•		1		•	•	
(L2)	JC								•			•	0	•	•					_	-		_	1			_	
L4 L5 L5 L8 L9 A A A A A A A A A A A A A A A A A A A										ļ								ļ	_	•	+ -					-	_	
L5 L5 L8 L9 L9 L5 L5 L8 L8 L8 L8 L8 L8 L8 L8	(L2)	•			•	•	•	•	•			•	•	•	•	•			•	•	•	•	•			•	•	
L5 L5 L8 L9 L9 L5 L5 L8 L8 L8 L8 L8 L8 L8 L8	14								•				0			^							•					
L5 L8 L9 L9 L5 L8										1											+	-		1			_	
L9															•						1			1			_	
L9									_			•								_	+						_	
L9	LO											•								•	+						_	
L9																							•					
L9																_							•			•		*1
L9 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0																		<u> </u>		_	1			1-		_		
3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	1.0								_	-		_						<u> </u>		Ť	+	1		-		<u> </u>	•	
	L9											0	•		0	1				•	•	•	0			•		
																L_		-					_	-				
																					+							
	10								_	-								-		_	+			-		_		
	LC								•			•	0	•	•	•			•	•	•	•	•			•	0	
Display of contents of Display of contents of Display 4 of Display 0 of							γ <u></u>							γ							<u> </u>			1	1			

Display of contents of malfunction (first digit)

Display of contents of malfunction (second digit)

Display 1 of malfunction in detail

Display 2 of malfunction in detail

Molfunction

<Monitor mode>

To enter the monitor mode, push the MODE (BS1) button when in "Setting mode 1".

* Refer to P.184 for Monitor mode.

<Selection of setting item>

Push the SET (BS2) button and set the LED display to a setting item.

Refer to P.184 for Monitor mode.

<Confirmation of malfunction 1>

Push the RETURN (BS3) button once to display "First digit" of malfunction code.

<Confirmation of malfunction 2>

Push the SET (BS2) button once to display "Second digit" of malfunction code.

Detail

on next page.

description

<Confirmation of malfunction 3>

Push the SET (BS2) button once to display "malfunction location".

<Confirmation of malfunction 4>

Push the SET (BS2) button once to display "master or slave 1 or slave 2" and "malfunction location".

Push the RETURN (BS3) button and switches to the initial status of "Monitor mode".

* Push the MODE (BS1) button and returns to "Setting mode 1".

Contents of	malfunction	Malfunction code
Open phase/Power supply imbalance	Imbalance of inverter power supply voltage	P1
Faulty temperature sensor inside switch box	Faulty thermistor of inverter box	P3
Faulty temperature sensor of inverter radiation fin	Faulty thermistor of inverter fin	P4
Incorrect combination of Inverter and	Incorrect combination of inverter	PJ
fan driver	Incorrect combination of fan driver 1	
	Incorrect combination of fan driver 2	
Gas shortage	Gas shortage alarm	U0
Reverse phase	Reverse phase error	U1
Abnormal power supply voltage	Insufficient Inverter voltage	U2
	Inverter open phase (phase T)	
	Charging error of capacitor in inverter main circult	
No implementation of test-run		U3
Transmission error between indoor	I/O transmission error	U4
and outdoor unit	I/O transmission error	
Transmission error between outdoor	Sequential startup ADP alarm	U7
units, transmission error between thermal storage units, duplication of IC	Sequential startup ADP malfunction	U7
address	Malfunction of transmission between multi units (Multi 1)	
	Malfunction of transmission between multi units (Multi 2)	
	Abnormal multi horsepower setting	
	Abnormal multi address setting	
	Excessive multi connections	
	Multi system malfunction	
Transmission error of other system	Indoor unit system abnormal in other system or other indoor unit system abnormal in own system	U9
Erroneous field setting	System transmission malfunction	UA
	Overconnection malfunction of indoor units	
	Malfunction of field setting	
	Refrigerant abnormal	
	Multi-ID abnormal	
	Alarm of TSS field setting	UA
	Alarm of CT address setting	
Faulty system malfunction	Wiring error (Auto-address error)	UH
Transmission error in accessory	Malfunction of multi-level connection	UJ
devices	Alarm of multi-level connection	UJ
Conflict in wiring and piping, no setting	Conflict in wiring and piping	UF

Contanto of malfunction

		code
Open phase/Power supply imbalance	Imbalance of inverter power supply voltage	P1
Faulty temperature sensor inside switch box	Faulty thermistor of inverter box	P3
Faulty temperature sensor of inverter radiation fin	Faulty thermistor of inverter fin	P4
Incorrect combination of Inverter and	Incorrect combination of inverter	PJ
fan driver	Incorrect combination of fan driver 1	
	Incorrect combination of fan driver 2	
Gas shortage	Gas shortage alarm	U0
Reverse phase	Reverse phase error	U1
Abnormal power supply voltage	Insufficient Inverter voltage	U2
	Inverter open phase (phase T)	
	Charging error of capacitor in inverter main circult	
No implementation of test-run		U3
Transmission error between indoor	I/O transmission error	U4
and outdoor unit	I/O transmission error	
Transmission error between outdoor	Sequential startup ADP alarm	U7
units, transmission error between thermal storage units, duplication of IC	Sequential startup ADP malfunction	U7
address	Malfunction of transmission between multi units (Multi 1)	
	Malfunction of transmission between multi units (Multi 2)	
	Abnormal multi horsepower setting	
	Abnormal multi address setting	
	Excessive multi connections	
	Multi system malfunction	
Transmission error of other system	Indoor unit system abnormal in other system or other indoor unit system abnormal in own system	U9
Erroneous field setting	System transmission malfunction	UA
	Overconnection malfunction of indoor units	
	Malfunction of field setting	
	Refrigerant abnormal	
	Multi-ID abnormal	
	Alarm of TSS field setting	UA
	Alarm of CT address setting	
Faulty system malfunction	Wiring error (Auto-address error)	UH
Transmission error in accessory	Malfunction of multi-level connection	UJ
devices	Alarm of multi-level connection	UJ
Conflict in wiring and piping, no setting for system	Conflict in wiring and piping	UF

Malfunction	С	onfire	natior	n of m	nalfun	ction	1	(Confir	matio	n of m	nalfun	ction	2	(Confir	matio	n of m	nalfun	ction	3	(Confir	matio	n of m	nalfun	ction -	4
	H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H1P	H2P	НЗР	H4P	H5P	H6P	H7P	H1P	H2P	НЗР	H4P	H5P	H6P	H7P
P1	•			0	•	•	•	•			•	•	•	•	•			•	•	•	•	•			•	•		
P3								•			•	•	•	•	•			•	•	•	•	•			•	•		
P4								•			•	•	•	•	•			•	•	•	•	•			•	•	*	1
PJ								•			•	•	•	•	•			•	•	•	•	•			•	•		
															•			•	•	•	•	•			•	•		
															•			•	•	•	•	•			•	•		
U0	•			•	•	•	•	•			•	•	•	•	•			•	•	•	•	•			•	•	•	•
U1								•			•	•	•	•	•			•	•	•	•	•			•	•		
U2								•			•	•	•	•	•			•	•	•	•	•			•	•		
															•			•	•	•	•	•			•	•		
U3								•			•	•	•	•	•			•	•	•	•	•			•	•	•	•
															•			•	•	•	•	•			•	•	•	•
U4								•			•	•	•	•	•			•	•	•	•	•			•	•	•	•
															•			•	•	•	•	•			•	•	•	•
U7								•			•	•	•	•	•			•	•	•	•	•			•	•	•	•
U7															•			•	•	•	•	•			•	•	•	•
															•			•	•	•	•	•			•	•	•	•
															•			•	•	•	•	0			0	•	•	•
															•			•	•	•	•	•			•	•	•	•
															•			•	•	•	•	•			•	•	•	•
															0			•	•	•	0	0			0	•	0	0
U9								•			•	•	•	•	0			•	•	•	•	0			•	•	0	0
UA								0			•	•	•	•	•			•	•	•	•				•	•	•	•
UA															•			•	•	•	•	0			•	•	0	0
															0			•	•	•	•	0			0	•	0	0
															0			•	•	•	0	0			•	•	0	0
															0			•	•	•	0	0			•	0	0	•
UA															0			•	•	•	0	0			0	•	0	•
															0			•	•	•	•	0			0	0	0	•
UH								•			•	•	•	•	•			•	•	•	•	•			•	•	•	•
UJ								•			0	•	•	•	•			•	•	•	•	•			•	•	*	1
UJ															•			•	•	•	•	•			•	•	*	1
UF								•			•	•	•	•	•			•	•	•	•	•			•	•	•	•

Display of contents of malfunction (first digit)

Display of contents of malfunction (second digit)

Display 1 of malfunction in detail

Display 2 of malfunction in detail

● ● Master
● ● Slave1
● ● Slave2
● ● System

3. Troubleshooting by Indication on the Remote Controller

3.1 "RO" Indoor Unit: Error of External Protection Device

Remote Controller Display R0

Applicable Models

All indoor unit models

Method of Malfunction Detection Detect open or short circuit between external input terminals in indoor unit.

Malfunction Decision Conditions When an open circuit occurs between external input terminals with the remote controller set to "external ON/OFF terminal".


Supposed Causes

- Actuation of external protection device
- Improper field set
- Defect of indoor unit PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



3.2 "8?" Indoor Unit: PC Board Defect

Remote Controller Display *R1*

Applicable Models

All indoor unit models

Method of Malfunction Detection

Check data from E2PROM.

Malfunction Decision Conditions

When data could not be correctly received from the E²PROM E²PROM: Type of nonvolatile memory. Maintains memory contents even when the power supply is turned off.


Supposed Causes

■ Defect of indoor unit PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



(V2777)

3.3 "A3" Indoor Unit: Malfunction of Drain Level Control System (S1L)

Remote
Controller
Display

83

Applicable Models

FXCQ, FXFQ, FXSQ, FXKQ, FXDQ, FXMQ, FXUQ, FXHQ (Option), FXMQ200,250M (Option), FXAQ (Option), FXMQ-MF (Option)

Method of Malfunction Detection


By float switch OFF detection


Malfunction Decision Conditions When rise of water level is not a condition and the float switch goes OFF.

Supposed Causes

- 220~240V power supply is not provided
- Defect of float switch or short circuit connector
- Defect of drain pump
- Drain clogging, upward slope, etc.
- Defect of indoor unit PC board
- Loose connection of connector

Troubleshooting





(V2778)

3.4 "86" Indoor Unit: Fan Motor (M1F) Lock, Overload

Remote Controller Display 88

Applicable Models

All indoor units

Method of Malfunction Detection


Detection by failure of signal for detecting number of turns to come from the fan motor

Malfunction Decision Conditions When number of turns can't be detected even when output voltage to the fan is maximum

Supposed Causes

- Fan motor lock
- Disconnected or faulty wiring between fan motor and PC board

Troubleshooting



3.5 "87" Indoor Unit: Malfunction of Swing Flap Motor (M1S)

Remote Controller Display 87

Applicable Models

FXCQ, FXHQ, FXKQ

Method of Malfunction Detection


Utilizes ON/OFF of the limit switch when the motor turns.

Malfunction Decision Conditions When ON/OFF of the microswitch for positioning cannot be reversed even though the swing flap motor is energized for a specified amount of time (about 30 seconds).

Supposed Causes

- Defect of swing motor
- Defect of connection cable (power supply and limit switch)
- Defect of air flow direction adjusting flap-cam
- Defect of indoor unit PC board

Troubleshooting



3.6 "89" Indoor Unit: Malfunction of Moving Part of Electronic Expansion Valve (Y1E)

Remote Controller Display 89

Applicable Models

All indoor unit models

Method of Malfunction Detection

Use a microcomputer to check the electronic expansion valve for coil conditions.

Malfunction Decision Conditions When the pin input of the electronic expansion valve is not normal while in the initialization of the microcomputer.


Supposed Causes

- Malfunction of moving part of electronic expansion valve
- Defect of indoor unit PC board
- Defect of connecting cable

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



(V2781)

*1: Coil check method for the moving part of the electronic expansion valve Disconnect the electronic expansion valve from the PC board and check the continuity between the connector pins.

(Normal)

Pin No.	1. White	2. Yellow	3. Orange	4. Blue	5. Red	6. Brown
1. White		×	O Approx. 300Ω	×	O Approx. 150Ω	×
2. Yellow			×	O Approx. 300Ω	×	O Approx. 150Ω
3. Orange				×	Ο Approx. 150Ω	×
4. Blue					×	O Approx. 150Ω
5. Red						×
6. Brown						

O: Continuity

x: No continuity

3.7 "8F" Indoor Unit: Drain Level above Limit

Remote Controller Display RF

Applicable Models

FXCQ, FXFQ, FXSQ, FXKQ, FXMQ, FXDQ, FXMQ-MF, FXUQ

Method of Malfunction Detection

Water leakage is detected based on float switch ON/OFF operation while the compressor is in non-operation.

Malfunction Decision Conditions

When the float switch changes from ON to OFF while the compressor is in non-operation.


Supposed Causes

- Humidifier unit (optional accessory) leaking
- Defect of drain pipe (upward slope, etc.)
- Defect of indoor unit PC board

A humidifier unit (optional accessory) is installed on the indoor unit.

ŃΟ

Troubleshooting



YES

Check if the humidifier unit is leaking.

Defect of indoor unit PC board.

(V2782)

3.8 "AJ" Indoor Unit: Malfunction of Capacity Determination Device

Remote controller display

RJ

Applicable Models

All indoor unit models

Method of Malfunction Detection

Capacity is determined according to resistance of the capacity setting adaptor and the memory inside the IC memory on the indoor unit PC board, and whether the value is normal or abnormal is determined.

Malfunction Decision Conditions


Operation and:


When the capacity code is not contained in the PC board's memory, and the capacity setting adaptor is not connected.

Supposed Causes

- You have forgotten to install the capacity setting adaptor.
- Defect of indoor unit PC board

Troubleshooting





(V2783)

3.9 "[4" Indoor Unit: Malfunction of Thermistor (R2T) for Heat Exchanger

Remote Controller Display LA

Applicable Models

All indoor unit models

Method of Malfunction Detection

Malfunction detection is carried out by temperature detected by heat exchanger thermistor.

Malfunction Decision Conditions When the heat exchanger thermistor becomes disconnected or shorted while the unit is running.


Supposed Causes

- Defect of thermistor (R2T) for liquid pipe
- Defect of indoor unit PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.10 "[5" Indoor Unit: Malfunction of Thermistor (R3T) for Gas Pipes

Remote Controller Display **E**5

Applicable Models

All indoor unit models

Method of Malfunction Detection

Malfunction detection is carried out by temperature detected by gas pipe thermistor.

Malfunction Decision Conditions When the gas pipe thermistor becomes disconnected or shorted while the unit is running.


Supposed Causes

- Defect of indoor unit thermistor (R3T) for gas pipe
- Defect of indoor unit PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.11 "[9" Indoor Unit: Malfunction of Thermistor (R1T) for Suction Air

Remote Controller Display [9

Applicable Models

All indoor unit models

Method of Malfunction Detection

Malfunction detection is carried out by temperature detected by suction air temperature thermistor.

Malfunction Decision Conditions When the suction air temperature thermistor becomes disconnected or shorted while the unit is running.


Supposed Causes

- Defect of indoor unit thermistor (R1T) for air inlet
- Defect of indoor unit PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.12 "[J" Indoor Unit: Malfunction of Thermostat Sensor in Remote Controller

Remote Controller Display ΓII

Applicable Models

All indoor unit models

Method of Malfunction Detection

Malfunction detection is carried out by temperature detected by remote controller air temperature thermistor. (Note:)

Malfunction Decision Conditions When the remote controller air temperature thermistor becomes disconnected or shorted while the unit is running.


Supposed Causes

- Defect of remote controller thermistor
- Defect of remote controller PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



(V2787)



In case of remote controller thermistor malfunction, unit is still operable by suction air thermistor on indoor unit.



* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.13 "El" Outdoor Unit: PC Board Defect

Remote Controller Display E1

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Check data from E2PROM


Malfunction Decision Conditions When data could not be correctly received from the E²PROM E²PROM: Type of nonvolatile memory. Maintains memory contents even when the power supply is turned off.

Supposed Causes

■ Defect of outdoor unit PC board (A1P)

Troubleshooting





(V3064)

3.14 "E3" Outdoor Unit: Actuation of High Pressure Switch

Remote Controller Display E3

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection Abnormality is detected when the contact of the high pressure protection switch opens.

Malfunction Decision Conditions Error is generated when the HPS activation count reaches the number specific to the operation

mode.

(Reference) Operating pressure of high pressure switch

Operating pressure: 4.0MPa Reset pressure: 2.85MPa


Supposed Causes

- Actuation of outdoor unit high pressure switch
- Defect of High pressure switch
- Defect of outdoor unit PC board
- Instantaneous power failure
- Faulty high pressure sensor


Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



- *1: Make a comparison between the voltage of the pressure sensor and that read by the pressure gauge.
 - (As to the voltage of the pressure sensor, make measurement of voltage at the connector, and then convert it to pressure according to information on page 367.)
- *2: Make a comparison between the high pressure value checked with the Service Checker and the voltage of the pressure sensor (see *1).
- *3: Make measurement of voltage of the pressure sensor.



3.15 "EY" Outdoor Unit: Actuation of Low Pressure Sensor

Remote
Controller
Display
A I! I. I.

EY

Applicable Models RXYQ5P~54P

Method of Malfunction Detection

Abnormality is detected by the pressure value with the low pressure sensor.

Malfunction Decision Conditions Error is generated when the low pressure is dropped under specific pressure. Operating pressure:0.07MPa


Supposed Causes

- Abnormal drop of low pressure (Lower than 0.07MPa)
- Defect of low pressure sensor
- Defect of outdoor unit PC board
- Stop valve is not opened.

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.




*1: Make a comparison between the voltage of the pressure sensor and that read by the pressure gauge.

(As to the voltage of the pressure sensor, make measurement of voltage at the connector, and then convert it to pressure according to information on page 367.)

*2: Make a comparison between the low pressure value checked with the Service Checker and the voltage of the pressure sensor (see *1).

*3: Make measurement of voltage of the pressure sensor.



Make measurement of DC voltage between these wires.

3.16 "E5" Outdoor Unit: Inverter Compressor Motor Lock

Remote Controller Display *E*5

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Inverter PC board takes the position signal from UVW line connected between the inverter and compressor, and the malfunction is detected when any abnormality is observed in the phase-current waveform.

Malfunction Decision Conditions This malfunction will be output when the inverter compressor motor does not start up even in forced startup mode.

Supposed Causes

- Inverter compressor lock
- High differential pressure (0.5MPa or more)
- Incorrect UVW wiring
- Faulty inverter PC board
- Stop valve is left in closed.

Troubleshooting



3.17 "E6" Outdoor Unit: STD Compressor Motor Overcurrent/ Lock

Remote Controller Display *E*6

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Detects the overcurrent with current sensor (CT).


Malfunction Decision Conditions Malfunction is decided when the detected current value exceeds the below mentioned value for 2 seconds.

400 V unit : 15.0 A

Supposed Causes

- Closed stop value
- Obstacles at the air outlet
- Improper power voltage
- Faulty magnetic switch
- Faulty compressor
- Faulty current sensor (A6P, A7P)

Troubleshooting



Note:

- *1 Abnormal case
- The current sensor value is 0 during STD compressor operation.
- The current sensor value is more than 15.0A during STD compressor stop.

3.18 "E7" Outdoor Unit: Malfunction of Outdoor Unit Fan Motor

Remote Controller Display *E*7

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Malfunction of fan motor system is detected according to the fan speed detected by hall IC when the fan motor runs.


Malfunction Decision Conditions

- When the fan runs with speed less than a specified one for 6 seconds or more when the fan motor running conditions are met
- When connector detecting fan speed is disconnected
- When malfunction is generated 4 times, the system shuts down.

Supposed Causes

- Malfunction of fan motor
- The harness connector between fan motor and PC board is left in disconnected, or faulty connector
- Fan does not run due to foreign matters tangled
- Clearing condition: Operate for 5 minutes (normal)






(V3077)


Note: Refer check 1 and 2 to P.311.

3.19 "E9" Outdoor Unit: Malfunction of Moving Part of Electronic Expansion Valve (Y1E, Y2E)

Remote Controller Display	E9
Applicable Models	RXYQ5P~54PY1
Method of Malfunction Detection	Check disconnection of connector Check continuity of expansion valve coil
Malfunction Decision Conditions	Error is generated under no common power supply when the power is on.
Supposed Causes	 Defect of moving part of electronic expansion valve Defect of outdoor unit PC board (A1P) Defect of connecting cable



*Make measurement of resistance between the connector pins, and then make sure the resistance falls in the range of 40 to 50Ω .



(V3067)

3.20 "F3" Outdoor Unit: Abnormal Discharge Pipe Temperature

Remote Controller Display FR

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Abnormality is detected according to the temperature detected by the discharge pipe temperature sensor.

Malfunction Decision Conditions When the discharge pipe temperature rises to an abnormally high level When the discharge pipe temperature rises suddenly

Supposed Causes


- Faulty discharge pipe temperature sensor
- Faulty connection of discharge pipe temperature sensor
- Faulty outdoor unit PC board

Troubleshooting



Pull out the discharge pipe thermistor from the outdoor PCB, and then make measurement of resistance using a multiple meter.

NO



(V3068)

refrigerant system.

Replace outdoor unit PC board

 $(A\dot{1}P).$

G

* Refer to "Thermistor Resistance / Temperature Characteristics" table on P366.

3.21 "F6" Outdoor Unit: Refrigerant Overcharged

Remote Controller Display F6

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Excessive charging of refrigerant is detected by using the outside air temperature, heat exchanging deicer temperature and liquid pipe temperature during a check run.

Malfunction Decision Conditions When the amount of refrigerant, which is calculated by using the outside air temperature, heat exchanging deicer temperature and liquid pipe temperature during a check run, exceeds the standard.

Supposed Causes


- Refrigerant overcharge
- Misalignment of the outside air thermistor
- Misalignment of the heat exchanging deicer thermistor
- Misalignment of the liquid pipe thermistor

Troubleshooting



Caution

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



(V2797)

L

* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.22 "H7" Outdoor Unit: Abnormal Outdoor Fan Motor Signal

Remote Controller Display H7

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Detection of abnormal signal from fan motor.

Malfunction Decision Conditions In case of detection of abnormal signal at starting fan motor.


Supposed Causes

- Abnormal fan motor signal (circuit malfunction)
- Broken, short or disconnection connector of fan motor connection cable
- Fan Inverter PC board malfunction

Troubleshooting



★1: Disconnect connector (X2A) and measure the following resistance.



3.23 "H3" Outdoor Unit: Malfunction of Thermistor (R1T) for Outdoor Air

Remote Controller Display **H9**

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Malfunction is detected from the temperature detected by the outdoor air thermistor.


Malfunction Decision Conditions When the outside air temperature thermistor has short circuit or open circuit.

Supposed Causes

- Defect of thermistor (R1T) for outdoor air
- Defect of outdoor unit PC board (A1P)

Troubleshooting







* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.24 "J⊋" Outdoor Unit: Current Sensor Malfunction

Remote Controller Display 2ل

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected according to the current value detected by current sensor.

Malfunction Decision Conditions

When the current value detected by current sensor becomes 5A or lower, or 40A or more during standard compressor operation.


Supposed Causes

- Faulty current sensor (A6P, A7P)
- Faulty outdoor unit PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



(V3071)

3.25 "J3" Outdoor Unit: Malfunction of Discharge Pipe Thermistor (R3, R31~33T)

Remote Controller Display **ЛЗ**

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected from the temperature detected by discharge pipe temperature thermistor.

Malfunction Decision Conditions When a short circuit or an open circuit in the discharge pipe temperature thermistor is detected.


Supposed Causes

- Defect of thermistor (R31T, R32T or R33T) for outdoor unit discharge pipe
- Defect of outdoor unit PC board (A1P)
- Defect of thermistor connection

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



The alarm indicator is displayed when the fan is being used also.

Note:

5 HP class ··· R3T

8~12 HP class ··· R31T, R32T

14, 16Hp class ··· R31T, R32T and R33T



* Refer to "Thermistor Resistance / Temperature Characteristics" table on P366.

3.26 "J5" Outdoor Unit: Malfunction of Thermistor (R2T), (R7T) for Suction Pipe

Remote Controller Display 45

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected from the temperature detected by the suction pipe temperature thermistor.

Malfunction Decision Conditions When a short circuit or an open circuit in the suction pipe temperature thermistor is detected.


Supposed Causes

- Defect of thermistor (R2T), (R7T) for outdoor unit suction pipe
- Defect of outdoor unit PC board (A1P)
- Defect of thermistor connection

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.27 "√5" Outdoor Unit: Malfunction of Thermistor (R4T) for Outdoor Unit Heat Exchanger

Remote Controller Display J8

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Malfunction is detected from the temperature detected by the heat exchanger thermistor.


Malfunction Decision Conditions When a short circuit or an open circuit in the heat exchange thermistor is detected.

Supposed Causes

- Defect of thermistor (R4T) for outdoor unit coil
- Defect of outdoor unit PC board (A1P)
- Defect of thermistor connection

Troubleshooting





(V3074)

* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.28 "J7" Outdoor Unit: Malfunction of Liquid Pipe Thermistor (R6T)

Remote Controller Display **ال**

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected according to the temperature detected by liquid pipe thermistor.

Malfunction Decision Conditions When the liquid pipe thermistor is short circuited or open.


Supposed Causes

- Faulty liquid pipe thermistor (R6T)
- Faulty outdoor unit PC board
- Defect of thermistor connection

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, aution or parts damage may be occurred.



(V3075)

st Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.29 "J9" Outdoor Unit: Malfunction of Subcooling Heat Exchanger Gas Pipe Thermistor (R5T)

Remote Controller Display J9

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Malfunction is detected according to the temperature detected by subcooling heat exchanger gas pipe thermistor.


Malfunction Decision Conditions When the subcooling heat exchanger gas pipe thermistor is short circuited or open.

Supposed Causes

- Faulty subcooling heat exchanger gas pipe thermistor (R5T)
- Faulty outdoor unit PC board

Troubleshooting





(V3075)



* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.30 "JR" Outdoor Unit: Malfunction of High Pressure Sensor

Remote Controller Display JЯ

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Malfunction is detected from the pressure detected by the high pressure sensor.


Malfunction Decision Conditions When the high pressure sensor is short circuit or open circuit.

Supposed Causes


- Defect of high pressure sensor system
- Connection of low pressure sensor with wrong connection.
- Defect of outdoor unit PC board.

Troubleshooting





*1: Voltage measurement point



*2: Refer to "Pressure Sensor, Pressure / Voltage Characteristics" table on P367.

3.31 "Jℂ" Outdoor Unit: Malfunction of Low Pressure Sensor

Remote Controller Display JE

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected from pressure detected by low pressure sensor.

Malfunction Decision Conditions When the low pressure sensor is short circuit or open circuit.


Supposed Causes

- Defect of low pressure sensor system
- Connection of high pressure sensor with wrong connection.
- Defect of outdoor unit PC board.


Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, **tion** or parts damage may be occurred.



*1: Voltage measurement point





*2: Refer to "Pressure Sensor, Pressure / Voltage Characteristics" table on P367.

3.32 "LY" Outdoor Unit: Malfunction of Inverter Radiating Fin Temperature Rise

Remote Controller Display 14

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection


Fin temperature is detected by the thermistor of the radiation fin.

Malfunction Decision Conditions When the temperature of the inverter radiation fin increases above 93°C.

Supposed Causes

- Actuation of fin thermal (Actuates above 93°C)
- Defect of inverter PC board
- Defect of fin thermistor


Troubleshooting



Be sure to turn off power switch before connect or disconnect connector,

- It is supposed that radiation fin temperature has risen due to on-site causes. Conduct the checks

 Conduct he checks
- shown below.Radiation fin for stains
- Airflow for interference
- Fan propeller for damage
- Whether or not outdoor temperature is too high



Inverter PCB for compressor



* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.33 "L5" Outdoor Unit: Inverter Compressor Abnormal

Remote Controller Display L5

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected from current flowing in the power transistor.

Malfunction Decision Conditions When an excessive current flows in the power transistor. (Instantaneous overcurrent also causes activation.)

Supposed Causes


- Defect of compressor coil (disconnected, defective insulation)
- Compressor start-up malfunction (mechanical lock)
- Defect of inverter PC board


Troubleshooting

Compressor inspection

(Cautio

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





3.34 "L8" Outdoor Unit: Inverter Current Abnormal

Remote Controller Display L8

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Malfunction is detected by current flowing in the power transistor.

Malfunction Decision Conditions

When overload in the compressor is detected. (Inverter secondary current 16.1A)


Supposed Causes


- Compressor overload
- Compressor coil disconnected
- Defect of inverter PC board
- Faulty compressor

Troubleshooting

Output current check

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





3.35 "L9" Outdoor Unit: Inverter Start up Error

Remote Controller Display 19

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

This malfunction code will be output if overcurrent occurs at the time of startup.

Malfunction Decision Conditions


When the startup control is failed.


When an overcurrent is passed to the inverter due to the malfunction of a compressor or electrical system.


Supposed Causes

- Defect of compressor
- Pressure differential start
- Defect of inverter PC board
- Failure to open the stop valve
- Faulty compressor connection

Troubleshooting







3.36 "Lt" Outdoor Unit: Malfunction of Transmission Between Inverter and Control PC Board

Remote Controller Display LE

Applicable Models

RXYQ5P~54P


Method of Malfunction Detection


Check the communication state between inverter PC board and control PC board by microcomputer.

Malfunction Decision Conditions When the correct communication is not conducted in certain period.

Supposed Causes

- Malfunction of connection between the inverter PC board and outdoor control PC board
- Defect of outdoor control PC board (transmission section)
- Defect of inverter PC board
- Defect of noise filter
- Faulty fan inverter
- Incorrect type of fan inverter
- Faulty compressor
- Faulty fan motor





3.37 "Pi" Outdoor Unit: Inverter Over-Ripple Protection

Remote Controller Display



Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Imbalance in supply voltage is detected in PC board.

Imbalance in the power supply voltage causes increased ripple of voltage of the main circuit capacitor in the inverter. Consequently, the increased ripple is detected.

Malfunction Decision Conditions

When the resistance value of thermistor becomes a value equivalent to open or short circuited status.

★ Malfunction is not decided while the unit operation is continued.
 "P1" will be displayed by pressing the inspection button.

When the amplitude of the ripple exceeding a certain value is detected for consecutive 4 minutes.


Supposed Causes

- Open phase
- Voltage imbalance between phases
- Defect of main circuit capacitor
- Defect of inverter PC board
- Defect of K2 relay in inverter PC board
- Improper main circuit wiring

supply, but the imbalance

in voltage recurs.

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector,

 $(\mathsf{Explanation}\,\mathsf{for}\,\mathsf{users}) *\mathsf{In}\,\mathsf{accordance}\,\mathsf{with}$ "notification of inspection results" accompanying spare parts.

Give the user a copy of "notification of inspection results" and leave it up to him to improve the imbalance.

Be sure to explain to the user that there is a "power supply imbalance" for which DAIKIN is not responsible.

> Replace the inverter PC board.

(V2816)

Troubleshooting 271

measure

3.38 "P4" Outdoor Unit: Malfunction of Inverter Radiating Fin Temperature Rise Sensor

Remote Controller Display PЧ

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Resistance of radiation fin thermistor is detected when the compressor is not operating.

Malfunction Decision Conditions When the resistance value of thermistor becomes a value equivalent to open or short circuited status.

★ Malfunction is not decided while the unit operation is continued.
 "P4" will be displayed by pressing the inspection button.


Supposed Causes


- Defect of radiator fin temperature sensor
- Defect of inverter PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.





Inverter PCB for compressor



* Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.

3.39 "PJ" Outdoor Unit: Faulty Field Setting after Replacing Main PC Board or Faulty Combination of PC Board

Remote Controller Display PJ

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

The faulty (or no) field setting after replacing PC board or faulty PC board combination is detected through communications with the inverter.

Malfunction Decision Conditions Whether or not the field setting or the type of the PC board is correct through the communication date is judged.


Supposed Causes

- Faulty (or no) field setting after replacing main PC board
- Mismatching of type of PC board

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



*Note) Type of PC board mismatching includes; Main PC board Inverter PC board (for compressor) Fan driver PC board

3.40 "UO" Outdoor Unit: Low Pressure Drop Due to Refrigerant Shortage or Electronic Expansion Valve Failure

Remote Controller Display UO.

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Short of gas malfunction is detected by discharge pipe temperature thermistor.

Malfunction Decision Conditions Microcomputer judge and detect if the system is short of refrigerant.

★Malfunction is not decided while the unit operation is continued.


Supposed Causes

- Out of gas or refrigerant system clogging (incorrect piping)
- Defect of pressure sensor
- Defect of outdoor unit PC board (A1P)
- Defect of thermistor R7T or R4T

Troubleshooting

Caution (

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



C

- *1: Refer to "Thermistor Resistance / Temperature Characteristics" table on P365.
- *2: Refer to "Pressure Sensor, Pressure / Voltage Characteristics" table on P367.

3.41 "Ul" Reverse Phase, Open Phase

Remote Controller Display 111

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

The phase of each phase are detected by reverse phase detection circuit and right phase or reverse phase are judged.

Malfunction Decision Conditions

When a significant phase difference is made between phases.


Supposed Causes

- Power supply reverse phase
- Power supply open phase
- Defect of outdoor PC board (A1P)

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



3.42 "U⊇" Outdoor Unit: Power Supply Insufficient or Instantaneous Failure

Remote Controller Display 112

Applicable Models

RXYQ5P~54P


Method of Malfunction Detection


Detection of voltage of main circuit capacitor built in the inverter and power supply voltage.

Malfunction Decision Conditions When the voltage aforementioned is not less than 780V or not more than 320V, or when the current-limiting voltage does not reach 200V or more or exceeds 740V.

Supposed Causes

- Power supply insufficient
- Instantaneous power failure
- Open phase
- Defect of inverter PC board
- Defect of outdoor control PC board
- Main circuit wiring defect
- Faulty compressor
- Faulty fan motor
- Faulty connection of signal cable





3.43 "U3" Outdoor Unit: Check Operation not Executed

Remote Controller Display *U3*

Applicable Models

RXYQ5P~54P

Method of Malfunction Detection

Check operation is executed or not

Malfunction Decision Conditions Malfunction is decided when the unit starts operation without check operation.


Supposed Causes

Check operation is not executed.

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



Press and hold BS4 on the outdoor master PCB for 5 seconds or more, or turn ON the local setting mode 2-3 to conduct a check operation.

Performs the chech operation again and completes the check operation.

When a leakage detection function is needed, normal operation of charging refrigerant must be completed. And then, start once again and complete a check operation.

(V3052)

3.44 "U4" Malfunction of Transmission Between Indoor Units

Remote Controller Display \overline{UY}

Applicable Models

All model of indoor unit RXYQ5P~54P


Method of Malfunction Detection

Microcomputer checks if transmission between indoor and outdoor units is normal.

Malfunction Decision Conditions When transmission is not carried out normally for a certain amount of time

Supposed Causes

- Indoor to outdoor, outdoor to outdoor transmission wiring F1, F2 disconnection, short circuit or wrong wiring
- Outdoor unit power supply is OFF
- System address doesn't match
- Defect of indoor unit PC board
- Defect of outdoor unit PC board



3.45 "U5" Indoor Unit: Malfunction of Transmission Between Remote Controller and Indoor Unit

Remote Controller Display U5

Applicable Models

All models of indoor units

Method of Malfunction Detection

In case of controlling with 2-remote controller, check the system using microcomputer is signal transmission between indoor unit and remote controller (main and sub) is normal.

Malfunction Decision Conditions


Normal transmission does not continue for specified period.

Supposed Causes

- Malfunction of indoor unit remote controller transmission
- Connection of two main remote controllers (when using 2 remote controllers)
- Defect of indoor unit PC board
- Defect of remote controller PC board
- Malfunction of transmission caused by noise


Troubleshooting

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



3.46 "U7" Indoor Unit: Malfunction of Transmission Between Outdoor Units

Remote Controller Display	U7							
Applicable Models	All models of indoor units							
Method of Malfunction Detection	Microcomputer checks if transmission between outdoor units.							
Malfunction Decision Conditions	When transmission is not carried out normally for a certain amount of time							
Supposed Causes	 Improper connection of transmission wiring between outdoor unit and external control adaptor for outdoor unit Improper connection of transmission wiring between outdoor units. Improper cool/heat selection Improper cool/heat unified address (outdoor unit, external control adaptor for outdoor unit) Defect of outdoor unit PC board (A1P) Defect of external control adaptor for outdoor unit 							



3.47 "U8" Indoor Unit: Malfunction of Transmission Between Main and Sub Remote Controllers

Remote Controller Display *U8*

Applicable Models

All models of indoor units

Method of Malfunction Detection


In case of controlling with 2-remote controller, check the system using microcomputer if signal transmission between indoor unit and remote controller (main and sub) is normal.


Malfunction Decision Conditions Normal transmission does not continue for specified period.

Supposed Causes

- Malfunction of transmission between main and sub remote controller
- Connection between sub remote controllers
- Defect of remote controller PC board

Troubleshooting





3.48 "U9" Indoor Unit: Malfunction of Transmission Between Indoor and Outdoor Units in the Same System

Remote Controller Display U9

Applicable Models

All models of indoor units

Method of Malfunction Detection

Detect the malfunction signal of any other indoor unit within the system concerned.

Malfunction Decision Conditions When the malfunction decision is made on any other indoor unit within the system concerned.


Supposed Causes

- Malfunction of transmission within or outside of other system
- Malfunction of electronic expansion valve in indoor unit of other system
- Defect of PC board of indoor unit in other system
- Improper connection of transmission wiring between indoor and outdoor unit

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



indicated by the malfunction code U9 is normal.
Check for the indoor unit of other system, and then conduct troubleshooting by diagnosis according to the Malfunction Code Flowchart.

3.49 "UR" Improper Combination of Indoor and Outdoor Units, Indoor Units and Remote Controller

Remote Controller Display *UR*

Applicable Models

All models of indoor unit

RXYQ5P~54P

Method of Malfunction Detection

A difference occurs in data by the type of refrigerant between indoor and outdoor units. The number of indoor units is out of the allowable range.


Malfunction Decision Conditions The malfunction decision is made as soon as either of the abnormalities aforementioned is detected.

Supposed Causes

- Excess of connected indoor units
- Defect of outdoor unit PC board (A1P)
- Mismatching of the refrigerant type of indoor and outdoor unit.
- Setting of outdoor PC board was not conducted after replacing to spare parts PC board.



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



* The number of indoor units that can be connected to a single outdoor unit system depends on the model of outdoor unit.

3.50 "UE" Address Duplication of Centralized Controller

Remote Controller Display UE

Applicable Models

All models of indoor unit Centralized controller

Method of Malfunction Detection

The principal indoor unit detects the same address as that of its own on any other indoor unit.

Malfunction Decision Conditions The malfunction decision is made as soon as the abnormality aforementioned is detected.

Supposed Causes

Address duplication of centralized controller

Troubleshooting



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.

The centralized address is duplicated.

Make setting change so that the centralized address will not be duplicated.

3.51 "UE" Malfunction of Transmission Between Centralized Controller and Indoor Unit

Remote
Controller
Display

UE

Applicable Models

All models of indoor units Centralized controller Schedule timer Intelligent Touch Controller

Method of Malfunction Detection


Microcomputer checks if transmission between indoor unit and centralized controller is normal.

Malfunction Decision Conditions When transmission is not carried out normally for a certain amount of time

Supposed Causes


- Malfunction of transmission between optional controllers for centralized control and indoor
 unit
- Connector for setting master controller is disconnected.

 (or disconnection of connector for independent / combined use changeover switch.)
- Failure of PC board for central remote controller
- Defect of indoor unit PC board



(V2822)

DIII-NET test run menu.



3.52 "UF" System is not Set yet

Remote Controller Display LIF

Applicable Models

All models of indoor units

RXYQ5P~54P

Method of Malfunction Detection


On check operation, the number of indoor units in terms of transmission is not corresponding to that of indoor units that have made changes in temperature.


Malfunction Decision Conditions The malfunction is determined as soon as the abnormality aforementioned is detected through checking the system for any erroneous connection of units on the check operation.

Supposed Causes

- Improper connection of transmission wiring between indoor-outdoor units and outdoor-outdoor units
- Failure to execute check operation
- Defect of indoor unit PC board
- Stop valve is left in closed

Troubleshooting





Note:

Wiring check operation may not be successful if carried out after the outdoor unit has been off for more than 12 hours, or if it is not carried out after running all connected indoor units in the fan mode for at least an hour.

3.53 "UH" Malfunction of System, Refrigerant System Address Undefined

Remote Controller Display UH

Applicable Models

All models of indoor units


RXYQ5P~54P

Method of Malfunction Detection Detect an indoor unit with no address setting.

Malfunction Decision Conditions The malfunction decision is made as soon as the abnormality aforementioned is detected.

Supposed Causes

- Improper connection of transmission wiring between indoor-outdoor units and outdoor-outdoor units
- Defect of indoor unit PC board
- Defect of outdoor unit PC board (A1P)



from other equipment.

4. Troubleshooting (OP: Central Remote Controller)

4.1 "fil" PC Board Defect

Remote Controller Display M

Applicable Models

Central remote controller

Schedule timer

Method of Malfunction Detection

Detect an abnormality in the DIII-NET polarity circuit.

Malfunction Decision Conditions When + polarity and - polarity are detected at the same time.

Supposed Causes

- Defect of central remote controller PC board
- Defect of Schedule timer PC board


Troubleshooting

Replace the central remote controller.



_

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.




4.2 "#8" Malfunction of Transmission Between Optional Controllers for Centralized Control

Remote Controller Display	M8					
Applicable Models	Central remote controller Intelligent Touch Controller Schedule timer					
Method of Malfunction Detection	Detect the malfunction according to DIII-NET transmission data. (The system will be automatically reset.)					
Malfunction Decision Conditions	When no master controller is present at the time of the startup of slave controller. When the centralized controller, which was connected once, shows no response.					
Supposed Causes	Malfunction of transmission between optional controllers for centralized control Defect of PC board of optional controllers for centralized control					



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.




4.3 "PR" Improper Combination of Optional Controllers for Centralized Control

Remote Controller Display	ПЯ					
Applicable Models	Central remote controller Intelligent touch controller Schedule timer					
Method of Malfunction Detection	Detect the malfunction according to DIII-NET transmission data.					
Malfunction Decision Conditions	When the schedule timer is set to individual use mode, other central component is present. When multiple master controller are present. When the remote control adapter is present.					
Supposed Causes	 Improper combination of optional controllers for centralized control More than one master controller is connected 					

■ Defect of PC board of optional controller for centralized control



Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



4.4 "MC" Address Duplication, Improper Setting

Remote Controller Display ME

Applicable Models

Central remote controller Schedule timer

Intelligent Touch Controller

Method of Malfunction Detection

Detect the malfunction according to DIII-NET transmission data.

Malfunction Decision Conditions


- Two or more units of central remote controllers and Intelligent Touch Controllers are connected, and all of them are set to master unit central setting or slave unit central setting.
- Two units of schedule timers are connected.

Supposed Causes

Address duplication of centralized controller

Troubleshooting

Be sure to turn off power switch before connect or disconnect connector, or parts damage may be occurred.



Master-Slave Unit Setting Table

Combination of Intelligent Touch Controller and Central Remote Controller



*	#1		#2		#3		#4	
Pattern	1-00~4-15	Master/ Slave	5-00~8-15	Master/ Slave	1-00~4-15	Master/ Slave	5-00~8-15	Master/ Slave
1)	CRC	Master	CRC	Master	CRC	Slave	CRC	Slave
2	CRC	Master	_	_	CRC	Slave	_	_
3	Intelligent Touch controller	Master	_	_	Intelligent Touch controller	Slave	_	_
4	CRC	Master	_	_	Intelligent Touch controller	Slave	_	_
(5)	Intelligent Touch controller	Master	_		CRC	Slave	_	
6	CRC	Master	_	_	_	_	_	_
7	Intelligent Touch controller	Master	_		_		_	

CRC: Central remote controller <DCS302C1>

Intelligent Touch controller: < DCS601C51) >

Master Unit Central Connector Setting Table The master unit central setting connector (CN1/X1A) is mounted at the factory.

- To independently use a single unit of the intelligent Touch controller or a single unit of the central remote controller, do not dismount the master unit central setting connector (i.e., use the connector with the factory setting unchanged).
- To independently use the schedule timer, insert an independent-use setting connector.
 No independent-use setting connector has been mounted at the factory. Insert the
 connector, which is attached to the casing of the main unit, in the PC board (CN1/X1A).
 (Independent-use connector=Master unit central setting connector)
- To use two or more central equipment in combination, make settings according to the table shown below.

	Central equipment connection pattern				Setting of master unit central setting connector(*2)				
Pattern	Intelligent Touch controller	Central remote controller	Unified ON/OFF controller	Schedule timer	Intelligent Touch controller	Central remote controller	Unified ON/OFF controller	Schedule timer	
1	1 to 2 units			× (*1)	Only a single unit: "Provided", Others: "Not provided"				
2				× (*1)					
3	1 unit	1 unit		× (*1) Provided Not provided	Not provided				
4	1 to 2 units		1 to 8 units	× (*1)	Only a single unit: "Provided", Others: "Not provided"		All "Not provided"		
5						Only a			
6		1 to 4	1 to 16	1 unit		single unit: "Provided",	All "Not	Not provided	
7		units	units			Others: "Not	provided"		
8				1 unit		provided"		Not provided	
9							Only a		
10			1 to 16 units	1 unit			single unit: "Provided", Others: "Not provided"	Not provided	
11)				1 unit				Provided	

(*1) The intelligent Touch controller and the schedule timer are not available for combined use.

^{*}The patterns marked with "*" have nothing to do with those described in the list of Setting of master unit central setting connector.


^(*2) The intelligent Touch controller, central remote controller, and the unified ON/OFF controller have been set to "Provided with the master unit central setting connector" at the factory. The schedule timer has been set to "Not provided with the master unit central setting connector" at the factory, which is attached to the casing of the main unit.

said place with continuity.

Procedures for Detecting Broken Wires in Transmission Wiring for Control

- 1. Procedure for checking outdoor-outdoor unit transmission wiring for broken wires On the system shown below, turn OFF the power supply to all equipment, short-circuit between the outdoor-outdoor unit terminal parts F1 and F2 in the "Outdoor Unit A" that is farthest from the central remote controller, and then conduct continuity checks between the transmission wiring terminal blocks F1 and F2 of the central remote controller using a multiple meter. If there is continuity between the said terminal blocks, the outdoor-outdoor unit transmission wiring has no broken wires in it.
 If there is no continuity, the transmission wiring may have broken wires. With the outdoor-outdoor unit terminal parts of the "Outdoor Unit A" short-circuited, conduct continuity checks between the transmission wiring terminal blocks F1 and F2 of the unified ON/OFF controller. If there is no continuity as well, conduct continuity checks between the outdoor-outdoor unit terminal parts of the "Outdoor Unit E", between the outdoor-outdoor unit terminal parts of the "Outdoor Unit D", between the outdoor-outdoor unit terminal parts of the "Outdoor Unit C", ... in the order described, thus identifying the place with continuity.
 If the place with continuity can be identified, there may be broken wires in places before the
- 2. Procedure for checking indoor-outdoor unit transmission wiring for broken wires (for checking the indoor-outdoor unit transmission wiring of the "Outdoor Unit C" for broken wires)

Turn OFF the power supply to all equipment, short-circuit between the indoor-outdoor unit terminal parts F1 and F2 in the "Outdoor Unit C, and then conduct continuity checks between the transmission wirings F1 and F2 of the "Indoor Unit a" that is farthest from the "Outdoor Unit C" using a multiple meter. If there is continuity between the said transmission wirings, the indoor-outdoor unit transmission wiring has no broken wires in it. If there is no continuity, the transmission wiring may have broken wires. With the indoor-outdoor unit terminal parts of the "Outdoor Unit C" short-circuited, identify the place with continuity in the transmission wiring of the "Indoor Unit b", transmission wiring of the "Indoor Unit c", and transmission wiring of the "Indoor Unit d" in the order described. If the place with continuity can be identified, there may be broken wires in places before the said place with continuity.



5. Troubleshooting (OP: Unified ON/OFF Controller)

5.1 Operation Lamp Blinks

Remote Controller Display Operation lamp blinks

Applicable Models

All model of indoor units
Unified ON/OFF controller

Method of Malfunction Detection

Detect the malfunction according to DIII-NET transmission data.


Malfunction Decision Conditions

Supposed Causes

- Malfunction of transmission between optional central controller and indoor unit
- Connector for setting master controller is disconnected
- Defect of unified ON/OFF controller PC board
- Defect of indoor unit PC board
- Malfunction of air conditioner

(V2841)

Troubleshooting



5.2 Display "Under Centralized Control" Blinks (Repeats Single Blink)

Remote Controller Display (Repeats single blink) "under centralized control"

Applicable Models

Unified ON/OFF controller

Central remote controller, Schedule timer

Method of Malfunction Detection

Detect the malfunction according to DIII-NET transmission data.

Malfunction Decision Conditions When the centralized controller, which was connected once, shows no response.

The control ranges are overlapped.

When multiple master central controller are present.


When the schedule timer is set to individual use mode, other central controller is present.


When the wiring adaptor for electrical appendices is present.

Supposed Causes

Address duplication of optional controllers for centralized control

- Improper combination of optional controllers for centralized control
- Connection of more than one master controller
- Malfunction of transmission between optional controllers for centralized control
- Defect of PC board of optional controllers for centralized control





5.3 Display "Under Centralized Control" Blinks (Repeats Double Blink)

Remote Controller Display · under centralized control" (Repeats double blink)

Applicable Models

Unified ON/OFF controller

Method of Malfunction Detection


Detect the malfunction according to DIII-NET transmission data.

Malfunction Decision Conditions When no central control addresses are set to indoor units. When no indoor units are connected within the control range.

Supposed Causes

- Central control address (group No.) is not set for indoor unit.
- Improper control range setting switch
- Improper wiring of transmission wiring


Troubleshooting



Check No. 1 Check on connector of fan motor (Power supply cable)

(1) Turn off the power supply.


Measure the resistance between phases of U,V,W at the motor side connectors (three-core wire) to check that the values are balanced and there is no short circuiting, while connector or relay connector is disconnected.



Check No. 2


- (1) Turn off the power supply.
- (2) Measure the resistance between Vcc and each phase of U,V,W, and GND and each phase at the motor side connectors (five-core wire) to check that the values are balanced within the range of ± 20 %, while connector or relay connector is disconnected.

Furthermore, to use a multiple meter for measurement, connect the probe of negative pole to Vcc and that of positive pole to GND.



[CHECK 3] Check for causes of rise in high pressure

Referring to the Fault Tree Analysis (FTA) shown below, probe the faulty points.




- *1: In cooling, it is normal if the outdoor unit electronic expansion valve (EV1) is fully open.
- *2: In heating, the indoor unit electronic expansion valve is used for "subcooled degree control". (For details, refer to "Electronic Expansion Valve Control" on page 135.)

SDK04009

[CHECK 4] Check for causes of drop in low pressure

Referring to the Fault Tree Analysis (FTA) shown below, probe the faulty points.



- *1: For details of the compressor capacity control while in cooling, refer to "Compressor PI Control" on page 95
- *2: The "low pressure protection control" includes low pressure protection control and hot gas bypass control. For details, refer to page 119.
- *3: In cooling, the indoor unit electronic expansion valve is used for "superheated degree control". (For details, refer to page 135.)
- *4: In heating, the outdoor unit electronic expansion valve (EV1) is used for "superheated degree control of outdoor unit heat exchanger". (For details, refer to page 107.)

SDK04009

314 Troubleshooting

Part 7 Appendix


1.	Piping Diagrams	316
	1.1 Outdoor Unit	
	1.2 Indoor Unit	320
2.	Wiring Diagrams for Reference	324
	2.1 Outdoor Unit	
	2.2 Field Wiring	329
	2.3 Indoor Unit	332
3.	List of Electrical and Functional Parts	348
	3.1 Outdoor Unit	348
	3.2 Indoor Side	351
4.	Option List	357
	4.1 Option List of Controllers	
	4.2 Option Lists (Outdoor Unit)	359
5.	Piping Installation Point	361
	5.1 Piping Installation Point	
	5.2 The Example of A Wrong Pattern	362
6.	Example of connection (R-410A Type)	363
7.	Thermistor Resistance / Temperature Characteristics	365
	Pressure Sensor	
	Method of Checking The Inverter's Power Transistors and	
٥.	Diode Modules	368

Piping Diagrams Si34-601A

1. Piping Diagrams

1.1 Outdoor Unit


RXYQ5PY1



3D050782

Si34-601A Piping Diagrams


RXYQ8P



3D050783

Piping Diagrams Si34-601A


RXYQ10P / 12PY1



3D050784

Si34-601A Piping Diagrams

RXYQ14P / 16P / 18PY1




3D050785

Piping Diagrams Si34-601A

1.2 Indoor Unit

FXCQ, FXFQ, FXKQ, FXSQ, FXMQ, FXHQ, FXAQ, FXLQ, FXNQ



DU220-602J


Code	Name	Code	Main function
(1)) Electronic expansion valve Y1E Used for gas superheate cooling operation or subclin heating operation.		Used for gas superheated degree control while in cooling operation or subcooled degree control while in heating operation.
(2)	Suction air temperature thermistor	R1T	Used for thermostat control.
(3)	Liquid pipe	R2T	Used for gas superheated degree control while in cooling operation or subcooled degree control while in heating operation.
(4)	Gas pipe	R3T	Used for gas superheated degree control while in cooling operation.

(mm)

		()
Capacity	GAS	Liquid
20 / 25 / 32 / 40 / 50M(A)	φ12.7	ф6.4
63 / 80 / 100 / 125M(A)	φ15.9	ф9.5
200M(A)	φ19.1	ф9.5
250M(A)	ф22.2	ф9.5

Si34-601A Piping Diagrams

FXZQ



Th1: Thermister for suction air temp.

Th2: Thermister for liquid line temp.

Th3: Thermister for gas line temp.

4D040157


■ Refrigerant pipe connection port diameters

(mm)

Model	Gas	Liquid
FXZQ20M / 25M / 32M / 40M / 50M	φ12.7	φ6.4

Piping Diagrams Si34-601A

FXDQ




4D043864H

■ Refrigerant pipe connection port diameters

(mm)

Model	Gas	Liquid
FXDQ20N(A), P / 25N(A), P / 32N(A), P / 40N(A) / 50N(A)VE(T)	φ12.7	φ6.4
FXDQ63N(A)VE(T)	φ15.9	φ9.5

FXMQ125MF / 200MF / 250MFV1



4D018650B

■ Refrigerant pipe connection port diameters


(mm)

		()
Model	Gas	Liquid
FXMQ125MFV1	φ15.9	φ9.5
FXMQ200MFV1	φ19.1	φ9.5
FXMQ250MFV1	φ22.2	φ9.5

Si34-601A Piping Diagrams


FXUQ + BEVQ

Indoor unit



4D037995F

Connection Unit






2. Wiring Diagrams for Reference


2.1 Outdoor Unit

RXYQ5PY1




050453G


RXYQ8PY1




RXYQ10PY1




RXYQ12PY1




RXYQ14P / 16P / 18PY1




RXYQ5P / 8P / 10P / 12P / 14P / 16P / 18PY1



RXYQ20P / 22P / 24P / 26P / 28P / 30P / 32PY1




RXYQ34P / 36P / 38P / 40P / 42P / 44P / 46P / 48P / 50P / 52P / 54PY1



2.3 Indoor Unit


FXCQ20M / 25M / 32M / 63MVE



3D039556A

3D039557A

FXCQ40M / 50M / 80M/ 125MVE



-O-:TERMINAL ADD.

AN EGROPTIONAL P.

AN ECONNECTOR FOR EUR ECORICAL APPROICES

VIECTORICAL APPROICES

V RECELVERZOISPLAY UNIT CO MIRELESS REMOTE CONTROLLER) X1 A Z P PRINTED CIRCUIT BOARD
A 3 P PRINTED CIRCUIT BOARD THERMISTOR(AIR) (MIF EMBEDDED)

SELECTOR SWITCH (WIRELESS ADDRESS SET)

SELECTOR SWITCH (MAIN/SUB)

551

MOTOR (SWING FLAP) MOTOR(INDOOR FAN)

M1S

THERMO SWITCH

_ ∑

CONNECTOR FOR OPTIONAL PART

LIGHT EMITTING DIODE LIGHT EMITTING DIODE

(ON-RED)

TIMER-GREEN)

LIGHT EMITTING DIODE

X 1 M | TERMINAL BLOCK(POWER) X 2 M | TERMINAL BLOCK(CONTROL)

LIGHT EMITTING DIODE

HAP

TRANSFORMER(220-240V/22

(SWING FLAP)

PRINTED CIRCUIT BOARD S 1 Q

1 P

LIGHT EMITTING DIODE (DEFROST-ORANGE) FILTER SIGN-RED)

SELECTOR SWITCH

WIRED REMOTE CONTROLLER

THERMISTOR(A)

EXPANSION VALVE

Y 1 E ELECTRONIC

(1R-K3R MAGNET IC RELAY(M1F) KAR MAGNET IC RELAY(M1S) (SERVICE MONITOR-GREEN)

MAGNETIC RELAY(M1P) MOTOR(DRAIN PUMP)

KPR

(MAIN/SUB)

oo, →: connector, NOTES)1. TITT : TERMINAL BLOCK, ===:FIELD WIRING

4, X23A IS CONNECTED WHEN THE WIRELESS REMOTE CONTROLLER KIT IS BEING USED. 3, IN CASE USING CENTRAL REMOTE CONTROLLER, CONNECT IT TO THE UNIT IN ACCORDANCE WITH THE ATTACHED INSTRUCTION MANUAL,


IN DETAILS, REFER TO THE INSTALLATION MANUAL ATTACHED THE UNIT, 6. SYMBOLS SHOWS AS FOLLOWS.

OPERATION CAN BE SELECTED BY REMOTE CONTROLLER.


PNK:PINK WHT:WHITE YLW:YELLOW ORG:ORANGE BLU:BLUE BLK:BLACK RED:RED BRN:BROWN GRN:GREEN

USE COPPER CONDUCTORS ONLY


FXFQ25M / 32M / 40M / 50M / 63M / 80M / 100M / 125MVE



FXZQ20M / 25M / 32M / 40M / 50M7V1B



FXKQ25MA / 32MA / 40MA / 63MAVE



BOARD

PRINTED CIRCUI

GRFFN

SERVICE MONITOR

EMITTING

LIGHT

CAPACITOR(M1F FUSE(F5A/250V

F1U

 C_1


FXDQ20P / 25P / 32P FXDQ20NA / 25NA / 32NA / 40NA / 50NA / 63NAVE (with Drain Pump)

WIRING CENTRAL TRANSMISSION WIRED REMOTE CONTROLLER NPUT FROM 3.IN CASE USING CENTRAL REMOTE CONTROLLER, CONNECT II IU THE UNTI IN ACCURDANCE WITH THE ATTENTAL AND CATALOGS, ETC. BEFORE CONNECTING.
4. REMOTE CONTROLLER MODEL VARIES ACCORDING TO THE COMBINATION SYSTEM, CONFIRM ENGINEERING MATERIALS AND CATALOGS, ETC. BEFORE CONNECTING.

7. """"" A CONTROLLER MODEL VARIES ACCORDING TO THE COMBINATION SYSTEM, CONTROL OPERATION CAN BE SELECTED BY REMOTE CONTROLLER. GRN:GREEN E H 551 \₩ ORG:ORANGE __WHT_ -BLU--∀LW--PNK--0RG- $2 \pm \frac{\text{WJY}}{\text{THW}}$ Z2C N=3 PNK:PINK 00 :X30A X18A VITR WHT:WHITE YLW:YELLOW PRP:PURPLE GRY:GRAY BLU:BLUE 000000 X16A \otimes НАР Д 9 (25A) KPR = 000 R1T X8A 31A: $\begin{array}{c} & & & \\ & &$ QQ THE INSTALLATION MANUAL ATTACHED THE UNIT, M \ ✓ HRED-HBLU--GRN- \Box S1L X2M Z 2H09 X2M⊕ X16A SYMBOLS SHOW AS FOLLOWS: RED: RED BLK: BLACK BOX POWER SUPPLY 220-2407 CONTROL 50HZ 18A AlP C 1 ×1M Z1C.Z2C|NOISE FILTER (FERRITE CORE SELECTOR SWITCH (MAIN/SU CONNECTOR(WIRING ADAPTOR FOR ELECTRICAL APPENDICES) CONNECTOR(ADAPTOR FOR WIRING WIRED REMOTE CONTROLLER OPTIONAL PART PHASE CONTROL CIRCU PROTECTOR(W1F EMBEI THERM | STOR (CO | L-2 ELECTRONIC EXPANSION VALVE TRANSFORMER(220V/22V MAGNETIC RELAY(M1P) THERMISTOR (COIL-1 MOTOR (DRAIN PUMP MOTOR (INDOOR FAN THERMISTOR (AIR THERMISTOR(AIR TERMINAL BLOCK REFER TO , ∰ : CONNECTOR FIELD WIRING TERMINAL : TERMINAL TERMINAL SWI FOR IN DETAILS, HERMAL FLOAT 00 VITR X16A X18A × M M_1 Ω 1 M \mathbb{Z}^{1} R2T S1L H H X2M Y 1 E \mathbb{R}^{1} R3T 551

3D045500C

FXDQ20P / 25P / 32P FXDQ20N / 25N / 32N / 40N / 50N / 63NVET (without Drain Pump)



3D049604A


LIGHT EMITTING

CAPACITOR(M1F FUSE(F5A/250V


F10

PRINTED


FXSQ20M / 25M / 32M / 40M / 50M / 63M / 80M / 100M / 125MVE




FXMQ40MA / 50MA / 63MA / 80MA / 100MA / 125MAVE




FXMQ200MA / 250MAVE




FXHQ32MA / 63MA / 100MAVE




FXAQ20MA / 25MA / 32MAVE / 40MA / 50MA / 63MAVE




FXLQ20MA / 25MA / 32MA / 40MA / 50MA / 63MAVE FXNQ20MA / 25MA / 32MA / 40MA / 50MA / 63MAVE



FXUQ71MA / 100MA / 125MAV1



FXMQ125MF / 200MF / 250MFV1



	INDOOR UNIT	X 1 M	TERMINAL BLOCK(POWER)
A1P	PRINTED CIRCUIT BOARD	X2M	TERMINAL BLOCK(CONTROL)
C1, C2	CAPACITOR(M1F)	ХЗМ	TERMINAL BLOCK
F1U	FUSE(B, 5A, 250V)(A1P)	X51A, X52A	CONNECTOR
HAP	LIGHT EMMITING DIODE	Y1E	ELECTRIC EXPANSION VALVE
	(SERVICE MONITOR-GREEN)	Y1S	SOLENOID VALVE(HOT GAS)
K1M	MAGNETIC RELAY(M1F)		
K1R	MAGNETIC RELAY(M1F)		OPTIONAL PARTS
KPR	MAGNETIC RELAY(M1P)	M1P	MOTOR(DRAIN PUMP)
KSR	MAGNETIC RELAY(Y1S)	S1L	FLOAT SWITCH(DRAIN PUMP)
M1F	MOTOR(FAN)		
Q1M	THERMAL PROTECTOR	WIRED REMOTE CONTROLLER	
	(M1F EMBEDDED 135%)	SS1	SELECT SWITCH(MAIN/SUB)
R1T	THERMISTOR(SUCTION AIR)		
R2T THERMISTOR(COIL, LIQUID)		CONNECTOR FOR OPTIONAL PARTS	
R3T	THERMISTOR(COIL, GAS)	X18A	CONNECTOR (WIRING ADAPTOR
R4T	THERMISTOR(DISCHARGE AIR)		FOR ELECTRICAL APPENDICES)
T1R	TRANSFORMAR(220-240V/22V)		

3D044996C

NOTES)

NOTES)

NOTES)

NOTES

S□:SHORT CIRCUIT CONNECTOR, □□:FIELD WIRING,


NOTES USING CENTRAL REMOTE CONTROLLER, CONNECT IT TO THE UNIT IN ACCORDANCE WITH THE ATTACHED INSTRUCTION MANUAL,

NOTES INSTALLING THE DRAIN PUMP KIT, REMOVE THE SHORT CIRCUIT CONNECTOR OF X8A AND EXECUTE THE ADDITIONAL WIRING FOR FLOAT SWITCH AND DRAIN PUMP,

NOTES CONNECTING THE INPUT WIRES FROM OUTSIDE, FORCED OFF OR ON/OFF CONTROL OPERATION CAN BE SELECTED BY REMOTE CONTROLLER, IN DETAILS, REFER TO THE INSTALLATION MANUAL ATTACHED TO THE UNIT.

DO NOT REMOVE SHORT CIRCUIT CONNECTOR OF X9A.

BEVQ71MA / 100MA / 125MAVE



2. = FIELD WIRING

3. THIS WIRING DIAGRAM ONLY SHOWS THE BEV UNIT. SEE THE WIRING DIAGRAMS AND INSTALLATION MANUALS FOR THE WIRING

AND SETTINGS FOR THE INDOOR, OUTDOOR, AND BS UNITS.

4. SEE THE INDOOR UNIT'S WIRING DIAGRAM WHEN INSTALLING OPTIONAL PARTS FOR THE INDOOR UNIT.

5. ONLY ONE INDOOR UNIT MAY BE CONNECTED TO THE BEV UNIT.

SEE THE INDOOR UNIT'S WIRING DIAGRAM FOR WHEN CONNECTING THE REMOTE CONTROL,

- 6. ALWAYS USE THE SKY AIR CONNECTION ADAPTER FOR THE INDOOR UNIT WHEN USING A CENTRAL CONTROL UNIT. REFER TO THE MANUAL ATTACHED THE UNIT WHEN CONNECTING.
- 7. COOL/HEAT CHANGEOVER OF INDOOR UNITS CONNECTED TO BEV UNIT CANNOT BE CARRIED OUT UNLESS THEY ARE CONNECTED TO BS UNIT.
- IN CASE OF A SYSTEM WITH BEV UNIT ONLY, COOL/HEAT SELECTOR IS REQUIRED.

 8. SET THE SS1 TO 'M' ONLY FOR THE BEV UNIT CONNECTED TO THE INDOOR UNIT WHICH IS TO HAVE
- COOL/HEAT SWITCHING CAPABILITY, WHEN CONNECTING THE BS UNIT. THE "M/S" ON THE SS1 STANDS FOR "MAIN/SUB". THIS IS SET TO "S" WHEN SHIPPED FROM THE FACTORY.
- 9. CONNECT THE ATTACHED THERMISTOR TO THE R3T.
- 1 O. SYMBOLS SHOW AS FOLLOWS.

(BLU:BLUE RED:RED WHT:WHITE BLK:BLACK)

3D044901B

3. List of Electrical and Functional Parts

3.1 Outdoor Unit

3.1.1 RXYQ5PY1~8PY1

Itom	Name		Symbol	Model	
Item				RXYQ5PY1	RXYQ8PY1
		Туре		JT1GCVDKYR@S	
	Inverter	Inverter OC protection device		14.7A	
		Туре			
Compressor	STD 1	OC protection device	M2C	_	
		Туре			
	STD 2	OC protection device	МЗС	_	
Fan motor OC protection device		M1F	1.15A	3A	
Electronic expansion valve (Main)			Y1E	Fully closed: 0pls	Fully open: 480pls
Electronic expansion valve (Subcool)			Y2E		Fully closed: 0pls Fully open: 480pls
		For M1C	S1PH	OFF: 4.0 $^{+0}_{-0.12}$ MPa ON: 3.0±0.15MPa	
Pressure protection	High pressure switch	For M2C	S2PH	_	_
		For M3C	S3PH	_	
	Low pressure	sensor	SLNPL	OFF: 0.07MPa	
Temperature	Discharge gas temperature protection (Discharge pipe thermistor)		R3T	OFF: 135°C	
protection			R1T	OFF: 93°C	
		For main PC	F1U	250V AC 10A Class B Time-lag 3.15A AC 250V	
Others	Fuse	board	F2U	250V AC 10A Class B T	ime-lag 3.15A AC 250V
		For Noise filter PC board	F1U	250V AC 5A Class B	

3.1.2 RXYQ10PY1~12PY1

lka na	Name		Symbol	Model	
Item				RXYQ10PY1	RXYQ12PY1
		Туре	M1C	JT1GCVDKYR@S	
	Inverter	OC protection device		14.7A	
		Туре	M2C	JT170G-KYE@T	
Compressor	STD 1	OC protection device		15.0A	
		Туре			
	STD 2	OC protection device	МЗС	_	
Fan motor OC protection device			M1F	3A	3A (for General overseas : 1.14A)
Electronic expa	nsion valve (Mair	n)	Y1E	Fully closed: 0pls	Fully open: 480pls
Electronic expa	nsion valve (Sub	cool)	Y2E	Fully closed: 0pls	Fully open: 480pls
		For M1C	S1PH	OFF: 4.0 ⁺⁰ _{-0.12} MPa	ON: 3.0±0.15MPa
Pressure protection	High pressure switch	For M2C	S2PH	OFF: 4.0 ⁺⁰ _{-0.12} MPa	ON: 3.0±0.15MPa
		For M3C	S3PH		
	Low pressure sensor		SLNPL	OFF: 0.07MPa	
Temperature	Discharge gas temperature protection (Discharge pipe thermistor)		R3T	OFF: 135°C	
protection	Inverter fin tem protection (Radiator fin th		R1T	OFF: 93°C	
		FOI IIIalli FC	F1U	250V AC 10A Class B 7	Fime-lag 3.15A AC 250V
Others	Fuse		F2U	250V AC 10A Class B 7	Fime-lag 3.15A AC 250V
0.11013	1 436	For Noise filter PC board	F1U	250V AC 5A Class B	

là a ma		la ma a	C: male al		Model			
Item	ľ	lame	Symbol	RXYQ14PY1	RXYQ16PY1	RXYQ18PY1		
		Туре			JT1GCVDKYR@S			
	Inverter	OC protection device	M1C		14.7A			
		Туре			JT170G-KYE@T			
Compressor	STD 1	OC protection device	M2C		15.0A			
		Туре			JT170G-KYE@T			
	STD 2	OC protection device	МЗС		15.0A			
Fan motor		OC protection device	M1F	1.1	4A	ЗА		
Electronic expa	nsion valve (Mair	n)	Y1E	Fully clos	sed: Opls Fully ope	n: 480pls		
Electronic expan	nsion valve (Sub	cool)	Y2E	Fully clos	sed: 0pls Fully ope	n: 480pls		
		For M1C	S1PH	OFF: 4.0	+0 -0.12 MPa ON: 3.0	±0.15MPa		
Pressure	High pressure switch	For M2C	S2PH	OFF: 4.0	+0 -0.12 MPa ON: 3.0			
protection	Owner	For M3C	S3PH		OFF: 4.0 ⁺⁰ 0.12 MPa ON: 3.0±0.15MPa			
	Low pressure :	sensor	SLNPL		OFF: 0.07MPa			
Temperature	Discharge gas protection (Discharge pip	•	R3T		OFF: 135°C			
protection	Inverter fin tem protection (Radiator fin th		R1T OFF: 93°C					
		For main PC	F1U	250V AC 10A	Class B Time-lag 3.	15A AC 250V		
Others	Fuse	board	F2U	250V AC 10A	Class B Time-lag 3.	15A AC 250V		
		For Noise filter PC board	F1U		250V AC 5A Class E	3		

3.2 Indoor Side

3.2.1 Indoor Unit

						Мо	del					
	Parts Name	Symbol	FXFQ25 MVE	FXFQ32 MVE	FXFQ40 MVE	FXFQ50 MVE	MVE MVE MVE MVE MVE RC1C62 Option					
Remote	Wired Remote Controller					BRC	1C62				Ontion	
Controller	Wireless Remote Controller					BRC7	E61W				Ориоп	
	Fan Motor	M1F			DC380V	30W 8P			DC 380V	120W 8P		
Motors	Drain Pump	M1P		FXFQ25 MVE FXFQ40 MVE FXFQ50 MVE FXFQ63 MVE FXFQ80 MVE FXFQ100 MVE FXFQ125 MVE BRC1C62 BRC7E61W								
	Swing Motor	M1S										
	Thermistor (Suction Air)	R1T			In PC boar	d A4P or w	rired remot	e controller				
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T										
	Thermistor (Heat Exchanger)	R2T	MP35HCA[3P007482-1]									
	Float Switch	S1L				FS-0	211B					
Others	Fuse	F1U				250V 5	δA φ5.2					
Others	Thermal Fuse	TFu				_	_					
	Transformer	T1R		AC220-240V (50Hz) AC220V (60Hz) PLD-12230DM Thermal Fuse 145°C MP35HCA[3P007482-1] Stepping Motor DC16V In PC board A4P or wired remote controller ST8605-5 φ8 L1000 20kΩ (25°C) ST8602A-5 φ6 L1000 20kΩ (25°C) FS-0211B								

						Мо	del				
	Parts Name	Symbol	FXCQ 20MVE	FXCQ 25MVE	FXCQ 32MVE	FXCQ 40MVE	FXCQ 50MVE	FXCQ 63MVE	FXCQ 80MVE	FXCQ 125MVE	Remark
Remote	Wired Remote Controller					BRC	1C62				Ontion
Controller	Wireless Remote Controller					BRC	7C62				Option
						AC 220~2	40V 50Hz				
	Fan Motor	M1F	1φ10W	1φ1	5W	1φ2	20W	1φ30W	1φ50W	1φ85W	
Matara				Thermal Fuse 152°C — Thermal protector 135°C : OFF 87°C : ON							
Motors	Drain Pump	M1P		AC220-240V (50Hz) AC220V (60Hz) PLD-12230DM Thermal Fuse 145°C MT8-L[3PA07509-1]							
	Swing Motor	M1S				MT8-L[3P AC200	A07509-1] ~240V				
	Thermistor (Suction Air)	R1T				ST8601-6 20kΩ	φ4 L1250 (25°C)				
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T				ST8605-6 20kΩ	φ8 L1250 (25°C)				
	Thermistor (Heat Exchanger)	R2T		ST8602A-5 φ6 L1000 20kΩ (25°C)							
	Float Switch	S1L		FS-0211B							
Others	Fuse	F1U				250V 5	δΑ φ5.2				
	Transformer	T1R				TR22l	H21R8				

				M	odel			
	Parts Name	Symbol	FXKQ 25MAVE	FXKQ 32MAVE	FXKQ 40MAVE	FXKQ 63MAVE	Remark	
Remote	Wired Remote Controller			BRO	C1C62		Option	
Controller	Wireless Remote Controller			BRO	C4C61			
				AC 220~	240V 50Hz			
	Fan Motor	M1F	1φ15W 4P 1φ20W 4P 1φ45W 4P Thermal Fuse 146°C Thermal protector 120°C : OFF 105°C : ON AC 220-240V (50Hz) PLD-12200DM					
			Thermal F	use 146°C	Thermal protector 12	20°C:OFF 105°C: N		
Motors	Drain Pump	M1P		PLD-1	2200DM ´			
	Swing Motor	M1S						
	Thermistor (Suction Air)	R1T						
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T						
	Thermistor (Heat Exchanger)	R2T						
	Float Switch	S1L		FS-0	0211B			
Others	Fuse	F1U		250V	5A φ5.2			
	Transformer	T1R	Thermal Fuse 146°C Thermal protector 120°C: OFF 105°C: ON AC 220-240V (50Hz)					

					Mo	del			
	Parts Name	Symbol	FXDQ 20N(A)VE(T), PVE(T)	FXDQ 25N(A)VE(T), PVE(T)	FXDQ 32N(A)VE(T), PVE(T)	FXDQ 40N(A)VE(T)	FXDQ 50N(A)VE(T)	FXDQ 63N(A)VE(T)	Remark
Remote	Wired Remote Controller				BRC	1C62			Option
Controller	Wireless Remote Controller				BRC	4C62			Оршоп
					AC 220~2	240V 50Hz			
	Fan Motor	M1F		1φ62W 1φ130W Thermal protector					
Motors					Thermal 130°C: OFF	protector =, 83°C: ON			
	Drain Pump	M1P			PLD-12	0V (50Hz) 2230DM use 145°C			*
	Thermistor (Suction Air)	R1T				φ4 L=250 (25°C)			
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T				φ8 L=800 (25°C)			
	Thermistor (Heat Exchanger)	R2T				4 φ6 L=800 (25°C)			
	Float Switch	S1L	_		FS-0	211E			*
Others	Fuse	F1U			250V 5	5A φ5.2			
	Transformer	T1R			TR22l	H21R8			

^{*}only for FXDQ20~63N(A)VE, FXDQ20~32PVE (with Drain Pump Type)

							Model					
	Parts Name	Symbol	FXSQ 20MVE	FXSQ 25MVE	FXSQ 32MVE	FXSQ 40MVE	FXSQ 50MVE	FXSQ 63MVE	FXSQ 80MVE	FXSQ 100MVE	FXSQ 125MVE	Remark
Remote	Wired Remote Controller						BRC1C62	2			•	Option
Controller	Wireless Remote Controller						BRC4C62	2				Option
						AC 2	20~240V	50Hz				
	Fan Motor	M1F		1¢50W		1¢65W	1φ85W	1φ125 W		1¢225W		
Motors				-	Thermal F	use 152°0			The 135°C :	rmal prote	ector 7°C : ON	
	Drain Pump	M1P				PL	20-240V (5 .D-12230[nal Fuse	OM				
	Thermistor (Suction Air)	R1T					601-4 φ4 l 0kΩ (25°0					
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T					605-7 φ8 L 0kΩ (25°0					
	Thermistor (Heat Exchanger)	R2T					02A-6 φ6 0kΩ (25°0					
	Float Switch	S1L		FS-0211B								
Others	Fuse	F1U				25	50V 5A φ5	.2				
	Transformer	T1R			•	Т	R22H21F	18		•		

						Мо	del				
	Parts Name	Symbol	FXMQ 40MAVE	FXMQ 50MAVE	FXMQ 63MAVE	FXMQ 80MAVE	FXMQ 100MAVE	FXMQ 125MAVE	FXMQ 200MAVE	FXMQ 250MAVE	Remark
Remote	Wired Remote Controller					BRC	1C62				Ontion
Controller	Wireless Remote Controller					BRC	4C62				Option
						AC 220~2	40V 50Hz				
	Fan Motor	M1F	1 φ100W 1 φ160W 1 φ270W 1 φ430W 1 φ380W×2 Thermal protector 135°C : OFF 87°C : ON					0W×2			
Motors				-	Thermal pro	otector 135	°C : OFF	87°C : O	V		
	Capacitor for Fan Motor	C1R		5μ F-400V		7μ F 400V	10μ F 400V	8μ F 400V	10μ F 400V	12μ F 400V	
	Thermistor (Suction Air)	R1T			ST8601A- 20kΩ					1A-13 -630	
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T			ST8605A- 20kΩ	4 φ8 L800 (25°C)				05A-5 1000	
	Thermistor (Heat Exchanger)	R2T			ST8602A- 20kΩ	4 φ6 L800 (25°C)				02A-6 1250	
	Float switch	S1L				FS-0	0211				
Others	Fuse	F1U	2	50V 5A φ5.	.2	25	50V 10A φ5	5.2	250\	/ 10A	
	Transformer	T1R				TR22l	H21R8				

				Model		
	Parts Name	Symbol	FXHQ 32MAVE	FXHQ 63MAVE	FXHQ 100MAVE	Remark
Remote	Wired Remote Controller			BRC1C62	•	Option
Controller	Wireless Controller			BRC7E63W		
			A	.C 220~240V/220V 50Hz/60I	Hz	
	Fan Motor	M1F	1 φ 6	3W	1¢130W	
Motors			Therma	I protector 130°C : OFF 8	0°C : ON	
Motoro	Capacitor for Fan Motor	C1R	3.0μF	-400V	9.0μF-400V	
	Swing Motor	M1S		MT8-L[3P058751-1] AC200~240V		
	Thermistor (Suction Air)	R1T		ST8601A-1 φ4 L250 20kΩ (25°C)		
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T		∮8 L = 1250 (25°C)	ST8605-6 φ8 L = 1250 20kΩ (25°C)	
	Thermistor (Heat Exchanger)	R2T		φ6 L = 1250 (25°C)	ST8602A-6 φ6 L = 1250 20kΩ (25°C)	
Others	Fuse	F1U		250V 5A φ5.2	•	
Ottleis	Transformer	T1R		TR22H21R8		

					Мс	odel				
	Parts Name	Symbol	FXAQ 20MAVE	FXAQ 25MAVE	FXAQ 32MAVE	FXAQ 40MAVE	FXAQ 50MAVE	FXAQ 63MAVE	Remark	
Remote	Wired Remote Controller				BRC	1C62			Ontion	
Controller	Wireless Remote Controller				BRC	7E618			Option	
					AC 220~2	240V 50Hz				
	Fan Motor	M1F		1¢40W 1¢43W						
Motors			Thermal protector 130°C : OFF 80°C : ON							
	Swing Motor	M1S	Thermal protector 130°C : OFF 80°C : ON MP24 [3SB40333-1]							
	Thermistor (Suction Air)	R1T				2 φ4 L400 (25°C)				
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T				2 φ8 L400 (25°C)				
	Thermistor (for Heat Exchanger)	R2T		ST8602-2 φ6 L400 20kΩ (25°C)						
Others	Float Switch	S1L		OPTION						
Others	Fuse	F1U			250V 5	5A φ5.2				

					Мо	del			
	Parts Name	Symbol	FXLQ 20MAVE	FXLQ 25MAVE	FXLQ 32MAVE	FXLQ 40MAVE	FXLQ 50MAVE	FXLQ 63MAVE	Remark
Remote	Wired Remote Controller				BRC	1C62			- Option
Controller	Wireless Remote Controller				BRC	4C62			Орион
					AC 220~2	40V 50Hz			
Motors	Fan Motor	M1F	1φ1	5W	1φ2	:5W	1φ3	5W	
IVIOIOIS				Thermal	protector 135°	C: OFF 12	0°C : ON		
	Capacitor for Fan Motor	C1R	1.0μF	-400V	0.5μF-400V	1.0μF-400V	1.5μF-400V	2.0μF-400V	
	Thermistor (Suction Air)	R1T			ST8601-6 20kΩ	φ4 L1250 (25°C)			
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T			ST8605-9 20kΩ	φ8 L2500 (25°C)			
	Thermistor (for Heat Exchanger)	R2T			ST8602A-9 20kΩ	9 φ6 L2500 (25°C)			
Others	Fuse	F1U			AC25	0V 5A			
Outers	Transformer	T1R			TR22l	H21R8			

					Мо	del			
	Parts Name	Symbol	FXNQ 20MAVE	FXNQ 25MAVE	FXNQ 32MAVE	FXNQ 40MAVE	FXNQ 50MAVE	FXNQ 63MAVE	Remark
Remote	Wired Remote Controller				BRC	1C62			Option
Controller	Wireless Remote Controller				BRC	4C62			Оршоп
					AC 220~2	40V 50Hz			
Motors	Fan Motor	M1F	1φ1	5W	1φ2	5W	1φ3	5W	
IVIOLOIS				Thermal	protector 135°	C:OFF 12	0°C : ON		
	Capacitor for Fan Motor	C1R	1.0μF	-400V	0.5μF-400V	1.0μF-400V	1.5μF-400V	2.0μF-400V	
	Thermistor (Suction Air)	R1T			ST8601-6 20kΩ	φ4 L1250 (25°C)			
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T			ST8605-9 20kΩ	φ8 L2500 (25°C)			
	Thermistor (for Heat Exchanger)	R2T			ST8602A-9 20kΩ				
Others	Fuse	F1U			AC25	0V 5A			
Olliers	Transformer	T1R			TR22H	H21R8			

	Davida Maria	Cumbal		Model		Domorile
	Parts Name	Symbol	FXUQ71MAV1	FXUQ100MAV1	FXUQ125MAV1	- Remark
Remote	Wired Remote Controller			BRC1C62		Ontion
Controller	Wireless Remote Controller			BRC7C528W		Option
				AC 220~240V 50Hz		
	Fan Motor	M1F	1φ45W	1φ9	90W	
			Thermal protector 130°C	Thermal protector 130	°C : OFF 83°C : ON	
Motors	Drain Pump	M1P	AC2	20-240V (50Hz) AC220V (60 PJV-1426	OHz)	
	Swing Motor	M1S		MT8-L[3PA07572-1] AC200~240V		
Thermistors	Thermistor (Suction Air)	R1T		ST8601-1 φ4 L=250 20kΩ (25°C)		
memilistors	Thermistor (Heat Exchanger)	R2T		ST8602A-4 φ6 L=800 20kΩ (25°C)		
Others	Float Switch	S1L		FS-0211B		

	Parts Name			Model		Damada		
			FXMQ125MFV1	FXMQ200MFV1	FXMQ250MFV1	Remark		
Remote	Wired Remote Controller		BRC1C62					
Controller	Wireless Remote Controller			_		Option		
				AC200~240V 50Hz				
	Fan Motor	M1F	1φ380W					
Motors			Thermal protector 135°C : OFF 87°C : ON					
	Capacitor for Fan Motor	C1R	10μ F 400V×2	10μ F 400V	16μ F 400V			
Solenoid valve	Solenoid valve (Hot gas)	Y1S	Co	Body: VPV-603D il: NEV-MOAJ532C1 AC220-2	40V			
	Thermistor (Suction Air)	R1T	ST8601-13 φ4 L=630 20kΩ (25°C)					
Thermistors	Thermistor (for Heat Exchanger High Temp.)	R3T	ST8605-6 φ8 L=1250 20kΩ (25°C)					
memisiois	Thermistor (Heat Exchanger)	R2T		ST8602A-2 φ6 L=1250 20kΩ (25°C)				
	Thermistor (for discharge air)	R4T	ST8605-8 L=2000 20kΩ (25°C)					
	Float switch	S1L	Option					
Others	Fuse	F1U		250V 5A ¢5.2				
	Transformer	T1R		TR22H21R8				

Si34-601A Option List

4. Option List

4.1 Option List of Controllers

Operation Control System Optional Accessories

No.	Item	Туре	FXCQ-M	FXFQ-M	FXKQ-MA	FXDQ-N(A) FXDQ-P	FXUQ-M	FXSQ-M	FXMQ-MA	FXHQ-MA	FXAQ-MA	FXLQ-MA FXNQ-MA
1	Remote	Wireless	BRC7C62	BRC7E61W	BRC4C61	BRC4C62	BRC7C528W	BRC	4C62	BRC7E63W	BRC7E618	BRC4C62
	controller	Wired					BRC	1C62				
2		note controller dy schedule timer					BRC	1D61				
3	Simplified			_		Note 8 BRC2C51		Not BRC		_	_	Note 8 BRC2C51
4	Remote of hotel use	controller for		_		BRC3A61	_	BRC	3A61	-	_	BRC3A61
5	Adaptor f	or wiring	★KRP1B61	★KRP1B59	KRP1B61	★KRP1B56		KRP	1B61	KRP1C3	_	KRP1B61
6-1	Wiring ac electrical	laptor for appendices (1)	★KRP2A61	★KRP2A62	KRP2A61	★KRP2A53	★KRP2A62	KRP	2A61	★KRP2A62	★KRP2A61	KRP2A61
6-2		laptor for appendices (2)	★KRP4A51	★KRP4A53	KRP4A51	★KRP4A54	★KRP4A53	KRP4A51		★KRP4A52	★KRP4A51	KRP4A51
7	Remote	sensor	KRCS01-1	_				KRC	601-1			
8	Installation adaptor F	on box for PC board	Note 2, 3 KRP1B96	Note 2, 3 KRP1D98	_	Note 4, 6 KRP1B101	KRP1B97	Note 5 KRP4A91	_	Note 3 KRP1C93	Note 2, 3 KRP4A93	_
9	Central re	emote controller					DCS30	2CA61				
9-1	Electrical terminal	box with earth (3 blocks)					KJB	311A				
10	Unified o	n/off controller					DCS30	1BA61				
10-1	Electrical terminal	box with earth (2 blocks)					KJB	212A				
10-2	Noise filte electroma use only)	er (for agnetic interface		KEK26-1								
11	Schedule	timer					DST30	1B(A)61				
12	for outdo	control adaptor or unit (Must be on indoor units)	★ DTA104A61	*DTA104A6 2	DTA104A61	★ DTA104A53		DTA1	D4A61	★ DTA104A62	★ DTA104A61	DTA104A61
13	Interface SkyAir-s	e adaptor for series	_	_	_	_	Note 7 DTA102A52	_	-	_	_	_

Note:

- 1. Installation box (No.8) is necessary for each adaptor marked *.
- 2. Up to 2 adaptors can be fixed for each installation box.
- 3. Only one installation box can be installed for each indoor unit.
- 4. Up to 2 installation boxes can be installed for each indoor unit.
- 5. Installation box (No. 8) is necessary for second adaptor.
- 6. Installation box (No. 8) is necessary for each adaptor.
- 7. This adaptor is required when connecting with optional controller for centralized control.
- 8. BRC2A51 is also available.

Various PC Boards

No.	Part name	Model No.	Function				
1	Adaptor for wiring	KRP1B56 KRP1B57 KRP1B59 KRP1B61 KRP1C3	■ PC board when equipped with auxiliary electric heater in the indoor unit.				
2	DIII-NET Expander Adaptor	DTA109A51	 Up to 1024 units can be centrally controlled in 64 different groups. Wiring restrictions (max. length: 1000m, total wiring length: 2000m, max. number of branches: 16) apply to each adaptor. 				

System Configuration

No.	Part name	Model No.	Function
1	Central remote controller	DCS302CA61	■ Up to 64 groups of indoor units (128 units)can be connected, and ON/OFF, temperature setting and monitoring can be accomplished individually or simultaneously. Connectable up to "2" controllers in one system.
2	Unified ON/OFF controller	DCS301BA61	Up to 16 groups of indoor units (128 units) can be turned, ON/OFF individually or simultaneously, and operation and malfunction can be displayed. Can be used in combination with up to 8 controllers.
3	Schedule timer	DST301BA61	Programmed time weekly schedule can be controlled by unified control for up to 64 groups of indoor units (128 units). Can turn units ON/OFF twice per day.
4	Unification adaptor for computerized control	★ DCS302A52	■ Interface between the central monitoring board and central control units
5	Interface adaptor for SkyAir-series	★DTA102A52	■ Adaptors required to connect products other than those of the VRV System to the high-
6	Central control adaptor kit	★ DTA107A55	speed DIII-NET communication system adopted for the VRV System. To use any of the above optional controllers, an appropriate adaptor must be installed on
7	Wiring adaptor for other air-conditioner	★ DTA103A51	the product unit to be controlled.
8	DIII-NET Expander adaptor	DTA109A51	 Up to 1,024 units can be centrally controlled in 64 different groups. Wiring restrictions (max. length: 1,000m, total wiring length: 2,000m, max. number of branches: 16) apply to each adaptor.
9	Mounting plate	KRP4A92	■ Fixing plate for DTA109A51

Note:

Installation box for ★ adaptor must be procured on site.

Option List Si34-601A

Building management system

No.		Pai	t name		Model No.	Function
1	uch	basic	Hardware	intelligent Touch Controller	DCS601C51	Air-Conditioning management system that can be controlled by a compact all-in-one unit.
1-1	intelligent Touch Controller		Hardware	DIII-NET plus adaptor	DCS601A52	Additional 64 groups (10 outdoor units) is possible.
1-2	itelli C	Option		P.P.D.	DCS002C51	P.P.D.: Power Proportional Distribution function
1-3	in		Software	Web	DCS004A51	Monitors and controls the air conditioning system using the Internet and Web browser application on a PC.
1-4	Electrica	box with e	arth termina	(4blocks)	KJB411A	Wall embedded switch box.
				128 units	DAM602B52	
			Number of	256 units	DAM602B51	
2	intelligen Manager		units to be	512 units	DAM602B51x2	Air conditioner management system (featuring minimized engineering) that can be controlled by personal computers.
	Managor		connected	768 units	DAM602B51x3	and our be continued by personal compaters.
				1024 units	DAM602B51x4	
0.1	intelligent	O-+:	Cathurana	P.P.D	DAM002A51	P.P.D.: Power Proportional Distribution function.
2-1	Manager III	Option	Software	ECO.	DAM003A51	Software for energy-saving control.
2-2		Optional D	III Ai unit		DAM101A51	Analog input for "sliding temperature" function (to reduce cold shock) for intelligent Manager III.
3	ation	★2 Interfa	ce for use in	BACnet [®]	DMS502A51	Interface unit to allow communications between VRV and BMS. Operation and monitoring of air-conditioning systems through BACnet® communications.
3-1	Communication Line	Optional D	III board		DAM411A1	Expansion kit, installed on DMS502A51, to provide 3 more DIII-NET communication ports. Not usable independently.
3-2	Comr	Optional D	i board		DAM412A1	Expansion kit, installed on DMS502A51, to provide 16 more wattmeter pulse input points. Not usable independently.
4		★3 Interfac	e for use in L	ON WORKS®	DMS504B51	Interface unit to allow communications between VRV and BMS. Operation and monitoring of air-conditioning systems through Lon Works [®] communication.
5		<u>e</u> eo	Basic unit		DPF201A51	Enables ON/OFF command, operation and display of malfunction; can be used in combination with up to 4 units.
6	ınal	Parallel interface	Temperature measuremen		DPF201A52	Enables temperature measurement output for 4 groups; 0-5VDC.
7	g sig		Temperature setting units		DPF201A53	Enables temperature setting input for 16 groups; 0-5VDC.
8	4nalοç	Unification adaptor for computerized control		DCS302A52	Interface between the central monitoring board and central control units	
9-1	Contact/Analog signal	Wiring adaptor for electrical appendices (1)		KRP2A53, 61, 62	Simultaneously controls air-conditioning control computer and up to 64 groups of indoor units.	
9-2	°C	Wiring adap appendices	tor for electric (2)	al	KRP4A51-54	To control the group of indoor units collectively, which are connected by the transmission wiring of remote controller.
13			ntrol adaptor fo e installed on		DTA104A53, 61, 62	Cooling/Heating mode change over. Demand control and Low noise control are available between the plural outdoor units.

Notes:

- *1. PPD does not support Connection Unit Series.
 *2. BACnet[®] is a registered trademark of American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE).
- *3. LON WORKS® is a registered trade mark of Echelon Corporation.

Please refer to Option Handbook etc. for detail.

Si34-601A Option List

4.2 Option Lists (Outdoor Unit)

RXYQ5 ~ 18PY1

	Optional accessories	RXYQ5PY1	RXYQ5PY1E	RXYQ8PY1 RXYQ10PY1	RXYQ8PY1E RXYQ10PY1E	RXYQ12PY1 RXYQ14PY1 RXYQ16PY1 RXYQ18PY1	RXYQ12PY1E RXYQ14PY1E RXYQ16PY1E RXYQ18PY1E
Cool	/Heat Selector			KRC1	9-26A		
Cool/Heat Selector	Fixing box	KJB111A					
Distributive Piping	Refnet header	KHRP26M22H (Max. 4 branch)		KHRP26M22H, (Max. 4 branch) KHRP26M33H (Max. 8 branch)		KHRP26M22H, (Max. 4 branch) KHRP26M72H (Max. 8 branch)	(Max. 8 branch)
Dis	Refnet joint	KHRP26A22T			6A22T, 26A33T	KHRP26A22T, KHRP2	
Cent	tral drain pan kit	KWC26C160	★KWC26C160E	KWC26C280	★KWC26C280E	KWC26C450	★KWC26C450E
Digital Pressure Gauge Kit		BHGP26A1(E)					

C:3D053052A

RXYQ20 ~ 36PY1

	Optional accessories	RXYQ20PY1 RXYQ22PY1	RXYQ20PY1E RXYQ22PY1E	RXYQ24PY1 RXYQ26PY1 RXYQ28PY1	RXYQ24PY1E RXYQ26PY1E RXYQ28PY1E	RXYQ30PY1 RXYQ32PY1 RXYQ34PY1 RXYQ36PY1	RXYQ30PY1E RXYQ32PY1E RXYQ34PY1E RXYQ36PY1E
Cool	/Heat Selector			KRC1	9-26A		
Cool/Heat Selector	Fixing box			KJB111A			
Distributive Piping	Refnet header	KHRP26M22H (Max. 4 branch), KHRP26M33H (Max. 8 branch), KHRP26M72H (Max. 8 branch)		KHRP26M22H, KHRP26M33H, KHRP26M72H, KHRP26M73 (Max. 4 branch) (Max. 8 branch) (Max. 8 branch) (Max. 8 branch)			
Ä	Refnet joint	KHRP2	26A22T, 26A33T, 26A72T	KHRP26A22T, KHRP26A33T, KHRP26A72T, KHRP26A73T			
Outo	loor unit multi connection piping kit			BHFP22P100			
Pipe	size reducer	-	_	ŀ	KHRP26M73TP,	KHRP26M73H)
Cent	tral drain pan kit	KWC26C280 KWC26C450	★ KWC26C280E ★ KWC26C450E	KWC26C280 KWC26C450	★ KWC26C280E ★ KWC26C450E	KWC26C450 × 2	★ KWC26C450E×2
Digit	al Pressure Gauge Kit	BHGP26A1(E)					

C:3D053052A

RXYQ38 ~ 54PY1

Optional accessories		RXYQ38PY1 RXYQ40PY1 RXYQ42PY1 RXYQ44PY1 RXYQ46PY1	RXYQ38PY1E RXYQ40PY1E RXYQ42PY1E RXYQ44PY1E RXYQ46PY1E	RXYQ48PY1 RXYQ50PY1 RXYQ52PY1 RXYQ54PY1	RXYQ48PY1E RXYQ50PY1E RXYQ52PY1E RXYQ54PY1E	
Cool	/Heat Selector		KRC1	9-26A		
Cool/Heat Selector	Fixing box	KJB111A				
utive	Refnet header	KHRP26M22H, KHRP26M33H, KHRP26M72H, KHRP26M73H (Max. 4 branch) (Max. 8 branch) (Max. 8 branch) (Max. 8 branch)				
Distributive Piping	Refnet joint	KHRP26A22T, KHRP26A33T, KHRP26A72T, KHRP26A73T				
Outo	loor unit multi connection piping kit		BHFP2	2P151		
Pipe	size reducer	KHRP26M73TP, KHRP26M73HP				
Cent	ral drain pan kit	KWC26C280 KWC26C450 × 2	*KWC26C280E *KWC26C450E × 2	KWC26C450 × 3	★ KWC26C450E × 3	
Digit	al Pressure Gauge Kit		BHGP2	6A1(E)	C:2D053053A	

C:3D053052A

Note)★: Order products

Option List Si34-601A

RXYQ16 ~ 18PHY1

	Optional accessories	RXYQ16PHY1 RXYQ18PHY1	RXYQ16PHY1E RXYQ18PHY1E	
Cool	/Heat Selector	KRC1	9-26A	
Selector Selector Fixing box		KJB111A		
Distributive Piping	Refnet header	KHRP26M22H, KHRP26M33H, (Max. 4 branch) (Max. 8 branch) KHRP26M72H (Max. 8 branch)		
	Refnet joint	KHRP26A22T, KHRP2	6A33T, KHRP26A72T	
Outd	loor unit multi connection piping kit	BHFP22P100		
Cent	ral drain pan kit	KWC26C280 × 2	★ KWC26C280E × 2	
Digit	al Pressure Gauge Kit	BHGP26A1(E)		

C:3D053053A

RXYQ24 ~ 30PHY1

	Optional accessories	RXYQ24PHY1 RXYQ26PHY1	RXYQ24PHY1E RXYQ26PHY1E	RXYQ28PHY1 RXYQ30PHY1	RXYQ28PHY1E RXYQ30PHY1E		
Cool	/Heat Selector		KRC1	9-26A			
Cool/Heat Selector	Fixing box	KJB111A					
utive ng	Refnet header	KHRP26M22H, KHRP26M33H, KHRP26M72H, KHRP26M73H (Max. 4 branch) (Max. 8 branch) (Max. 8 branch)					
Distributive Piping	Refnet joint	KHRP	KHRP26A22T, KHRP26A33T, KHRP26A72T, KHRP26A73T				
Outo	loor unit multi connection piping kit		BHFP2	22P151			
Pipe	size reducer		KHRP26M73TP,	KHRP26M73HP			
Cent	ral drain pan kit	KWC26C280 × 3					
Digit	al Pressure Gauge Kit	BHGP26A1(E)					
					C:3D053053A		


RXYQ32 ~ 50PHY1

Optional accessories		RXYQ32PHY1 RXYQ34PHY1	RXYQ32PHY1E RXYQ34PHY1E	RXYQ36PHY1 RXYQ44PHY1 RXYQ38PHY1 RXYQ46PHY1 RXYQ40PHY1 RXYQ48PHY1 RXYQ42PHY1 RXYQ50PHY1	RXYQ36PHY1E RXYQ44PHY1E RXYQ38PHY1E RXYQ46PHY1E RXYQ40PHY1E RXYQ48PHY1E RXYQ42PHY1E RXYQ50PHY1E		
Cool	/Heat Selector			KRC19-26A			
Cool/Heat Selector	Fixing box	ox KJB111A					
utive ng	Refnet header	KHRP26M22H, KHRP26M33H, KHRP26M72H, KHRP26M73H (Max. 4 branch) (Max. 8 branch) (Max. 8 branch) (Max. 8 branch)					
Distributive Piping	Refnet joint		KHRP26A22T	KHRP26A33T, KHRP26A72T,	KHRP26A73T		
Outo	loor unit multi connection piping kit		BHFP22P151				
Pipe	size reducer		k	HRP26M73TP, KHRP26M73H	Р		
Cent	ral drain pan kit	KWC26C280			★ KWC26C450E × 3		
Digit	al Pressure Gauge Kit	BHGP26A1(E)					
		•			C:3D053053A		

Note)★: Order products

5. Piping Installation Point

5.1 Piping Installation Point




Since there is a possibility that oil may be collected on a stop machine side, install piping between outdoor units to go to level or go up to an outdoor unit, and to make a slope.

(V3036)


The projection part between multi connection piping kits

When the piping length between the multi connection kits or between multi connection kit and outdoor unit is 2m or more, prepare a vertical projection part (200mm or more as shown below) only on the gas pipe line location less than 2m from multi connection kit.

In the case of 2m or less




In the case of 2m or more




Piping Installation Point Si34-601A

5.2 The Example of A Wrong Pattern



(V3039)




	Outdoor Unit - Multi Connection Piping Kit	Actual piping length 10m or less, equivalent length 13m or less				
Max.allowable Piping Length	Multi Connection Piping Kit - Indoor Unit	Actual piping length 165m or less, equivalent length 190m or less, the total extension 1000m or less				
i iping zongin	REFNET Joint - Indoor Unit	Actual piping length 40m or less (Refer to Page 363, 364 Note 2 in case of up to 90m)				
	Outdoor Unit - Outdoor Unit	5m or less				
Allowable Level Difference	Outdoor Unit - Indoor Unit	50m or less ★90m or less (when an outdoor unit is lower than indoor units: 40m or less in case of RXYQ5P)				
	Indoor Unit - Indoor Unit	15m or less				

Note)★: Available on request if the outdoor unit is above.

Si34-601A Example of connection (R-410A Type)


6. Example of connection (R-410A Type)



Example of connection (R-410A Type)

*Note 1

When the equivalent pipe length between outdoor and indoor units is 90m or more, the size of main pipes (both gas-side and liquid-side) must be increased. Depending on the length of the piping, the capacity may drop, but even in such case it is able to increase the size of main pipes.



■ Diameter of above case

Model	Gas	Liquid
RXYQ5 Type	φ19.1	Not Increased
RXYQ8 Type	ф22.2	φ12.7
RXYQ10 Type	ф25.4*	φ12.7
RXYQ12 Type	Not Increased	φ15.9
RXYQ14 Type	Not Increased	φ15.9
RXYQ16 Type	ф31.8*	φ15.9
RXYQ18 Type	ф31.8*	φ19.1

Model	Gas	Liquid
RXYQ20 Type	ф31.8*	φ19.1
RXYQ22 Type	ф31.8*	φ19.1
RXYQ24 Type	Not Increased	ф19.1
RXYQ26 Type	ф38.1*	ф22.2
RXYQ28 Type	ф38.1*	ф22.2
RXYQ30 Type	ф38.1*	ф22.2
RXYQ32 Type	ф38.1*	ф22.2

Model	Gas	Liquid
RXYQ34 Type	ф38.1*	φ22.2
RXYQ36 Type	Not Increased	φ22.2
RXYQ38 Type	Not Increased	φ22.2
RXYQ40 Type	Not Increased	φ22.2
RXYQ42 Type	Not Increased	ф22.2
RXYQ44 Type	Not Increased	φ22.2
RXYQ46 Type	Not Increased	ф22.2

Model	Gas	Liquid
RXYQ48 Type	Not Increased	ф22.2
RXYQ50 Type	Not Increased	ф22.2
RXYQ52 Type	Not Increased	ф22.2
RXYQ54 Type	Not Increased	ф22.2

^{*}If available on the site, use this size. Otherwise, it can not be increased.

*Note 2

Allowable length after the first refrigerant branch kit to indoor units is 40 m or less, however it can be extended up to 90 m if all the following conditions are satisfied. (In case of "Branch with REFNET joint")

Required Conditions	Example Drawings	
It is necessary to increase the pipe size between the first branch kit and the final branch kit. (Reducers must be procured on site)	8 $b+c+d+e+f+g+p \le 90 \text{ m}$ increase the pipe size of b, c, d, e, f, g	Increase the pipe size as follows
For calculation of Total extension length, the actual length of above pipes must be doubled. (except main pipe and the pipes that are not increased)	a+b×2+c×2+d×2+e×2+f×2+g×2 +h+i+j+k+l+m+n+p≤ 1000 m	Outdoor unit REFNET joint (A-G)
3. Indoor unit to the nearest branch kit ≤ 40 m	h, i, j p ≤ 40 m	a b c d e f g H1
4. The difference between [Outdoor unit to the farthest indoor unit] and [Outdoor unit to the nearest indoor unit] ≤ 40 m	The farthest indoor unit $\boxed{8}$ The nearest indoor unit $\boxed{1}$ $(a+b+c+d+e+f+g+p)-(a+h) \leq 40 \text{ m}$	h i j j k l m n n p n n n p n n n n n n n n n n n n

^{*}If available on the site, use this size. Otherwise it can not be increased.

*Note 3

If the pipe size above the REFNET header is \$\phi 34.9\$ or more, KHRP26M73HP is required.

7. Thermistor Resistance / Temperature Characteristics

Indoor unit For air suction R1T For liquid pipe R2T

For gas pipe

Outdoor unit for fin thermistor R1T Outdoor unit For outdoor air R1T

For suction pipe R4T
For Receiver gas pipe R5T

For Receiver outlet liquid pipe R6T

 $(k\Omega)$

R3T

T°C	0.0
-10	-
-8	-
-6 -4	88.0 79.1
-4 -2	79.1
0	64.1
2	57.8
4	52.3
6	47.3
8	42.9
10	38.9
12	35.3
14	32.1
16	29.2
18	26.6
20	24.3
22	22.2
24	20.3
26	18.5
28	17.0
30 32	15.6 14.2
34	13.1
36	12.0
38	11.1
40	10.3
42	9.5
44	8.8
46	8.2
48	7.6
50	7.0
52	6.7
54	6.0
56	5.5
58	5.2
60 62	4.79
64	4.46 4.15
66	3.87
68	3.61
70	3.37
72	3.15
74	2.94
76	2.75
78	2.51
80	2.41
82	2.26
84	2.12
86	1.99
88	1.87
90	1.76

92

94

96

1.65

1.55

1.46 1.38


T°C	0.0	0.5	T°C	0.0	0.5
-20	197.81	192.08	30	16.10	15.76
-19	186.53	181.16	31	15.43	15.10
-18	175.97	170.94	32	14.79	14.48
-17	166.07	161.36	33	14.18	13.88
-16	156.80	152.38	34	13.59	13.31
-15	148.10	143.96	35	13.04	12.77
-14	139.94	136.05	36	12.51	12.25
-13	132.28	128.63	37	12.01	11.76
-12	125.09	121.66	38	11.52	11.29
-11	118.34	115.12	39	11.06	10.84
-10	111.99	108.96	40	10.63	10.41
-9	106.03	103.18	41	10.21	10.00
-8	100.41	97.73	42	9.81	9.61
-7	95.14	92.61	43	9.42	9.24
-6	90.17	87.79	44	9.06	8.88
-5	85.49	83.25	45	8.71	8.54
-4	81.08	78.97	46	8.37	8.21
-3	76.93	74.94	47	8.05	7.90
-2	73.01	71.14	48	7.75	7.60
-1	69.32	67.56	49	7.46	7.31
0	65.84	64.17	50	7.18	7.04
1	62.54	60.96	51	6.91	6.78
2	59.43	57.94	52	6.65	6.53
3	56.49	55.08	53	6.41	6.53
4	53.71	52.38	54	6.65	6.53
5	51.09	49.83	55	6.41	6.53
6	48.61	47.42	56	6.18	6.06
7	46.26	45.14	57	5.95	5.84
8	44.05	42.98	58	5.74	5.43
9	41.95	40.94	59	5.14	5.05
10	39.96	39.01	60	4.96	4.87
11	38.08	37.18	61	4.79	4.70
12	36.30	35.45	62	4.62	4.54
13	34.62	33.81	63	4.46	4.38
14	33.02	32.25	64	4.30	4.23
15	31.50	30.77	65	4.16	4.08
16	30.06	29.37	66	4.01	3.94
17	28.70	28.05	67	3.88	3.81
18	27.41	26.78	68	3.75	3.68
19	26.18	25.59	69	3.62	3.56
20	25.01	24.45	70	3.50	3.44
21	23.91	23.37	71	3.38	3.32
22	22.85	22.35	72	3.27	3.21
23	21.85	21.37	73	3.16	3.11
24	20.90	20.45	74	3.06	3.01
25	20.00	19.56	75	2.96	2.91
26	19.14	18.73	76	2.86	2.82
27	18.32	17.93	77	2.77	2.72
28	17.54	17.17	78	2.68	2.64
29	16.80	16.45	79	2.60	2.55
30	16.10	15.76	80	2.51	2.47

Outdoor Unit Thermistors for Discharge Pipe (R3T, R31~33T)

									$(k\Omega)$
T°C	0.0	0.5	T°C	0.0	0.5		T°C	0.0	0.5
0	640.44	624.65	50	72.32	70.96		100	13.35	13.15
1	609.31	594.43	51	69.64	68.34		101	12.95	12.76
2	579.96	565.78	52	67.06	65.82		102	12.57	12.38
3	552.00	538.63	53	64.60	63.41		103	12.20	12.01
4	525.63	512.97	54	62.24	61.09		104	11.84	11.66
5	500.66	488.67	55	59.97	58.87		105	11.49	11.32
6	477.01	465.65	56	57.80	56.75		106	11.15	10.99
7	454.60	443.84	57	55.72	54.70		107	10.83	10.67
8	433.37	423.17	58	53.72	52.84		108	10.52	10.36
9	413.24	403.57	59	51.98	50.96		109	10.21	10.06
10	394.16	384.98	60	49.96	49.06		110	9.92	9.78
11	376.05	367.35	61	48.19	47.33		111	9.64	9.50
12	358.88	350.62	62	46.49	45.67		112	9.36	9.23
13	342.58	334.74	63	44.86	44.07		113	9.10	8.97
14	327.10	319.66	64	43.30	42.54		114	8.84	8.71
15	312.41	305.33	65	41.79	41.06		115	8.59	8.47
16	298.45	291.73	66	40.35	39.65		116	8.35	8.23
17	285.18	278.80	67	38.96	38.29		117	8.12	8.01
18	272.58	266.51	68	37.63	36.98		118	7.89	7.78
19	260.60	254.72	69	36.34	35.72		119	7.68	7.57
20	249.00	243.61	70	35.11	34.51		120	7.47	7.36
21	238.36	233.14	71	33.92	33.35		121	7.26	7.16
22	228.05	223.08	72	32.78	32.23		122	7.06	6.97
23	218.24	213.51	73	31.69	31.15		123	6.87	6.78
24	208.90	204.39	74	30.63	30.12		124	6.69	6.59
25	200.00	195.71	75	29.61	29.12		125	6.51	6.42
26	191.53	187.44	76	28.64	28.16		126	6.33	6.25
27	183.46	179.57	77	27.69	27.24		127	6.16	6.08
28	175.77	172.06	78	26.79	26.35		128	6.00	5.92
29	168.44	164.90	79	25.91	25.49		129	5.84	5.76
30	161.45	158.08	80	25.07	24.66		130	5.69	5.61
31	154.79	151.57	81	24.26	23.87		131	5.54	5.46
32	148.43	145.37	82	23.48	23.10		132	5.39	5.32
33	142.37	139.44	83	22.73	22.36		133	5.25	5.18
34	136.59	133.79	84	22.01	21.65		134	5.12	5.05
35	131.06	128.39	85	21.31	20.97		135	4.98	4.92
36	125.79	123.24	86	20.63	20.31		136	4.86	4.79
37	120.76	118.32	87	19.98	19.67		137	4.73	4.67
38	115.95	113.62	88	19.36	19.05		138	4.61	4.55
39	111.35	109.13	89	18.75	18.46		139	4.49	4.44
40	106.96	104.84	90	18.17	17.89		140	4.38	4.32
41	102.76	100.73	91	17.61	17.34		141	4.27	4.22
42	98.75	96.81	92	17.07	16.80		142	4.16	4.11
43	94.92	93.06	93	16.54	16.29		143	4.06	4.01
44	91.25	89.47	94	16.04	15.79		144	3.96	3.91
45	87.74	86.04	95 95	15.55	15.79		145	3.86	3.81
46	84.38	82.75	96	15.08	14.85		146	3.76	3.72
46 47	81.16	79.61	97	14.62	14.65		146	3.76	3.62
48	78.09	76.60	98	14.02	13.97		147	3.58	3.54
48 49	78.09 75.14		98				148		
50		73.71 70.96	100	13.76 13.35	13.55			3.49	3.45
50	72.32	70.90	100	10.00	13.15	l	150	3.41	3.37

Si34-601A Pressure Sensor

8. Pressure Sensor



9. Method of Checking The Inverter's Power Transistors and Diode Modules

9.1 Method of Checking The Inverter's Power Transistors and Diode Modules

Checking failures in power semiconductors mounted on inverter PC board

Check the power semiconductors mounted on the inverter PC board by the use of a multiple tester.

< tems to be prepared>

Multiple tester: Prepare the analog type of multiple tester.
 For the digital type of multiple tester, those with diode check function are available for the checking.


<Test points>

 Turn OFF the power supply. Then, after a lapse of 10 minutes or more, make measurement of resistance.


<Preparation>

• To make measurement, disconnect all connectors and terminals.

Inverter PC board



Electronic circuit



- According to the checking aforementioned, it is probed that the malfunction results from the faulty inverter. The following section describes supposed causes of the faulty inverter.
- Faulty compressor (ground leakage)
- Faulty fan motor (ground leakage)
- Entry of conductive foreign particles
- Abnormal voltage (e.g. overvoltage, surge (thunder), or unbalanced voltage) In order to replace the faulty inverter, be sure to check for the points aforementioned.

1. Power module checking

When using the analog type of multiple tester, make measurement in resistance measurement mode in the $x1k\Omega$ range.

No.		uring int	Criterion	Remark
	+	-		
1	P3	U		
2	P3	V	2 to 15kΩ	
3	P3	W		
4	U	P3		
5	V	P3	Not less	It may take time to determine the
6	W	P3	than	
7	N3	U	(including) to capacitor	resistance due
8	N3	V		charge or else.
9	N3	W		· ·
10	U	N3		
11	V	N3	2 to 15kΩ	
12	W	N3		

When using the digital type of multiple tester, make measurement in diode check mode ($\rightarrow \vdash$).

No.		uring int	Criterion	Remark	
	+	-			
1	P3	U	Not less	It may take time to	
2	P3	V	than 1.2V	determine the voltage due to capacitor	
3	P3	W	(including)	charge or else.	
4	U	P3			
5	V	P3			
6	W	P3	0.3 to 0.7V	7V	
7	N3	U	0.3 10 0.7 V		
8	N3	V	,		
9	N3	W			
10	U	N3	Not less	It may take time to	
11	V	N3	than 1.2V	determine the voltage due to capacitor	
12	W	N3	(including)	charge or else.	

2. Diode module checking

When using the analog type of multiple tester, make measurement in resistance measurement mode in the $x1k\Omega$ range.

No.		uring int	Criterion	Remark	
	+	-			
1	P1	J1			
2	P1	J2	2 to 15kΩ		
3	P1	J3			
4	J1	P1			
5	J2	P1	Not less	It may take	
6	J3	P1	than	time to determine the	
7	N3	J1		resistance due	
8	N3	J2	(including)	to capacitor charge or else.	
9	N3	J3		· ·	
10	J1	N3			
11	J2	N3	2 to 15kΩ		
12	J3	N3			

When using the digital type of multiple tester, make measurement in diode check mode ($\rightarrow \vdash$).

No.	Meas po	uring int	Criterion	Remark	
	+	-			
1	P1	J1	Not less	It may take time to	
2	P1	J2	than 1.2V	determine the voltage due to capacitor	
3	P1	J3	(including)	charge or else.	
4	J1	P1			
5	J2	P1			
6	J3	P1	0.3 to 0.7V		
7	N3	J1	0.3 10 0.7 V		
8	N3	J2			
9	N3	J3			
10	J1	N3	Not less	It may take time to	
11	J2	N3	than 1.2V		determine the voltage due to capacitor
12	J3	N3	(including)	charge or else.	

Part 8 Precautions for New Refrigerant (R-410A)

1.	Prec	autions for New Refrigerant (R-410A)	372
		Outline	
		Refrigerant Cylinders	
		Service Tools	

1. Precautions for New Refrigerant (R-410A)

1.1 Outline

1.1.1 About Refrigerant R-410A

- Characteristics of new refrigerant, R-410A
- 1. Performance

Almost the same performance as R-22 and R-407C

2. Pressure

Working pressure is approx. 1.4 times more than R-22 and R-407C.


3. Refrigerant composition

Few problems in composition control, since it is a Quasi-azeotropic mixture refrigerant.

	HFC units (Units us	HCFC units	
Refrigerant name	R-407C	R-410A	R-22
Composing substances	Non-azeotropic mixture of HFC32, HFC125 and HFC134a (*1)	Quasi-azeotropic mixture of HFC32 and JFC125 (*1)	Single-component refrigerant
Design pressure	3.2 MPa (gauge pressure) = 32.6 kgf/cm ²	4.0 MPa (gauge pressure) = 40.8 kgf/cm ²	2.75MPa (gauge pressure) = 28.0 kgf/cm ²
Refrigerant oil	Synthetic	oil (Ether)	Mineral oil (Suniso)
Ozone destruction factor (ODP)	0	0	0.05
Combustibility	None	None	None
Toxicity	None	None	None

- ★1. Non-azeotropic mixture refrigerant: mixture of two or more refrigerants having different boiling points.
- ★2. Quasi-azeotropic mixture refrigerant: mixture of two or more refrigerants having similar boiling points.
- ★3. The design pressure is different at each product. Please refer to the installation manual for each product.

(Reference) 1 MPa = 10.19716 kgf / cm²




Pressure-Enthalpy curves of HFC-32/125 (50/50wt%)

■ Thermodynamic characteristic of R-410A

C				,						DAIREP v	
	Temperature										
1.6	(0)		· 1		,		` ' '			,	~ /
-68		Liquid	vapoi	Liquid	Vapor	Liquid	Vapor	Liquid	vapoi	Liquid	vapoi
-66	-70	36.13	36.11	1410.7	1.582	1.372	0.695	100.8	390.6	0.649	2.074
-64 51.73 51.68 1392.5 2.213 1.377 0.716 109.1 395.3 0.702 2.046 -60 64.87 64.80 1386.2 2.734 1.379 0.726 114.6 396.4 0.715 2.037 -58 72.38 72.29 1374.0 3.030 1.380 0.726 117.4 397.6 0.728 2.030 -56 80.57 80.46 1367.8 3.350 1.382 0.732 120.1 395.3 0.741 2.023 -54 89.49 89.36 1361.6 3.686 1.384 0.737 122.9 399.8 0.744 2.023 -52 99.18 99.03 1355.3 4.071 1.386 0.744 125.7 400.1 0.766 2.010 -51.58 101.32 101.17 1354.0 4.153 1.386 0.745 126.3 400.1 0.766 2.010 -60 108.69 109.51 1349.0 4.474 1.388 0.745 128.5 402.0 0.779 2.046 -64 133.36 133.11 1336.3 5.377 1.394 0.763 134.2 403.1 0.791 1.998 -64 121.07 120.85 1342.7 4.999 1.391 0.756 131.2 403.1 0.791 1.998 -64 146.61 146.32 1330.9 5.880 1.397 0.770 136.8 405.2 0.816 1.987 -64 176.24 178.85 1317.0 6.996 1.405 0.785 142.4 407.3 0.840 1.976 -63 210.37 209.86 1304.0 8.275 1.414 0.800 148.1 409.3 0.862 1.975 -63 2243.6 228.86 1394.0 8.275 1.414 0.800 148.1 409.3 0.864 1.965 -63 210.37 209.86 1304.0 8.275 1.414 0.800 148.1 409.3 0.864 1.965 -64 210.37 207.86 289.9 0.55 1.420 0.826 166.6 412.1 0.867 1.976 -65 210.37 207.86 289.9 0.55 1.420 0.866 141.1 0.860 141.2 0.867 1.976 -68 229.39 299.16 1277.1 11.39 1.436 0.835 1.995 1.419 0.896 1.419 0.896 1.419 0.867 1.419 -60 210.37 207.28	-68	40.83	40.80	1404.7	1.774	1.374	0.700	103.6	391.8	0.663	2.066
-62 68,00 67,94 13864 2.463 1.378 0.715 111.9 396.3 0.702 2.044 -60 64,87 64,80 1380.2 2.734 1.379 0.720 114.6 396.4 0.715 2.037 -58 72.38 72.29 1374.0 3.030 1.380 0.726 117.4 397.6 0.728 2.030 -64 88.49 88.36 1367.8 3.350 1.382 0.732 122.9 399.8 0.751 2.017 -62 99.18 99.03 1365.3 4.011 1.386 0.737 122.9 399.8 0.751 2.017 -51.58 101.32 101.17 1354.0 4.163 1.386 0.745 126.3 401.1 0.769 2.009 -60 100.69 100.51 1349.0 4.474 1.388 0.750 128.5 402.0 0.791 2.904 -61 133.36 133.11 1336.3 5.377 1.394 0.766 1.212 403.1 0.791 1.998 -64 133.36 133.11 1336.3 5.377 1.394 0.763 114.6 405.2 0.828 1.981 -64 146.81 146.92 1317.0 6.996 1.405 0.775 136.8 405.2 0.828 1.981 -63 10.77 129.5 1317.0 6.996 1.405 0.785 124.4 407.3 0.840 1.976 -38 192.71 192.27 1310.5 7.614 1.409 0.792 146.3 408.3 0.852 1.970 -38 192.71 192.27 1310.5 7.614 1.409 0.792 145.3 408.3 0.852 1.970 -32 249.46 248.8 1297.3 2.932 1.424 4.07.3 0.886 1.987 -32 249.46 248.8 1297.5 1.229 1.442 0.803 1.412 0.893 1.900 -28 239.39 239.16 1277.1 113.9 1.430 0.855 156.6 412.1 0.898 1.960 -29 271.01 270.28 1283.3 10.55 1.444 0.844 1.440 0.822 1.944 -20 40.44 343.4 1.263.3 1.32.7 1.445 0.846 1.440 0.892 1.940 -20 271.01 270.28 1283.3 1.652 1.486 0.866 174.1 1.416 0.968 1.932 -20 40.34 400.6 129.2 15.77 1.435 0.866 1.744 1.440 0.922 1.941 -20 40.34 400.6 1.224 1.483 0.999 1.800 1.490 0.991 1.914 -20 40.34 400.6 1.224 1.483 0.990 1.800 1.944 0.968 1.932 -20 40.34 40.06 1.224 1.483 0.990 1.800 1.944 0.968 1.932 -20 40.34 40.06 40.06 1.242 1.483 0.990 1.800 1.944 0.968 1.932	-66	46.02	45.98	1398.6	1.984	1.375	0.705	106.3	393.0	0.676	2.058
-60 64.87 64.80 1380.2 2.734 1.379 0.726 114.6 396.4 0.715 2.037 58.8 72.38 72.29 1374.0 3.030 1.386 0.726 117.4 397.6 0.728 2.030 5.66 80.57 80.46 1367.8 3.350 1.382 0.732 120.1 398.7 0.741 2.023 5.65	-64	51.73	51.68	1392.5	2.213	1.377	0.710	109.1	394.1	0.689	2.051
-58	-62	58.00	57.94	1386.4	2.463	1.378	0.715	111.9	395.3	0.702	2.044
-56	-60	64.87	64.80	1380.2	2.734	1.379	0.720	114.6	396.4	0.715	2.037
-54 88.49 89.36 1361.6 3.696 1.384 0.737 122.9 399.8 0.754 2.017 -51.58 101.32 101.17 1354.0 4.153 1.396 0.745 126.3 401.1 0.769 2.009 -50 109.69 109.51 1349.0 4.474 1.388 0.750 128.5 402.0 0.779 2.004 -48 121.07 120.85 1342.7 4.909 1.391 0.756 131.2 403.1 0.791 1.998 -44 146.61 146.32 1330.0 5.880 1.397 0.770 136.8 405.2 0.815 1.987 -42 16.89 160.55 1323.5 6.319 1.401 1.777 136.8 405.2 0.816 1.987 -40 176.24 175.85 1311.0 6.966 1.405 0.785 142.4 407.3 0.840 1.976 -83 127.7 192.27 1301.5 7.661 1.405 0.785 142.4 409.0 0.845 1.976 -84 210.36 229.86 1300.0 8.261 1.405 0.869 146.3 409.0 0.845 1.976 -84 220.3 243.46 1.972 3.895 1.419 0.869 146.9 409.0 0.875 1.956 -82 239.99 291.16 1277.1 11.39 1.436 0.835 159.5 41.10 0.869 1.976 -28 293.99 293.16 1277.1 11.39 1.436 0.835 159.5 41.31 0.991 1.946 -24 344.44 343.41 1253.3 13.26 1.448 0.864 165.3 41.49 0.922 1.941 -24 344.44 343.41 1253.3 13.26 1.448 0.864 165.3 41.49 0.924 1.946 -24 344.44 343.41 1253.3 13.26 1.448 0.864 165.3 41.49 0.924 1.946 -25 353.6 333.6 124.9 1.485 0.865 171.1 1.49 0.921 1.946 -26 31.6 3.6	-58	72.38	72.29	1374.0	3.030	1.380	0.726	117.4	397.6	0.728	2.030
-62 99,18 99,03 1355.3 4,071 1,386 0,744 125.7 400.9 0,766 2,010 -51.58 101.32 101.17 1354.0 4,153 1,386 0,745 126.3 401.1 0,769 2,009 -60 109,69 109,51 1349.0 4,474 4,909 1,391 0,756 131.2 403.1 0,791 1,998 -64 133.36 133.11 1336.3 5,377 1,394 0,763 134.0 404.1 0,803 1,992 -64 164.61 146.22 1330.0 5,880 1,397 0,776 136.8 405.2 0,816 1,994 -64 166.12 165.25 1312.5 6,419 1,401 0,777 139.6 466.2 0,828 1,981 -64 176.24 175.85 1317.0 6,966 4,056 0,785 142.4 407.3 0,840 1,991 -58 192.71 192.27 1310.5 7,614 1,409 0,792 145.3 408.3 0,862 1,997 -56 210.37 209,86 1397.3 8,980 1,419 0,809 150.9 410.2 0,875 1,956 -32 249,46 248.81 1290.6 9,722 1,424 0,817 153.8 411.2 0,887 1,956 -32 249,46 248.81 1290.6 9,722 1,424 0,817 153.8 411.2 0,887 1,956 -33 271.01 270.28 128.9 10,53 1,436 0,855 156.5 412.1 0,889 1,950 -28 293.99 293.16 1277.1 11,39 1,436 0,855 156.5 412.1 0,891 1,966 -29 241.44 313.40 1270.2 12.39 1,436 0,855 156.5 412.1 0,891 1,966 -20 401.34 400.6 1249.2 12.5 1,438 0,864 188.2 415.7 0,943 1,930 -20 401.34 400.6 1249.2 15.37 1,461 0,875 1,470 0,943 1,949 -14 499.91 498.20 1227.5 1,468 0,866 188.2 415.7 0,968 1,932 -16 455.20 453.64 1234.8 1,741 1,476 0,897 1,914 -17 575.26 573.20 1212.5 21.86 1,499 0,931 185.9 426.5 1,014 1,966 -6 656.97 656.67 1157.0 1,499 0,931 1,859 0,909 1,900 1,914 -12 536.58 534.69 1220.0 20.41 1,491 0,921 1,829 1,900 1,914 -12 105.88 15.64 1,499 1,491 1,906 1,499 1,914 -12 136.69 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499 1,499	-56	80.57	80.46	1367.8	3.350	1.382	0.732	120.1	398.7	0.741	2.023
-51.58	-54	89.49	89.36	1361.6	3.696	1.384	0.737	122.9	399.8	0.754	2.017
109.69	-52	99.18	99.03	1355.3	4.071	1.386	0.744	125.7	400.9	0.766	2.010
109.69	5, 50	101.00	101.15	1051.0	4 150		0.745	100.0	401.1	0.700	0.000
-48 121.07 120.85 1342.7 4.999 1.391 0.756 131.2 403.1 0.791 1.998 -46 133.36 133.11 1336.3 5.377 1.394 0.763 134.0 404.1 0.803 1.992 -42 160.89 160.55 1323.5 6.419 1.401 0.777 136.8 405.2 0.816 1.997 -42 160.89 160.55 1323.5 6.419 1.401 0.777 139.6 406.2 0.828 1.991 -40 176.24 175.85 1317.0 6.996 1.409 0.792 145.3 408.3 0.820 1.970 -38 192.71 192.27 1310.5 7.614 1.409 0.792 145.3 408.3 0.825 1.970 -36 210.37 209.86 1304.0 8.275 1.414 0.800 148.1 409.3 0.864 1.956 -34 229.26 228.69 1297.3 8.980 1.419 0.809 150.9 410.2 0.875 1.960 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.887 1.955 -30 271.01 270.28 1283.9 10.53 1.430 0.826 156.5 411.1 0.899 1.956 -28 239.99 293.16 1277.1 11.39 1.436 0.835 159.5 411.3 0.911 1.946 -26 318.44 317.52 1270.2 12.29 1.442 0.844 162.4 414.0 0.922 1.941 -24 344.4 343.41 1263.3 13.26 1.448 0.854 165.3 414.9 0.992 1.914 -22 372.05 370.90 1256.3 14.28 1.455 0.864 168.2 415.7 0.945 1.932 -23 470.34 400.66 1249.2 15.537 1.461 0.876 171.1 417.4 0.968 1.932 -16 465.20 465.64 1234.8 1.475 0.968 174.1 417.4 0.968 1.932 -16 465.20 465.64 1234.8 1.477 1.476 0.897 177.0 418.2 0.990 1.914 -12 536.58 534.69 1220.0 20.41 1.491 0.991 180.9 419.8 0.091 1.914 -12 536.58 534.69 1220.0 20.41 1.491 0.991 180.9 419.8 0.091 1.914 -12 536.58 534.69 1220.0 20.41 1.491 0.991 180.9 419.8 0.091 1.914 -12 536.58 534.69 1220.2 20.41 1.491 0.991 180.9 419.8 0.091 1.914 -12 536.58 534.69 126.59 1.565 1.562 1.095 1.920 419.8 1.003 1.910 -14 499.91 498.20 1227.5 1.944 1.494 0.991 1.82.9 419.8 1.003 1.910 -15	-51.58	101.32	101.17	1354.0	4.153	1.386	0.745	126.3	401.1	0.769	2.0091
-46 133.36 133.11 133.63 5.377 1.394 0.765 134.0 404.1 0.803 1.992 -42 160.89 160.55 1332.5 6.419 1.401 0.777 139.6 406.2 0.816 1.987 -40 176.24 176.85 1317.0 6.996 1.405 0.785 142.4 407.3 0.840 1.976 -38 192.71 192.27 1310.5 7.614 1.409 0.792 145.3 408.3 0.852 1.970 -36 210.37 209.86 1304.0 8.275 1.414 0.800 148.1 409.3 0.864 1.965 -34 229.26 228.69 1297.3 8.980 1.419 0.809 150.9 410.2 0.875 1.960 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.887 1.955 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.887 1.955 -38 293.99 293.16 1277.1 11.99 1.436 0.835 159.5 413.1 0.911 1.946 -28 318.44 317.52 1270.2 12.29 1.442 0.844 162.4 414.0 0.922 1.941 -24 344.44 343.41 1263.3 13.36 1.456 0.865 165.6 412.1 0.899 1.950 -25 312.50 370.90 1266.3 14.28 1.455 0.865 168.2 415.7 0.945 1.932 -26 401.34 400.6 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.927 -18 422.36 400.96 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.927 -18 425.56 534.60 1234.8 17.74 1.476 0.897 177.0 418.2 0.990 1.914 -14 499.91 498.20 122.75 19.04 1.483 0.909 180.0 419.0 0.991 1.914 -10 575.26 573.20 1212.5 21.86 1.499 0.933 185.9 420.5 1.014 1.906 -8 616.03 613.78 1204.9 23.39 1.507 0.947 189.0 421.2 1.025 1.902 -2 751.64 748.76 1811.4 26.33 3.990 1.919 4.141 1.906 -3 8 616.03 613.78 1.465 1.563 1.995 1.924 4.141 1.906 1.898 -4 704.15 701.49 1189.4 26.72 1.554 1.905 1.92.0 4.21.9 1.005 1.898 -4 704.15 701.49 1189.4 26.72 1.554 1.905 1.92.0 4.21.9 1.005 1.898 -4 704.15 701.49 1189.4 26.72 1.554 1.905 1.92.0 4.21.9 1.005 1.898 -4 704.15 704.44	1 ,										
-44	1 1									1	
-42 160.89 160.55 1317.0 6.996 1.401 0.777 139.6 406.2 0.828 1.991 -40 176.24 175.85 1317.0 6.996 1.405 0.785 142.4 407.3 0.840 1.976 -88 192.71 192.27 1310.5 7.614 1.409 0.792 145.3 408.3 0.852 1.970 -86 210.37 209.86 1304.0 8.275 1.414 0.800 148.1 409.3 0.864 1.965 -34 229.26 228.69 1297.3 8.980 1.419 0.809 150.9 410.2 0.875 1.960 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.887 1.965 -32 239.99 293.16 1277.1 11.39 1.436 0.835 159.5 413.1 0.911 1.946 -26 318.44 317.52 1270.2 12.29 1.442 0.844 162.4 414.0 0.921 1.944 -24 344.44 343.41 1263.3 13.26 1.488 0.854 165.3 414.9 0.934 1.936 -22 372.05 370.90 1266.3 14.28 14.55 0.864 165.3 414.9 0.934 1.936 -20 401.34 400.06 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.932 -18 432.36 430.95 1242.0 16.652 1.468 0.885 174.1 417.4 0.968 1.932 -14 449.91 448.20 1227.5 19.04 1.483 0.999 180.0 419.0 0.991 1.914 -14 499.91 448.20 1227.5 19.04 1.483 0.999 180.0 419.0 0.991 1.914 -10 575.26 573.20 1212.5 21.86 1.499 0.933 185.9 420.5 1.014 1.906 -8 616.03 613.78 1204.9 23.99 1.507 0.947 189.0 421.2 1.025 1.902 -2 751.64 748.75 1814.9 26.52 1.533 0.999 1.919 412.1 1.025 1.902 -2 8 616.03 613.78 124.9 1.485 1.552 1.025 1.902 1.533 0.999 1.914 41.24 1.025 1.902 -2 751.64 748.75 1814.9 3.245 1.552 1.025 1.912 1.533 1.919 1.914 1.914 1.946 1.925 1.9	1									1	
-40 176.24 175.85 1317.0 6.996 1.409 0.726 142.4 407.3 0.840 1.976 -38 192.71 192.27 1310.5 7.614 1.409 0.792 145.3 408.3 0.852 1.970 -36 210.37 299.86 1304.0 8.275 1.414 0.800 148.1 409.3 0.864 1.955 -34 229.26 228.69 1297.3 8.990 1.419 0.809 150.9 410.2 0.875 1.960 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.887 1.955 -30 271.01 270.28 1283.9 10.53 1.430 0.826 156.6 412.1 0.899 1.956 -28 293.99 293.16 1277.1 11.39 1.436 0.825 159.5 413.1 0.911 1.946 -28 318.44 317.52 1270.2 12.29 1.442 0.841 162.4 414.0 0.922 1.941 -24 344.44 343.41 1283.3 13.26 1.442 0.845 165.3 414.9 0.934 1.935 -20 401.34 400.06 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.932 -20 401.34 400.06 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.932 -16 455.20 463.64 1234.8 17.74 1.476 0.897 177.0 418.2 0.980 1.919 -12 536.58 534.69 1220.0 20.41 1.491 0.921 182.9 419.8 1.003 1.910 -10 575.26 573.20 1227.5 21.86 1.499 0.993 185.9 420.5 1.014 1.906 -8 616.03 613.78 1204.9 23.39 1.507 0.947 189.0 421.2 1.025 1.902 -6 658.97 656.52 1197.2 25.01 1.516 0.960 192.0 421.9 1.036 1.894 -2 751.64 748.76 1165.3 32.46 1.552 1.095 1.914 1.876 -2 853.87 850.52 1165.3 32.46 1.552 1.095 1.915 1.095 1.884 -2 751.64 748.76 1167.3 32.45 1.573 1.057 210.5 422.6 1.044 1.894 -2 751.64 748.76 1167.3 32.46 1.552 1.002 204.3 424.4 1.081 1.894 -2 751.64 748.76 1165.3 32.46 1.552 1.095 1.915 423.8 1.003 1.894 -2 751.64 748.76 1165.3 32.46 1.552 1.095 1.914 1.484 1.844 -2 10 1.895.5 1.855.1 1131.3 41.71 1.596 1.096 1.92.0 424.8 1.081 1.884 -2 8 1.565.5 1.565.5 1.5											
-38 192.71 192.27 1310.5 7.614 1.409 0.792 145.3 408.3 0.852 1.970 -36 210.37 209.86 1304.0 8.275 1.414 0.800 150.9 410.2 0.875 1.960 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.887 1.955 -39 271.01 270.28 1283.9 10.53 1.430 0.826 156.6 412.1 0.899 1.950 -28 293.99 293.16 1277.1 11.39 1.436 0.835 159.5 413.1 0.911 1.946 -26 318.44 317.52 127.20 12.29 1.442 0.844 162.4 414.0 0.922 1.941 -24 344.4 343.41 1263.3 13.26 1.448 0.854 165.3 414.9 0.934 1.936 -22 372.05 370.90 129.29 1.445 0.846 168.2 415.7 0.945 1.927 -23 372.05 370.90 129.25 1.537 1.461 0.875 171.1 416.6 0.957 1.927 -18 432.36 430.95 1242.0 16.52 1.468 0.886 174.1 417.4 0.968 1.932 -14 499.91 498.20 1227.5 19.04 1.483 0.999 180.0 419.0 0.991 1.914 -12 536.58 534.69 1220.0 20.41 1.491 0.921 182.9 419.8 10.03 1.910 -10 575.26 573.20 1212.5 21.86 1.499 0.933 185.9 420.5 1.014 1.966 -8 616.03 613.78 120.49 23.39 1.507 0.947 189.0 421.9 1.025 1.902 -8 616.03 613.78 1173.4 30.44 1.543 1.005 201.2 423.8 1.070 1.886 -2 751.64 748.76 1181.4 28.53 1.533 0.990 198.1 423.2 1.025 1.992 -2 751.64 748.76 1181.4 28.53 1.533 0.990 198.1 423.2 1.025 1.990 -2 853.87 850.52 1197.2 25.01 1.560 0.960 192.0 421.9 1.036 1.888 -2 2 853.87 850.52 1197.2 25.01 1.560 0.960 1.92.0 421.9 1.036 1.888 -2 2 853.87 850.52 1197.2 550.1 1.500 0.960 1.92.0 421.9 1.036 1.888 -2 2 853.87 850.52 1197.2 550.1 1.560 0.960 1.92.0 421.9 1.036 1.888 -2 2 853.87 850.52 1197.2 550.1 1.560 0.960 1.92.0 421.9 1.036 1.888 -2 2 853.87 850.52 1197.2 1.965 1.665 1.665 1.039 1.920 421.9 1.										1	
-36											
-34 229.26 228.69 1297.3 8.980 1.419 0.809 150.9 410.2 0.875 1.960 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.889 1.950 -32 249.46 248.81 1290.6 9.732 1.424 0.817 153.8 411.2 0.889 1.950 -28 293.99 293.16 1277.1 11.39 1.436 0.835 159.5 413.1 0.991 1.946 -26 318.44 317.52 1270.2 12.29 1.442 0.844 162.4 414.0 0.922 1.941 -24 344.44 343.41 1263.3 13.26 1.448 0.854 165.3 41.9 0.934 1.936 -22 372.05 370.90 1266.3 14.28 1.485 0.864 168.2 415.7 0.945 1.932 -22 410.34 400.66 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.927 -18 432.36 430.95 1242.0 16.52 1.468 0.886 174.1 417.4 0.968 1.932 -16 465.20 463.64 1234.8 17.74 1.476 0.897 177.0 418.2 0.968 1.939 -14 499.91 498.20 1227.5 19.04 1.483 0.909 180.0 419.0 0.991 1.914 -12 536.58 534.69 1220.0 20.41 1.491 0.921 182.9 419.8 1.003 1.910 -10 575.26 573.20 1212.5 21.86 1.499 0.933 185.9 420.5 1.014 1.966 -8 616.03 613.78 1204.9 23.39 1.507 0.947 189.0 421.2 1.025 1.904 -2 751.64 748.7 6118.14 28.53 1.533 0.990 189.1 423.2 1.025 1.904 -2 751.64 748.7 6118.14 28.53 3.533 0.990 189.1 423.2 1.026 1.898 -2 751.64 748.7 6118.14 28.53 3.246 1.553 1.057 201.2 423.8 1.070 1.886 4.986.5 10.05.5 10.05.5 1.054 1.095 1.09											
-32											
-30											
-28	-32	249.46	248.81	1290.6	9.732	1.424	0.817	153.8	411.2	0.887	1.955
-26		271.01	270.28			1.430			412.1		
-26	-28	293.99	293.16			1.436	0.835	159.5		0.911	
-22 372.05 370.90 1256.3 14.28 14.55 0.864 168.2 415.7 0.945 1.922 1.804 400.06 1249.2 15.37 1.461 0.875 171.1 416.6 0.957 1.927 1.8461 0.886 174.1 417.4 0.968 1.923 1.646 0.886 174.1 417.4 0.968 1.923 1.646 0.886 174.1 417.4 0.968 1.923 1.646 0.887 177.0 418.2 0.980 1.919 1.914 499.91 499.20 1227.5 19.04 1.483 0.999 180.0 419.0 0.991 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915 1.914 1.915		318.44		1270.2					414.0		1.941
-20	-24	344.44	343.41	1263.3	13.26	1.448	0.854	165.3	414.9	0.934	1.936
-20	-22	372.05	370.90	1256.3	14.28	1.455	0.864	168.2	415.7	0.945	1.932
-18	-20	401.34	400.06				0.875		416.6		1.927
-14	-18	432.36	430.95	1242.0	16.52	1.468		174.1	417.4	0.968	
-12 536.58 534.69 1220.0 20.41 1.491 0.921 182.9 419.8 1.003 1.910 -10 575.26 573.20 1212.5 21.86 1.499 0.933 185.9 420.5 1.014 1.906 -8 616.03 613.78 1204.9 23.39 1.507 0.947 189.0 421.2 1.025 1.902 -6 658.97 656.52 1197.2 25.01 1.516 0.960 192.0 421.9 1.036 1.898 -4 704.15 701.49 1189.4 26.72 1.524 0.975 195.0 422.6 1.048 1.894 -2 751.64 748.76 1181.4 28.53 1.533 0.990 198.1 423.2 1.059 1.890 0 801.52 798.41 1173.4 30.44 1.543 1.005 201.2 423.8 1.070 1.886 2 853.87 850.52 1165.3 32.46 1.552 1.022 204.3 424.4 1.081 1.882 4 908.77 905.16 1157.0 34.59 1.563 1.039 207.4 424.9 1.092 1.878 6 966.29 962.42 1148.6 36.83 1.573 1.057 210.5 425.5 1.103 1.874 8 1026.5 1022.4 1140.0 39.21 1.584 1.076 213.7 425.9 1.114 1.870 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.168 1.852 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.841 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 25 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.224 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.224 1.834 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.855 1.514 260.5 428.6 1.224 1.834 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.6 1.224 1.339 31 1891.9 1884.2 10	-16	465.20	463.64	1234.8	17.74	1.476	0.897	177.0	418.2	0.980	1.919
-12 536.58 534.69 1220.0 20.41 1.491 0.921 182.9 419.8 1.003 1.910 -10 575.26 573.20 1212.5 21.86 1.499 0.933 185.9 420.5 1.014 1.906 -8 616.03 613.78 1204.9 23.39 1.507 0.947 189.0 421.2 1.025 1.902 -6 658.97 656.52 1197.2 25.01 1.516 0.960 192.0 421.9 1.036 1.898 -4 704.15 701.49 1189.4 26.72 1.524 0.975 195.0 422.6 1.048 1.894 -2 751.64 748.76 1181.4 28.53 1.533 0.990 198.1 423.2 1.059 1.890 0 801.52 798.41 1173.4 30.44 1.543 1.005 201.2 423.8 1.070 1.886 2 853.87 850.52 1165.3 32.46 1.552 1.022 204.3 424.4 1.081 1.882 4 908.77 905.16 1157.0 34.59 1.563 1.039 207.4 424.9 1.092 1.878 6 966.29 962.42 1148.6 36.83 1.573 1.057 210.5 425.5 1.103 1.874 8 1026.5 1022.4 1140.0 39.21 1.584 1.076 213.7 425.9 1.114 1.870 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.168 1.852 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.841 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 25 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.224 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.224 1.834 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.855 1.514 260.5 428.6 1.224 1.834 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.6 1.224 1.339 31 1891.9 1884.2 10	-14	499.91	498.20	1227.5	19.04	1.483		180.0	419.0	0.991	1.914
-8	-12	536.58	534.69	1220.0	20.41	1.491	0.921	182.9	419.8	1.003	1.910
-8	-10	575.26	573.20	1212.5	21.86	1 400	0 033	185.0	420.5	1.014	1 906
-6										L .	
-4											
-2											
0 801.52 798.41 1173.4 30.44 1.543 1.005 201.2 423.8 1.070 1.886 2 853.87 850.52 1165.3 32.46 1.552 1.022 204.3 424.4 1.081 1.882 4 908.77 905.16 1157.0 34.59 1.563 1.039 207.4 424.9 1.092 1.878 6 966.29 962.42 1148.6 36.83 1.573 1.057 210.5 425.5 1.103 1.874 8 1026.5 1022.4 1140.0 39.21 1.584 1.076 213.7 425.9 1.114 1.870 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.862 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.147 1.259 1.154 1.147 1.259 1.147 1.200.0 426											
2 853.87 850.52 1165.3 32.46 1.552 1.022 204.3 424.4 1.081 1.882 4 908.77 905.16 1157.0 34.59 1.563 1.039 207.4 424.9 1.092 1.878 6 966.29 962.42 1140.0 39.21 1.584 1.076 213.7 425.9 1.114 1.870 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 247.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.99 1.635 1.635 1.63 226.5 427.5 1.158 1.852 18 1371.2 1365.5 1095.1 53.20 <td>້</td> <td></td> <td></td> <td>1</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	້			1							
4 998.77 905.16 1157.0 34.59 1.563 1.039 207.4 424.9 1.092 1.874 8 1026.5 1022.4 1140.0 39.21 1.584 1.076 213.7 425.5 1.103 1.874 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.99 1.635 1.163 226.5 427.5 1.158 1.857 18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.3 1085.6 56.48 1.666<				1		1				1	
6 966.29 962.42 1148.6 36.83 1.573 1.057 210.5 425.5 1.103 1.874 8 1026.5 1022.4 1140.0 39.21 1.584 1.076 213.7 425.9 1.114 1.870 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.5 1.158 1.855 16 1296.2 1290.8 1104.4 50.09 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 21 1530.9 1624.6 1075.9 59.96 1.831<											
8 1026.5 1022.4 1140.0 39.21 1.584 1.076 213.7 425.9 1.114 1.870 10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.158 1.855 18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 22 1530.9 1524.6 1075.9 59.96 1.683											
10 1089.5 1085.1 1131.3 41.71 1.596 1.096 216.8 426.4 1.125 1.866 12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.158 1.855 18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.660 1.215 233.0 428.1 1.180 1.841 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1055.9 67.51 1.72										1	
12 1155.4 1150.7 1122.5 44.35 1.608 1.117 220.0 426.8 1.136 1.862 14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.158 1.855 18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 25 1796.2 178.9 1.721 1.306 243.1<											
14 1224.3 1219.2 1113.5 47.14 1.621 1.139 223.2 427.2 1.147 1.859 16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.158 1.855 18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.74											
16 1296.2 1290.8 1104.4 50.09 1.635 1.163 226.5 427.5 1.158 1.855 18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.76				1122.5							
18 1371.2 1365.5 1095.1 53.20 1.650 1.188 229.7 427.8 1.169 1.851 20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.79											
20 1449.4 1443.4 1085.6 56.48 1.666 1.215 233.0 428.1 1.180 1.847 22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.82	1			1							
22 1530.9 1524.6 1075.9 59.96 1.683 1.243 236.4 428.3 1.191 1.843 24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.85				1							
24 1615.8 1609.2 1066.0 63.63 1.701 1.273 239.7 428.4 1.202 1.839 26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891		1									
26 1704.2 1697.2 1055.9 67.51 1.721 1.306 243.1 428.6 1.214 1.834 28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932<											
28 1796.2 1788.9 1045.5 71.62 1.743 1.341 246.5 428.6 1.225 1.830 30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.258 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 </td <td></td>											
30 1891.9 1884.2 1034.9 75.97 1.767 1.379 249.9 428.6 1.236 1.826 32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.798 44 2672.2 2662.4 951.4 115.2 2.033 <td></td>											
32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.793 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 <td>28</td> <td>1796.2</td> <td>1788.9</td> <td>1045.5</td> <td>71.62</td> <td>1.743</td> <td>1.341</td> <td>246.5</td> <td>428.6</td> <td>1.225</td> <td>1.830</td>	28	1796.2	1788.9	1045.5	71.62	1.743	1.341	246.5	428.6	1.225	1.830
32 1991.3 1983.2 1024.1 80.58 1.793 1.420 253.4 428.6 1.247 1.822 34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.793 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 <td>30</td> <td>1891.9</td> <td>1884.2</td> <td>1034.9</td> <td>75.97</td> <td>1.767</td> <td>1.379</td> <td>249.9</td> <td>428.6</td> <td>1.236</td> <td>1.826</td>	30	1891.9	1884.2	1034.9	75.97	1.767	1.379	249.9	428.6	1.236	1.826
34 2094.5 2086.2 1012.9 85.48 1.822 1.465 256.9 428.4 1.258 1.817 36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.798 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.798 46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168											
36 2201.7 2193.1 1001.4 90.68 1.855 1.514 260.5 428.3 1.269 1.813 38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.798 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256											
38 2313.0 2304.0 989.5 96.22 1.891 1.569 264.1 428.0 1.281 1.808 40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.798 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256 2.069 287.3 424.5 1.351 1.776 52 3214.0 3203.6 892.2 147.7 2.362											1.813
40 2428.4 2419.2 977.3 102.1 1.932 1.629 267.8 427.7 1.292 1.803 42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.798 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256 2.069 287.3 424.5 1.351 1.776 52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493											
42 2548.1 2538.6 964.6 108.4 1.979 1.696 271.5 427.2 1.303 1.798 44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256 2.069 287.3 424.5 1.351 1.776 52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661		i e									
44 2672.2 2662.4 951.4 115.2 2.033 1.771 275.3 426.7 1.315 1.793 46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256 2.069 287.3 424.5 1.351 1.776 52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.749 58 3671.3 3661.2 836.9 180.4 2.883											
46 2800.7 2790.7 937.7 122.4 2.095 1.857 279.2 426.1 1.327 1.788 48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256 2.069 287.3 424.5 1.351 1.776 52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.749 58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.749 60 3834.1 3824.2 814.9 193.7 3.191											
48 2933.7 2923.6 923.3 130.2 2.168 1.955 283.2 425.4 1.339 1.782 50 3071.5 3061.2 908.2 138.6 2.256 2.069 287.3 424.5 1.351 1.776 52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.757 58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.741 60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650		l.									
52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.757 58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.749 60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732											
52 3214.0 3203.6 892.2 147.7 2.362 2.203 291.5 423.5 1.363 1.770 54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.757 58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.749 60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732	50	3071.5	3061.2	908.2	138.6	2 256	2 060	287 3	494 5	1 351	1 776
54 3361.4 3351.0 875.1 157.6 2.493 2.363 295.8 422.4 1.376 1.764 56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.757 58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.749 60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732											
56 3513.8 3503.5 856.8 168.4 2.661 2.557 300.3 421.0 1.389 1.757 58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.749 60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732											
58 3671.3 3661.2 836.9 180.4 2.883 2.799 305.0 419.4 1.403 1.749 60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732											
60 3834.1 3824.2 814.9 193.7 3.191 3.106 310.0 417.6 1.417 1.741 62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732											
62 4002.1 3992.7 790.1 208.6 3.650 3.511 315.3 415.5 1.433 1.732											
				I .							
								321.2			1.722

1.2 Refrigerant Cylinders

- Cylinder specifications
- The cylinder is painted refrigerant color (pink).
- The cylinder valve is equipped with a siphon tube.



Refrigerant can be charged in liquid state with cylinder in upright position.

Caution: Do not lay cylinder on its side during charging, since it cause refrigerant in gas state to enter the system.

Handling of cylinders

(1) Laws and regulations

R-410A is liquefied gas, and the High-Pressure Gas Safety Law must be observed in handling them. Before using, refer to the High-Pressure Gas Safety Law.

The Law stipulates standards and regulations that must be followed to prevent accidents with high-pressure gases. Be sure to follow the regulations.

(2) Handing of vessels

Since R-410A is high-pressure gas, it is contained in high-pressure vessels.

Although those vessels are durable and strong, careless handling can cause damage that can lead to unexpected accidents. Do not drop vessels, let them fall, apply impact or roll them on the ground.

(3) Storage

Although R-410A is not flammable, it must be stored in a well-ventilated, cool, and dark place in the same way as any other high-pressure gases.

It should also be noted that high-pressure vessels are equipped with safety devices that releases gas when the ambient temperature reaches more than a certain level (fusible plug melts) and when the pressure exceeds a certain level (spring-type safety valve operates).

1.3 Service Tools

R-410A is used under higher working pressure, compared to previous refrigerants (R-22,R-407C). Furthermore, the refrigerating machine oil has been changed from Suniso oil to Ether oil, and if oil mixing is occurred, sludge results in the refrigerants and causes other problems. Therefore, gauge manifolds and charge hoses that are used with a previous refrigerant (R-22,R-407C) can not be used for products that use new refrigerants. Be sure to use dedicated tools and devices.

■ Tool compatibility

	Compatibility			
Tool	HFC		HCFC	Reasons for change
	R-410A	R-407C	R-22	
Gauge manifold Charge hose	×			 Do not use the same tools for R-22 and R-410A. Thread specification differs for R-410A and R-407C.
Charging cylinder	>	<	0	Weighting instrument used for HFCs.
Gas detector)	×	The same tool can be used for HFCs.
Vacuum pump (pump with reverse flow preventive function)	0			To use existing pump for HFCs, vacuum pump adaptor must be installed.
Weighting instrument	0			
Charge mouthpiece	×			 Seal material is different between R-22 and HFCs. Thread specification is different between R-410A and others.
Flaring tool (Clutch type)	0			• For R-410A, flare gauge is necessary.
Torque wrench	0			Torque-up for 1/2 and 5/8
Pipe cutter		0		
Pipe expander	pander O			
Pipe bender	0			
Pipe assembling oil	×			Due to refrigerating machine oil change. (No Suniso oil can be used.)
Refrigerant recovery device	Check yo	our recover	y device.	
Refrigerant piping	See the chart below.		elow.	• Only φ19.1 is changed to 1/2H material while the previous material is "O".

As for the charge mouthpiece and packing, 1/2UNF20 is necessary for mouthpiece size of charge hose.

■ Copper tube material and thickness

	,	√e-up	Ve-upII		
	R-407C		R-410A		
Pipe size	Material	Thickness	Material	Thickness	
		t (mm)	Materiai	t (mm)	
φ6.4	0	0.8	0	0.8	
φ9.5	0	0.8	0	0.8	
φ12.7	0	0.8	0	0.8	
φ15.9	0	1.0	0	1.0	
φ19.1	0	1.0	1/2H	1.0	
φ22.2	1/2H	1.0	1/2H	1.0	
φ25.4	1/2H	1.0	1/2H	1.0	
φ28.6	1/2H	1.0	1/2H	1.0	
φ31.8	1/2H	1.2	1/2H	1.1	
ф38.1	1/2H	1.4	1/2H	1.4	
φ44.5	1/2H	1.6	1/2H	1.6	

* O: Soft (Annealed) H: Hard (Drawn)

1. Flaring tool



- Specifications
- · Dimension A

Unit:mm

			O111111111
Nominal size	Tube O.D.	A	+0 -0.4
Norminal Size	Do	Class-2 (R-410A)	Class-1 (Conventional)
1/4	6.35	9.1	9.0
3/8	9.52	13.2	13.0
1/2	12.70	16.6	16.2
5/8	15.88	19.7	19.4
3/4	19.05	24.0	23.3

- Differences
- · Change of dimension A



For class-1: R-407C For class-2: R-410A

Conventional flaring tools can be used when the work process is changed. (change of work process)

Previously, a pipe extension margin of 0 to 0.5mm was provided for flaring. For R-410A air conditioners, perform pipe flaring with a pipe extension margin of $\underline{\text{1.0 to 1.5mm}}$. (For clutch type only)

Conventional tool with pipe extension margin adjustment can be used.

2. Torque wrench



Specifications

Dimension B


Unit:mm

Nominal size	Class-1	Class-2	Previous
1/2	24	26	24
5/8	27	29	27

No change in tightening torque No change in pipes of other sizes


■ Differences

 Change of dimension B Only 1/2", 5/8" are extended



For class-1: R-407C For class-2: R-410A

3. Vacuum pump with check valve



- Specifications
- Discharge speed 50 l/min (50Hz) 60 l/min (60Hz)
- Suction port UNF7/16-20(1/4 Flare) UNF1/2-20(5/16 Flare) with adapter
- Maximum degree of vacuum
 Select a vacuum pump which is able to keep the vacuum degree of the system in excess of -100.7 kPa (5 torr - 755 mmHg).

■ Differences

- · Equipped with function to prevent reverse oil flow
- · Previous vacuum pump can be used by installing adapter.

4. Leak tester



- Specifications
- Hydrogen detecting type, etc.
- Applicable refrigerants
 R-410A, R-407C, R-404A, R-507A, R-134a, etc.

Differences

 Previous testers detected chlorine. Since HFCs do not contain chlorine, new tester detects hydrogen.

5. Refrigerant oil (Air compal)



- Specifications
- Contains synthetic oil, therefore it can be used for piping work of every refrigerant cycle.
- · Offers high rust resistance and stability over long period of time.

■ Differences

· Can be used for R-410A and R-22 units.


6. Gauge manifold for R-410A



- Specifications
- · High pressure gauge
 - 0.1 to 5.3 MPa (-76 cmHg to 53 kg/cm²)
- · Low pressure gauge
 - 0.1 to 3.8 MPa (-76 cmHg to 38 kg/cm²)
- 1/4" \rightarrow 5/16" (2min \rightarrow 2.5min)
- · No oil is used in pressure test of gauges.
 - → For prevention of contamination

- Temperature scale indicates the relationship between pressure and temperature in gas saturated state.
- Differences
- · Change in pressure
- · Change in service port diameter

7. Charge hose for R-410A



- Specifications
- Working pressure 5.08 MPa (51.8 kg/cm²)
- Rupture pressure 25.4 MPa (259 kg/cm²)
- Available with and without hand-operate valve that prevents refrigerant from outflow.
- Differences
- · Pressure proof hose
- · Change in service port diameter
- · Use of nylon coated material for HFC resistance

8. Charging cylinder



- Specifications
- Use weigher for refrigerant charge listed below to charge directly from refrigerant cylinder.
- Differences
- The cylinder can not be used for mixed refrigerant since mixing ratio is changed during charging.

When R-410A is charged in liquid state using charging cylinder, foaming phenomenon is generated inside charging cylinder.

9. Weigher for refrigerant charge



- Specifications
- High accuracy TA101A (for 10-kg cylinder) = ± 2g TA101B (for 20-kg cylinder) = ± 5g
- Equipped with pressure-resistant sight glass to check liquid refrigerant charging.
- A manifold with separate ports for HFCs and previous refrigerants is equipped as standard accessories.
- Differences
- · Measurement is based on weight to prevent change of mixing ratio during charging.

10. Charge mouthpiece



- Specifications
- For R-410A, 1/4" \rightarrow 5/16" (2min \rightarrow 2.5min)
- · Material is changed from CR to H-NBR.
- Differences
- Change of thread specification on hose connection side (For the R-410A use)
- Change of sealer material for the HFCs use.

Index

A		E9	246
A0	220	Electronic Expansion Valve PI Control	107
A1	221	Emergency Operation	
A3		Error of External Protection Device	220
A6			
A7	225	F	
A9	227	F3	
Abnormal Discharge Pipe Temperature	248	F6	249
Abnormal Outdoor Fan Motor Signal		Fan Motor (M1F) Lock, Overload	224
About Refrigerant R-410A		Faulty Field Setting after Replacing Main PC	Board
Actuation of High Pressure Switch		or Faulty Combination of PC Board	274
Actuation of Low Pressure Sensor		Field Setting	161
Address Duplication of Centralized Controller		Field Setting from Outdoor Unit	174
Address Duplication, Improper Setting		List of Field Setting Items	174
AF		Setting by pushbutton switches	178
AJ		Field Setting from Remote Controller	161
Applicable range of Field setting		Filter Sign Setting	166
Auto Restart after Power Failure Reset		Freeze Prevention	
		Functional Parts Layout	69
В		RXYQ10P, 12P	
Basic Control	94	RXYQ14P, 16P, 18P	
240.0 00.1110		RXYQ5P	
C		RXYQ8P	70
C4	231		
C5		Н	
C9		H7	250
Centralized Control Group No. Setting		H9	251
Check No. 2		Heating Operation Prohibition	128
Check Operation not executed		High Pressure Protection Control	
CJ		· ·	
Compressor Motor Overcurrent/Lock		I	
Compressor PI Control		Improper Combination of Indoor and Outdoor	r Units,
Contents of Control Modes		Indoor Units and Remote Controller	
Cool / Heat Mode Switching		Improper Combination of Optional Controllers	s for
Current Sensor Malfunction		Centralized Control	
Carron Consor Mananotton	202	Injection Control (only for RXYQ5P)	
D		Inverter Compressor Abnormal	
Defrosting Operation	113	Inverter Compressor Motor Lock	
Demand Operation		Inverter Current Abnormal	
Detailed Explanation of Setting Modes		Inverter Over-Ripple Protection	
Discharge Pipe Protection Control		Inverter Protection Control	
Display "Under Centralized Control" Blinks		Inverter Start up Error	266
(Repeats Double Blink)	310	•	
Display "Under Centralized Control" Blinks		J	
(Repeats Single Blink)	307	J2	252
Drain Level above Limit		J3	
Drain Pump Control		J5	
Diam'r amp Control	120	J6	
E		J7	
= E1	235	J9	
E3		JA	
E4		JC	
E5			00
E6		L	
E7		_ L4	260
L/	240	_ ·	200

Index

L5262	Malfunction of Transmission Between Optional
L8264	Controllers for Centralized Control 298
L9266	Malfunction of Transmission Between
LC268	Outdoor Units284
List of Electrical and Functional Parts348	Malfunction of Transmission Between Remote
Indoor Unit351	Controller and Indoor Unit 283
Outdoor Unit348	MC 302
Louver Control for Preventing Ceiling Dirt131	Method of Checking The Inverter's Power Transistors
Low Pressure Drop Due to Refrigerant Shortage or	and Diode Modules368
Electronic Expansion Valve Failure275	
Low Pressure Protection Control119	0
	Oil Return Operation11
M	Operation Lamp Blinks305
M1297	Operation Mode93
M8298	Operation When Power is Turned On 159
MA300	Option List
Malfunction code indication by	Other Control
outdoor unit PC board216	Outdoor Air Processing Unit-Field Setting 169
Malfunction of Capacity Determination Device230	Outdoor Unit Fan Control in
Malfunction of Discharge Pipe Thermistor	Cooling Operation108
(R3, R31~33T)253	Outdoor Unit PC Board Layout
Malfunction of Drain Level Control System	Outdoor Unit Rotation
(S1L)222	Outdoor Unit Thermistors for Discharge Pipe 366
Malfunction of High Pressure Sensor258	P
Malfunction of Inverter Radiating Fin Temperature	-
Rise	P1
Malfunction of Inverter Radiating Fin Temperature Rise Sensor272	PC Board Defect
Malfunction of Liquid Pipe Thermistor (R6T)256	Piping Installation Point36
Malfunction of Low Pressure Sensor259	The Example of A Wrong Pattern362
Malfunction of Moving Part of Electronic Expansion	PJ
Valve (Y1E)227	Power Supply Insufficient or
Malfunction of Moving Part of Electronic Expansion	Instantaneous Failure277
Valve (Y1E, Y2E)246	Precautions for New Refrigerant (R-410A) 372
Malfunction of Outdoor Unit Fan Motor243	Pressure Sensor
Malfunction of Subcooling Heat Exchanger Gas Pipe	Procedure and Outline145
Thermistor (R5T)257	Protection Control118
Malfunction of Swing Flap Motor (M1S)225	Pump-down Residual Operation114
Malfunction of System, Refrigerant System Address	'
Undefined295	R
Malfunction of Thermistor (R1T) for Suction Air233	Refrigerant Circuit 60
Malfunction of Thermistor (R2T) for	FXMQ125MFV1~250MFV168
Heat Exchanger231	RXYQ10P, 12P64
Malfunction of Thermistor (R2T), (R7T)	RXYQ14P, 16P, 18P66
for Suction Pipe254	RXYQ5P60
Malfunction of Thermistor (R3T) for Gas Pipes232	RXYQ8P62
Malfunction of Thermistor (R4T) for Outdoor Unit Heat	Refrigerant Cylinders
Exchanger255	Refrigerant Flow for Each Operation Mode 74
Malfunction of Thermostat Sensor in Remote	RXYQ10P, 12P82
Controller234	RXYQ14P, 16P, 18P86
Malfunction of Transmission Between Centralized	RXYQ5P74
Controller and Indoor Unit291	RXYQ8P
Malfunction of Transmission Between Indoor and	Refrigerant Overcharged
Outdoor Units in the Same System287	Restart Standby
Malfunction of Transmission Between Indoor Units281	Reverse Phase, Open Phase276
Malfunction of Transmission Between Inverter and	S
Control PC Board268	Selection of Pipe Size, Joints and Header 363
Malfunction of Transmission Between Main and Sub	Service Tools
Remote Controllers286	Setting by pushbutton switches
	Setting Contents and Code No 164

ii Index

Setting of Low Noise Operation and Demand	
Operation	
Special Control	
Specifications	
Indoor Units	
Outdoor Units	
Standby	
Startup Control	
STD Compressor Overload Protection	
Step Control of Outdoor Unit Fans	
Stopping Operation	
Symptom-based Troubleshooting	201
System is not Set yet	294
т	
Test Operation	144
Procedure and Outline	
The Example of A Wrong Pattern	
Thermistor Resistance /	
Temperature Characteristics	365
Thermostat Sensor in Remote Controller	
Troubleshooting	
(OP: Central Remote Controller)	297
Troubleshooting	
(OP: Unified ON/OFF Controller)	305
(G G	
U	
U0	275
U1	276
U2	277
U3	
U4	
U5	
U7	
U8	
U9	
UA	
UC	
UE	
UF	
III	

Index

iv Index

Drawings & Flow Charts

A	Field Setting from Outdoor Unit	174
Abnormal Discharge Pipe Temperature248	Mode changing procedure	178
Abnormal Outdoor Fan Motor Signal250	Setting by dip switches	176
Actuation of High Pressure Switch236	Freeze Prevention	136
Actuation of Low Pressure Sensor238	Functional Parts Layout	69
Address Duplication of Centralized Controller290		
Address Duplication, Improper Setting302	I	
	Improper Combination of Indoor and Outdoor Units	s,
C	Indoor Units and Remote Controller	288
Centralized Control Group No. Setting170	Improper Combination of Optional Controllers for	
BRC1A Type170	Centralized Control	300
BRC4C Type171	Inverter Compressor Abnormal2	262
BRC7C Type171	Inverter Compressor Motor Lock	240
BRC7E Type171	Inverter Current Abnormal2	264
Group No. Setting Example171	Inverter Over-Ripple Protection2	271
Check No. 1311	Inverter Start up Error2	
Check No. 2311	·	
Check Operation not executed280	L	
Compressor Motor Overcurrent/Lock242	Louver Control for Preventing Ceiling Dirt	131
Contents of Control Modes172	Low Pressure Drop Due to Refrigerant Shortage o	
How to Select Operation Mode173	Electronic Expansion Valve Failure	
Control of Outdoor Air Processing Unit (Unique	•	
Control for Outdoor Air Processing Unit)138	M	
Discharge Air Temperature Control139	Malfunction of Capacity Determination Device 2	230
Selection of Operation Mode (by suction air	Malfunction of Discharge Pipe Thermistor	
thermostat)138	(R3, R31~33T)	253
Current Sensor Malfunction252	Malfunction of Drain Level Control System	
Current Consor Manufolion	(S1L)2	222
D	Malfunction of High Pressure Sensor	
Display "Under Centralized Control" Blinks	Malfunction of Inverter Radiating Fin Temperature	
(Repeats Double Blink)310	Rise2	
Display "Under Centralized Control" Blinks	Malfunction of Inverter Radiating Fin Temperature	
(Repeats Single Blink)307	Rise Sensor2	
Display of sensor and address data211	Malfunction of Liquid Pipe Thermistor (R6T) 2	
Drain Level above Limit229	Malfunction of Low Pressure Sensor2	
Drain Pump Control	Malfunction of Moving Part of Electronic Expansion	
When the Float Switch is Tripped and "AF" is	Valve (Y1E)2	
Displayed on the	Malfunction of Moving Part of Electronic Expansion	
Remote Controller130	Valve (Y1E, Y2E)	
When the Float Switch is Tripped During Heating	Malfunction of Outdoor Unit Fan Motor	
Operation130	Malfunction of Subcooling Heat Exchanger Gas Pi	
When the Float Switch is Tripped while the	Thermistor (R5T)	
Cooling Thermostat is OFF129	Malfunction of Swing Flap Motor (M1S)	
When the Float Switch is Tripped While the	Malfunction of System, Refrigerant System Address	
Cooling Thermostat is ON129	Undefined2	
Cooling Monitodat is ON125	Malfunction of Thermistor (R1T)	
E	for Outdoor Air	251
Error of External Protection Device220	Malfunction of Thermistor (R1T)	-
Example of connection (R-410A Type)363	for Suction Air2	233
Example of confidential (11-410A Type)	Malfunction of Thermistor (R2T)	
F	for Heat Exchanger2	231
Fan Motor (M1F) Lock, Overload224	Malfunction of Thermistor (R2T), (R7T)	
Faulty Field Setting after Replacing Main PC Board	for Suction Pipe2	254
or Faulty Combination of PC Board274	Malfunction of Thermistor (R3T)	
of Faulty Combination of FC Doard274	for Gas Pipes2	232

Drawings & Flow Charts

Malfunction of Thermistor (R4T)
for Outdoor Unit Heat Exchanger255 Malfunction of Thermostat Sensor in Remote
Controller234
Malfunction of Transmission Between Centralized
Controller and Indoor Unit291
Malfunction of Transmission Between Indoor and
Outdoor Units in the Same System287 Malfunction of Transmission Between
Indoor Units281
Malfunction of Transmission Between Inverter and
Control PC Board268
Malfunction of Transmission Between Main and
Sub Remote Controllers286 Malfunction of Transmission Between Optional
Controllers for Centralized Control298
Malfunction of Transmission Between
Outdoor Units284
Malfunction of Transmission Between Remote
Controller and Indoor Unit
Method of Checking The Inverter's Power Transistors and Diode Modules368
and blode Modules
0
Operation Lamp Blinks305
Operation of The Remote Controller's Inspection /
Test Operation Button209 Outdoor Unit PC Board Layout160
Outdoor Offit PC Board Layout160
P
PC Board Defect221, 235, 297
Piping Diagrams316
Indoor Unit
Outdoor Unit
The Example of A Wrong Pattern362
Power Supply Insufficient or
Instantaneous Failure277
Pressure Sensor367
R
Refrigerant Flow for Each Operation Mode74
Refrigerant Overcharged249
Remote Controller Self-Diagnosis Function212
Remote Controller Service Mode210
Reverse Phase, Open Phase276
RXYQ10P, 12P71
RXYQ14P, 16P, 18P73
RXYQ5P69
RXYQ8P70
S
Self-diagnosis by Wired Remote Controller205
Self-diagnosis by Wired Hemote Controller205
Setting of Low Noise Operation and Demand
Setting of Low Noise Operation and Demand Operation191
Operation191 Image of operation in the case of A 192, 194
Operation191 Image of operation in the case of A192, 194 Image of operation in
Operation191 Image of operation in the case of A 192, 194

Simplified Remote Controller	
BRC2A51, BRC2C51	163
System is not Set yet	294
т	
Test Operation	144
Thermostat Sensor in Remote Controller	
Cooling	132
Heating	
Torque wrench	377
Troubleshooting	
(OP: Central Remote Controller)	297
Troubleshooting	005
(OP: Unified ON/OFF Controller)	
Troubleshooting by Remote Controller	204
W	
Weigher for refrigerant charge	380
Wired Remote Controller	
Wireless Remote Controller - Indoor Unit	162
BRC4C type	162
BRC7C type	
BRC7E type	
Wiring Diagrams for Reference	
Field Wiring	
Indoor Unit	
Outdoor Unit	324

vi Drawings & Flow Charts



- Daikin Industries, Ltd.'s products are manufactured for export to numerous countries throughout the world. Daikin Industries, Ltd. does not have control over which products are exported to and used in a particular country. Prior to purchase, please therefore confirm with your local authorised importer, distributor and/or retailer whether this product conforms to the applicable standards, and is suitable for use, in the region where the product will be used. This statement does not purport to exclude, restrict or modify the application of any local legislation.
- Ask a qualified installer or contractor to install this product. Do not try to install the product yourself. Improper installation can result in water or refrigerant leakage, electrical shock, fire or explosion.
- Use only those parts and accessories supplied or specified by Daikin. Ask a qualified installer or contractor to install those parts and accessories. Use of unauthorised parts and accessories or improper installation of parts and accessories can result in water or refrigerant leakage, electrical shock, fire or explosion.
- Read the User's Manual carefully before using this product. The User's Manual provides important safety instructions and warnings. Be sure to follow these instructions and warnings.

If you have any enquiries, please contact your local importer, distributor and/or retailer.

Cautions on product corrosion

- 1. Air conditioners should not be installed in areas where corrosive gases, such as acid gas or alkaline gas, are produced.
- 2. If the outdoor unit is to be installed close to the sea shore, direct exposure to the sea breeze should be avoided. If you need to install the outdoor unit close to the sea shore, contact your local distributor.





About ISO 9001

ISO 9001 is a plant certification system defined by the International Organization for Standardization (ISO) relating to quality assurance. ISO 9001 certification covers quality assurance aspects related to the "design, development, manufacture, installation, and supplementary service" of products manufactured at the plant.



About ISO 14001 -

ISO 14001 is the standard defined by the International Organization for Standardization (ISO) relating to environmental management systems. Our group has been acknowledged by an internationally accredited compliance organisation as having an appropriate programme of environmental protection procedures and activities to meet the requirements of ISO 14001.

Dealer

DAIKIN INDUSTRIES, LTD.

Head Office:

Umeda Center Bldg., 2-4-12, Nakazaki-Nishi, Kita-ku, Osaka, 530-8323 Japan

Tokyo Office:

JR Shinagawa East Bldg., 2-18-1, Konan, Minato-ku, Tokyo, 108-0075 Japan

http://www.daikin.com/global_ac/

©All rights reserved